

SERIES 400
PROFESSIONAL AUDIO RECORDER

INSTRUCTION MANUAL


MINNESOTA MINING AND MANUFACTURING COMPANY
300 SOUTH LEWIS ROAD, CAMARILLO, CALIFORNIA 93010



3M Brand

Professional Audio Recorder

Series 400



INSTRUCTION MANUAL

MINNESOTA MINING AND MANUFACTURING COMPANY
300 SOUTH LEWIS ROAD • CAMARILLO, CALIFORNIA 93010

M23 RRM 2-69

FOR SALES INFORMATION

Minnesota Mining and Manufacturing Company
3M Center
St. Paul, Minnesota 55101
(612) 733-1625

FOR PARTS AND SERVICE

Western U.S. 3M Company
Mincom Division
300 South Lewis Road
Camarillo, California 93010
(805) 482-1911

Eastern U.S. 3M Company
Mincom Division
1750 Pennsylvania Avenue
Suite 1100
Washington D. C. 20006
(202) 298-9200

INTRODUCTION

This Instruction Manual has been prepared for the convenience and use of owners of the 3M Brand Professional Audio Recorder. The manual is supplied with each recorder shipped from the factory, and should be consulted before installation and operation of the recorder is attempted.

This manual is a revised edition of the original Series 400 Professional Audio Recorder Instruction Manual. It contains information reflecting changes made in the recorders with serial number above 250. Much of the original information contained in the earlier manual has been retained or expanded in this manual and is applicable for all Series 400 Recorders. However, care should be taken in the event this manual is referenced when used with machines having serial numbers 250 or lower. Differences, although minor in most cases, could cause difficulty in troubleshooting and ordering replacement parts or assemblies.

LIST OF EFFECTIVE PAGES

INSERT LATEST CHANGED PAGES. DESTROY SUPERSEDED PAGES.

Dates of issue for original and changed pages are:

Original. . O. . Dec. 67

Change . . 1 . . Feb. 69

TOTAL NUMBER OF PAGES IN THIS PUBLICATION IS 294 CONSISTING OF THE FOLLOWING.

Page No.	Change No.	Page No.	Change No.
Title	1	39/40, 41	O
List of Sales Offices	1	42 through 49/50	1
Introduction	1	51 through 55	1
A	1	56	O
i through vi	1	57 through 89/90	1
0	O	91 through 100	1
1 through 6	1	101	O
7	O	102 through 129/130	1
8	1	131/132 through 161/162	1
9, 10	O	163 through 185/186	1
11 through 22	1	187/188	1
23/24	O	189 through 253/254	1
25 through 27	1	255 through 257/258	1
28, 29	O	259 through 275/276	1
30	1	277/278	1
31	O	279 through 287/288	1
32 through 34	1	289 through 303/304	1
35	O	305 through 312	1
36 through 38	1		

TABLE OF CONTENTS

	Page
GENERAL DESCRIPTION	
Functional Description	1
Dynatrack Electronic System	1
Isoloop Tape Transport	4
Physical Description	6
Equipment Description	6
Specifications	18
INSTALLATION	
Receipt Inspection	25
General	25
Location Considerations	25
Console Model Installation	25
Rack (or Custom) Mounting	26
Portable Model Installation	30
Electrical Connections	30
Power and Control Cable	30
Head Cables	32
Signal Connectors	32
Remote Meters	32
Pilot Tone	32
Remote Control	32
Edit Foot Control	32
Power Cord	34
Capstan Assist Spring	34
Reproduce Only Electronics Assembly Connections	34
Interface Information	36
Signal Input	36
Signal Output	36
Remote Meter	37
Pilot and Loudspeaker	38
Phones	38
Auxiliary Ground	39/40
OPERATING CONTROLS AND DETAILS	
Tape Transport Controls	41
PLAY Button	41
FORWARD Button	41
STOP Button	42
REWIND Button	42

TABLE OF CONTENTS (Continued)

	Page
 OPERATING CONTROLS AND DETAILS (Cont'd)	
RECORD Button	42
POWER Switch	42
A-B OUTPUT Transfer Switch	43
RUNOUT Switch	43
SPEED Switch	43
BALANCE Switch	43
Tape Transport, Tape Handling Components	44
Reversing Idler	44
Editing Index	44
Head Assembly	44
Tape Lifters	44
Head Shield Door	44
Capstan	44
Capstan Idler (Incoming)	46
Capstan Idler (Outgoing)	46
Tape-Threaded Sensor	46
Edit Post	46
Reel Holders	46
Electronics Assemblies	46
RECORD LEVEL Control	47
REPRO. LEVEL Control	47
REC. SELECT Switch	48
METER Switch	48
OUTPUT SELECT Switches	49/50
REC. Indicator	49/50
PHONES Jack	49/50
 GENERAL OPERATING PROCEDURES	
Preliminary	51
Threading	51
Monitoring	51
Recording	53
Playback	54
Overdubbing	54
Erasure	54
Editing	55

TABLE OF CONTENTS (Continued)

Page

ALIGNMENT AND ADJUSTMENT

Tape Transport	57
Flutter	67
NAB Signal Electronics Alignment	70
NAB Playback Alignment	70
NAB Record Alignment	74
15 IPS Tape Speed Alignment	74
7-1/2 IPS Tape Speed Alignment	75
Dynamic Range Adjustment (NAB)	76
Miscellaneous Adjustments and Circuit Arrangements	77
Dynatrack Electronic Alignment	80
Dynatrack Record Alignment	81
H Track NAB Alignment	82
L Track Alignment	83
Combined H-L Dynatrack Performance	83
Dynamic Range Measurement, Dynatrack	84
Heads	87
Tape Guides	87
Reel Hubs	88

MAINTENANCE

General Precautions	91
Troubleshooting	92
Field Service	100
Factory Repair Service	100

PRINCIPLES OF OPERATION

Introduction	101
Tape Drive Components (See Figure 30)	101
Tape Transport Circuit Descriptions	103
Power Circuits	103
Threaded Tape Condition	105
From Standstill to Play	105
From Play to Stop	106
From Stop to Rewind	107
From Rewind to Stop (Tape Moving in the Rewind Direction)	107
From Rewind to Stop (Tape Moving in Forward Direction)	108
From Stop to Forward	108
From Forward to Stop (Tape Moving in Forward Direction)	108
From Forward to Stop (Tape Moving in Rewind Direction)	109
From Forward to Rewind	109

TABLE OF CONTENTS (Continued)

	Page
PRINCIPLES OF OPERATION (Cont'd)	
From Rewind to Forward	109
From Rewind to Play	109
From Forward to Play	110
Tape Runout	110
Record Mode Operation	111
Speed Change Switch	111
Reel Size Switch	111
Torque Control Relay	112
Monitor Switching	112
Runout Switch	113
Fail-Safe Brakes	113
Signal Electronics Functions	113
NAB Electronics	114
NAB Recording	114
NAB Reproduction	116
Dynatrack Electronics	118
Detailed Circuit Descriptions	119
H and NAB Record Amplifier (4)	119
L Record and Bias (3D)	121
Bias and Erase Amplifier (1)	122
H and NAB Preamplifier (7)	123
H and NAB Preamplifier with Overdub (7/9)	125
Line Amplifier (6)	125
L Preamplifier and Switch (8D)	126
Meter and Power Supply Assembly (5)	129/130
NAB Erase Coupler (3N)	129/130
SCHEMATICS	
PARTS LISTS	
Introduction	163
Ordering Replacement Parts	163

LIST OF ILLUSTRATIONS

Figure No.		Page
1	3M Brand Professional Audio Recorder	0
2	Dynatrack Characteristics	2
3	Dynatrack H and L Channels	3
4	H and L Track Transfer	4
5	Isoloop Tape Drive	5
6	3M Brand Professional Audio Tape Recorder Systems . . .	7
7	Tape Transport	8
8	Electronics Assembly (One Channel)	9
9	Reproduce Only Electronics Assembly	10
10	Outline Dimensions, Console Models	27
11	Outline Dimensions for Rack Mounting and Custom Installations	28
12	Typical Rack Mounting Layout	29
13	Transporter Case Outline Dimensions	31
14	Cable Connections	33
15	Signal Input Connector Wiring	36
16	Signal Output Connector Wiring	37
17	Remote Meter Connector Wiring	38
18	Pilot Connector Wiring	39/40
19	Tape Drive Components	45
20	Electronic Controls	47
21	Tape Threading	52
22	Tape Editing	56
23	Tape Transport Adjustments, Top View	58
24	Tape Transport Adjustments, Bottom View	59
25	Example of Simple Stroboscope Lamp	60
26	Electronics Assembly Adjustment Locations	71
27	Record and Playback Head Azimuth Adjustments	73
28	ASA Weighting Network and Response Curve	85
29	Reel Hub Adjustment	89/90
30	Tape Recorder, Block Diagram	102
31	Tape Transport Schematic	133/134
32	Tape Transport Circuit Board Layout	135/136
33	Tape Transport Wiring Diagram	137/138
34	Electronics Block Diagram	139/140
35	Remote Control Assembly Schematic	141/142
36	Bias and Erase Amplifier Schematic	143/144
37	NAB Erase Coupler Schematic	145/146
38	Dynatrack L Record Amplifier Schematic	147/148
39	H and NAB Record Amplifier Schematic	149/150
40	Electronics Assembly (Meter and) Power Supply Schematic	151/152
41	Line Driver Amplifier Schematic	153/154

LIST OF ILLUSTRATIONS (Continued)

Figure No.		Page
42	H and NAB Reproduce Preamplifier Schematic	155/156
43	Dynatrack L Preamplifier and Switch Schematic	157/158
44	H and NAB Preamplifier with Overdub Schematic	159/160
45	Dynatrack Power Supply Schematic	161/162
46	Tape Editing Switch Assembly	187/188
47	Tape Deck Assembly	253/254
48	Remote Control Assembly	257/258
49	Audio Signal Electronics Housing Assembly	277/278
50	Signal Electronics Power Supply Assembly with Meter . .	287/288
51	Reproduce Signal Electronics Housing	303/304

LIST OF TABLES

Table		Page
1	3M Brand Professional Audio Recorder Components	11
2	Specifications	19
3	Standard Dynatrack and NAB Head and Signal Cable Connections	35
4	Capstan Speed Error (for 48 element strobe wheel)	61
5	Spring Scale Reading to Motor Torque Conversion Table . .	63
6	Takeup Motor Torques	64
7	Supply Motor Torques	64
8	Components Contributing to Flutter	68
9	Troubleshooting	92
10	Line Operating Level Calibrating Resistors	126
11	Parts List Index	164



Figure 1. 3M Brand Professional Audio Recorder

GENERAL DESCRIPTION

The 3M Brand Professional Audio Recorder is manufactured by the Mincom Division of the 3M Company in Camarillo, California. It fulfills a requirement in the professional recording industry for the ultimate quality in tape recording. The continued improvements in records, tapes, and playback equipment revealed deficiencies in original master recordings. The 3M Brand Professional Audio Recorder overcomes these problems and provides improved master music tapes -- improvement readily discernible by ear.

The 3M Brand Professional Audio Recorder provides significant improvements over present professional audio recorders in three basic areas. Probably the most important of these is the improved dynamic range, as much as 15 db. The second area of improvement is a new tape drive system that reduces flutter to half that present in other tape transports in the audio field. Third, the entire system affords an operating and editing ease unmatched by any other tape recorder. Other improvements, not readily apparent, are an increase in the long-term reliability due to the exclusive use of silicon transistors in the electronics assemblies plus the simplified tape-drive system.

The 3M Brand Professional Audio Recorder achieves its outstanding performance from such patented techniques as the 3M Dynatrack system of recording and playback, and the Isoloop tape drive system; plus experience gained from over a decade of design and manufacture of Mincom, state-of-the-art, aerospace tape recorder-reproducer systems.

FUNCTIONAL DESCRIPTION

Functionally, the 3M Brand Professional Audio Recorder operates on the same basic principles as any other tape recorder. These principles are covered in many textbooks and will not be presented in this manual. As stated, the features that give this recorder its outstanding performance are the Dynatrack technique of recording and reproducing, and the Isoloop tape drive.

DYNATRACK ELECTRONIC SYSTEM

The Dynatrack technique improves signal-to-noise ratio and expands the recorded dynamic range of tapes by as much as 15 db over other recorders. These improvements are the result of a revolutionary, yet relatively simple, diversity recording and reproducing system. The diversity system feeds the same signal through two recording heads, mounted parallel in the same head stack, and records two separate, full band information tracks simultaneously. Every channel in the Dynatrack recorder (one channel for mono, two for simple stereo, or three for

multi-channel stereo, or stereo and mono together), records two information tracks.

One track of a channel is recorded at a normal level, following NAB recording standards. The other track, recording the identical information records signals at a higher level (more recording amplifier gain), employs a preemphasis curve rising 15 db from 400 Hz to 15,000 Hz (figure 2A).

The track recorded at normal level can handle higher signal levels, so it is called the H track. It will reach distortion levels in accordance with standard VU meter practice and with NAB response and distortion specifications. The other track, with its preemphasized, higher-level signal, is better suited for recording signals of a much lower sound level, so it is called the L track. This L track will go into overload distortion at high-frequency signal levels considerably below 0 VU on the meter. But when reproducing very soft sounds, which are usually lost in tape noise when recorded at normal levels, the L track will put out a clean, undistorted signal at a level well above tape noise (figure 3).

Once these two tracks are recorded as described, the only remaining problem is to arrange for playing back the proper track -- that track with minimum noise or minimum distortion -- and at the proper signal level.




Figure 2. Dynatrack Characteristics




Figure 3. Dynatrack H and L Channels

Selection of the proper playback track is dependent upon an electronic circuit which is fully automatic and completely silent in switching from one track to the other. The circuitry is designed and calibrated so that the signals from the L track are reproduced up to the point where the signal approaches 1% total harmonic distortion. At this point the output is taken from the H track, which has a signal recorded as much as 15 db below the 1% distortion point. Now, the level of the output signal can continue rising until it reaches the normal maximum, as indicated on the VU meter. This track transfer from L to H occurs much faster than the ear can detect so that sudden steep transients of high volume are cleanly reproduced without any audible distortion. When the signal on the L track drops below 1% distortion, the electronic circuit automatically transfers the signal from the H track back to the L track in approximately 30 milliseconds.

NOTE

No switching occurs on signals below 400 Hz, as tape noise rarely intrudes on signals below this frequency.

To equalize playback levels of both the L and H tracks, there is a de-emphasis network in the play circuit of these preamplifiers, providing the exact opposite of the preemphasis network in the recording circuitry (figure 2B).

A continuous visual check as to which track is being reproduced is provided by the pilot lamp in the L track preamplifier section of the electronic assembly. When the lamp is glowing, the L track is being reproduced; when the lamp is out, the H track is being fed to the output.

This automatic track transfer system is a completely electronic system; no mechanical relays, switches, etc., are used (figure 4). All electronics are solid-state, assuring long term reliability and accuracy of performance. Also, as the Dynatrack recording technique is completely electronic, there is no noise involved at any frequency, and the system is completely undetectable in use -- except for the increased signal-to-noise ratio and the far greater dynamic range of tapes recorded and reproduced on the 3M Brand Professional Audio Recorder.

ISOLOOP TAPE TRANSPORT

The tape transport mechanism of the 3M Brand Professional Audio Recorder is derived from designs used in instrumentation recorders, where standards of timing accuracy, and wow and flutter are even more demanding than




Figure 4. H and L Track Transfer

they are in audio recording. The heart of the patented Isoloop tape drive is the differential capstan, which maintains a constant tape tension within the drive and positive contact of the tape against the heads (figure 5). In addition, the unsupported tape path is extremely short in comparison to standard design tape recorders. This short path reduces longitudinal oscillation to a new low and eliminates the need for a series of tape guides to maintain a proper tape path.

The tape tension required to minimize flutter and hold the tape against the heads is generated within the closed loop by the differential drive capstan. The tape drive surface of the capstan is divided into regions of two different diameters. The incoming idler roller is contoured so as to press the tape firmly into the matching "grooves" (of the smaller diameter) of the capstan. The outgoing idler roller is shaped so as to press the tape firmly against the "ridges" (of the larger diameter) of the capstan. This differential of capstan diameters constantly tries to extract more tape than is being fed into the loop and creates the necessary tension by means of the slight elasticity of the tape itself. This tape tension is always kept safely within its elastic limits.

The Isoloop tape drive, short tape path, and flywheel driven capstan all aid in reducing the flutter of the tape transport to approximately half that found in other professional tape drive systems.




Figure 5. Isoloop Tape Drive

PHYSICAL DESCRIPTION

The system equipment can be supplied in almost any configuration required. It is available in several standard console configurations, as a portable system contained in its own portable case, or unmounted for installation in a 19-inch equipment rack (figure 6). Special consoles and cabinets are available on special order. Systems are engineered to fit the user's requirements: the number and type of channels, and the mounting and installation to fit the application. Complete installation instructions for each of the standard models is given under Installation.

Physically, each system consists of a tape transport and electronics as required. This may be 1 to 8 channels of NAB electronics, 1 to 4 channels of Dynatrack electronics or a combination of both. Any system can be expanded up to the maximum capacity simply by adding additional channels of electronics and changing the tape width and magnetic heads.


EQUIPMENT DESCRIPTION

Each tape recorder system will have a tape transport (figure 7) and an electronics assembly (figure 8) for each record and play channel. Also, a system may have any of the accessories listed in table 1.

The basic tape transport is the same in all systems; the only difference is in the tape width, magnetic heads, and capstan speed. The tape guides and magnetic heads are installed as kits depending upon the number and type of channels. The transport is available with either of two capstan sizes. One of these kits accommodates 1/4-inch or 1/2-inch tape. It is normally furnished in machines that will never be expected to use tapes wider than 1/2 inch. The other kit is intended for machines using 1-inch tape. While 1/2-inch and 1/4-inch tape can be run on the 1-inch capstan, the latter is less convenient for threading and editing 1/4-inch or 1/2-inch tape.

The electronics assembly contains the electronics required for a single channel of NAB or Dynatrack record and playback. Each electronics assembly contains a plug-in power supply and meter (the meter may be in a remote location), controls and indicators, and as many as seven plug-in circuit boards. There is an input and an output transformer located behind the control panel. All electrical connections for each channel are made on the rear panel of the electronics assembly.

The electronics assembly plug-in circuit boards are numbered 1 through 9 on the board handle indicating the slot that the board goes in. Slot 2 is always empty and the meter and power supply is slot 5. To change the electronics assembly between NAB and Dynatrack it is only necessary to change the boards in slot 3 and 8. The NAB boards have an N on their handle and the Dynatrack boards have a D on their handle. It is also necessary, when changing between NAB and




UNMOUNTED

Consists of tape transport and electronics. Transport is complete with required magnetic heads and ready for horizontal or vertical mounting. Electronics are individual modular panels and provide either standard NAB and/or Dynatrack functions.

CONSOLE

Transport and electronics mounted within a console cabinet.





PORTABLE

Components mounted within rugged shock mounted portable cases.

Figure 6. 3M Brand Professional Audio Tape Recorder Systems

Figure 7. Tape Transport







(SHOWN WITH
DYNATRACK AND
OVERDUB BOARD
SET)

1176

Figure 8. Electronics Assembly (One Channel)



1178

Figure 9. Reproduce Only Electronics Assembly

Dynatrack, to change the cabling on the rear panel of the electronics assembly and possibly the magnetic heads and tape width of the transport.

The Professional Audio Recorder is available as an all reproduce (figure 9), or combination of record-reproduce, and reproduce only system. The reproduce only electronics are contained in a special electronics assembly. Two circuit boards per channel are required. There is a head cable input connector, output transformer, and signal output connector for each channel on the rear panel. The front panel contains a meter, selector switch, phone jack, and power on indicator.

The tape transport operates at either of two electrically selectable tape speeds. The most common speeds are 7-1/2 and 15 ips; however, other speeds are available. The electronics equalization is automatically switched to the selected tape speed. The standard transport is equipped to accommodate 10-1/2 inch reels with NAB hub; however, other hubs and reel capacities are available.

The tape transport contains the tape motion controls and tape handling controls; plus, it performs certain functions common to all of the electronic assemblies. It provides tape speed equalization control, the source of bias and erase frequency, the A-B transfer function, and control of the record function. The POWER button on the transport controls the power to the entire system. The electronics assembly contains all of the remaining controls, such as the record and reproduce level controls, and the meter control.

Table 1. 3M Brand Professional Audio Recorder Components

COMPONENT			DESCRIPTION	
TAPE TRANSPORT				
TAPE TRANSPORTS		Capstan Guides		Complete tape transport less mounting hardware and head assemblies
	<u>Speeds (ips)</u>	<u>(inches)</u>		
23013B000-10	7 1/2, 15	1/2	1/4	
23013B000-11	7 1/2, 15	1/2	1/2	
23013B000-12	7 1/2, 15	1	1/4	
23013B000-13	7 1/2, 15	1	1/2	
23013B000-14	7 1/2, 15	1	1	
23013B000-17	15, 30	1/2	1/4	
23013B000-18	15, 30	1/2	1/2	
23013B000-19	15, 30	1	1/4	
23013B000-20	15, 30	1	1/2	
23013B000-21	15, 30	1	1	

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENT			DESCRIPTION
BASIC TAPE TRANSPORT			Consists of the basic tape transport less the tape width determining elements, tape speed kits, head assemblies, and mounting hardware.
23013B990			
TAPE SPEED KIT (Capstan Motor & Flywheel Set)			Consists of capstan motor assembly, including capacitor and connector mounted on swing bracket, capstan flywheel, and resistor R63.
	<u>Speeds (ips)</u>	<u>Power (~)</u>	
23013B940	3 3/4, 7 1/2	60	
23013B945-1	7 1/2, 15	60	
23013B945-2	7 1/2, 15	50	
23013B950-1	15, 30	60	
23013B950-2	15, 30	50	
23013B955	30, 60	60	
23013B960	60, 120	60	
TAPE WIDTH KIT (Guides & Reel Hubs)			Consists of ingoing and outgoing fixed tape guides, and NAB hub.
	<u>Tape (inches)</u>	<u>Capstan (inches)</u>	
23013A910	1/4	1/2	
23013A915	1/2	1/2	
23013A930	1/4	1	
23013A935	1/2	1	
23013A920	1	1	
BRAKE KITS			Shortens mode change time. Prevents tape spill if power fails.
23013A970	Flywheel brake (capstan) (high speed transports)		
23004A900	Failsafe brake (reels)		

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENT			DESCRIPTION
CAPSTAN AREA PARTS			Capstan, reversing idler, capstan idlers, idler arms, tape lifter, head gate, trim covers and capstan assembly (shaft, housing, and bearings).
23013A900	(1/4-1/2 inch)		
23013A905	(1/2-1 inch)		
HEAD ASSEMBLIES			Includes erase, record, and playback head stacks mounted on bolt-on precision plate, with single 42-pin connector.
	<u>Tape (inches)</u>	<u>Tracks</u>	
23000A020-1	1/4	1	
23000A020-2	1/4	2	
23000A020-5	1/2	2	
23000A020-3	1/2	3	
23000A020-4	1/2	4	
23000A020-6	1	3	
23000A020-7	1	4	
23000A020-8	1	6	
23000A020-9	1	8	
PREPLAY HEADS			Monitors tape ahead of reproduce heads to drive variable-pitch record cutting lathe.
	<u>Tape (inches)</u>	<u>Tracks</u>	
23000A900-1	1/4	1	
23000A900-2	1/4	2	
23000A900-4	1/2	3	
23000A900-5	1/2	4	
23000A900-6	1	4	
23000A900-7	1	8	
TRANSPORT COVER PLATES			
23013A023	19-inch (-1 for 10 1/2-inch reel, -2 for 12-inch reel)		
23000A005	24-inch (10 1/2-inch reel)		

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENT	DESCRIPTION
3 1/2-INCH BLANK PANEL 83-1360-0166	This panel is installed to provide space above rack-mounted transports for reel hangover.
5 1/4-INCH BLANK PANEL 23028A046	Used in place of an electronics assembly.
PORTABLE TRANSPORTER CASES 23028A100-1 23028A100-2	Fits transport with 1 inch capstan. Fits transport with 1/2-inch capstan plus one channel of electronics.
ELECTRONICS ASSEMBLY	
ELECTRONICS ASSEMBLY 23059A010	Consists of the basic electronics chassis assembly less all of the plug-in units.
ELECTRONICS ASSEMBLY BOARDS	These boards may be obtained as NAB channel set, Dynatrack channel set, or individually. Six of the boards are common; used for both NAB and Dynatrack.
NAB BOARD SET 23059A900	
Bias and Erase Amplifier (1)	
NAB Erase Coupler (NAB only) (3)	
H and NAB Record (4)	
Meter/Power Supply (5)	
Line Driver Amplifier (6)	
Overdub Preamplifier (7/9)	

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENTS	DESCRIPTION
<p>DYNATRACK BOARD SET</p> <p>23059A910</p> <p>Bias and Erase Amplifier (1)</p> <p>L Record Amplifier (Dynatrack only)(3)</p> <p>H and NAB Record Amplifier (4)</p> <p>Meter/Power Supply (5)</p> <p>Line Driver Amplifier (6)</p> <p>L Preamp and Switch (Dynatrack only) (8)</p> <p>Overdub Preamplifier (7/9)</p>	
<p>BIAS & ERASE AMPLIFIER CIRCUIT BOARD</p> <p>23059A020</p>	<p>Part of the record circuit — installed in slot 1.</p>
<p>NAB ERASE COUPLER CIRCUIT BOARD</p> <p>23059A030</p>	<p>Part of the NAB record circuit — installed in slot 3 in place of Dynatrack record board, 23059A130.</p>
<p>L RECORD AMPLIFIER CIRCUIT BOARD</p> <p>23059A130</p>	<p>Part of the Dynatrack record circuit — installed in slot 3.</p>
<p>H AND NAB RECORD AMPLIFIER CIRCUIT BOARD</p> <p>23059B040</p>	<p>Part of the record circuit — installed in slot 4.</p>
<p>METER AND POWER SUPPLY ASSEMBLY</p> <p>23059A050</p>	<p>Power supply and meter — installed in slot 5.</p>
<p>LINE DRIVER AMPLIFIER CIRCUIT BOARD</p> <p>23059A060</p>	<p>Part of the reproduce circuit — installed in slot 6.</p>

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENTS	DESCRIPTION
H AND NAB PREAMPLIFIER CIRCUIT BOARD 23059A170	Part of the reproduce circuit -- installed in slot 7.
L PREAMPLIFIER AND SWITCH CIRCUIT BOARD 23059A140	Part of the Dynatrack reproduce circuit -- installed in slot 8.
H AND NAB PREAMPLIFIER WITH OVERDUB 23059B090	Same as slot 7 board but with overdub feature -- may be used in slot 7 or 9.
NAB CONVERTER 23059A920	This board is required only when a Dynatrack Electronics Assembly is converted to NAB operation.
POWER SUPPLY WITHOUT METER 23059A250	Power supply used with remote meters -- installed in slot 5.
CABLES	
TRANSPORT-TO-ELECTRONICS POWER AND CONTROL CABLES 23028A055 4 channel 23028A065 8 channel	5-foot cable, 15-pin connectors. 5-foot, Y-cable, 15-pin connectors.
HEAD CABLES 23000A010-1 1 track 23000A010-2 2 tracks 23000A010-3 3 tracks 23000A010-4 4 tracks 23000A010-8 8 tracks	This cable is about 66-inches long, and connects between the head plate on the transport and each channel of electronics. There is a play (P), record (R), and erase (E) head cable for each track.

Table 1. 3M Brand Professional Audio Recorder Components (Cont'd)

COMPONENT	DESCRIPTION
ACCESSORIES	
<p>REMOTE CONTROL (with 5-foot cable) 23017A000</p> <p>REMOTE CONTROL EXTENSION CABLE 23017A010</p> <p>EDIT FOOT SWITCH 23000A950</p> <p>EXTENDER BOARD 23059A110</p> <p>REPRODUCE ONLY ELECTRONICS 23059A960-1 4 channel NAB 23059A960-2 8 channel NAB</p> <p>FILM SYNC ELECTRONICS Chassis Assembly and Circuit Board Set 23059A950 Bias and Erase Amplifier Circuit Board (1) 23059A020 Erase Coupler Board (3N) 23059A030 Film Sync Record Amplifier Board (3S) 23059A330 H and NAB Record Amplifier Board (4) 23059B040</p>	<p>This unit provides remote control of the RECORD, PLAY, STOP, REWIND, FORWARD, and A-B OUTPUT transfer functions.</p> <p>A 25-foot extension cable for the remote controls.</p> <p>Permits hand-free spill/standby/wind for rapid tape editing.</p> <p>Extender board for circuit boards in the electronics assembly.</p> <p>Includes a chassis assembly, a preamplifier and line amplifier for each channel.</p> <p>Fits 5 1/4 x 19 inch rack space.</p> <p>Slot 1 Board</p> <p>Slot 2 Board</p> <p>Slot 3 Board</p> <p>Slot 4 Board</p>

Table 1. 3M Brand Professional Audio Recorder Components (Concluded)

COMPONENTS	DESCRIPTION
Meter and Power Supply Assembly 23059A050	Slot 5 Assembly
H and NAB Preamplifier Board (7) 23059A170	Slot 7 Board
Line Driver Amplifier Board (6) 23059A060	Slot 6 Board
Film Sync Reproduce Board (9S) 23059A390	Slot 9 Board
Film Sync Head Cable Set 23000A310	
Film Sync Power Cable 23023A350	

SPECIFICATIONS

Specifications for the 3M Brand Professional Tape Recorder are presented in table 2. These specifications are based upon operation in accordance with the procedures and conditions presented in this manual. Deviation from these procedures, use of other than recommended magnetic tapes, or modification of the equipment may result in degradation of the equipment performance. These specifications are subject to change without notice.

Table 2. Specifications

CHARACTERISTICS	SPECIFICATIONS																																								
ELECTRONICS																																									
Signal-to-Noise Ratio:	<p>For Dynatrack system employing 1/4-inch width of tape per channel (1 channel 1/4-inch tape; 2 channels 1/2-inch tape, etc.) at 15 ips tape speed based on peak record level of 3% THD and employing ASA weighting curve A: Greater than 80 db.</p> <p>For standard recording systems with NAB equalization measured from 3% THD level at 400 cycles to noise, on full spectrum basis:</p> <table><tr><th>Tracks No.</th><th>Tape Width Inches</th><th>Track Width Mils</th><th>15 or 7 1/2 ips Speed db</th></tr><tr><td>1</td><td>1/4</td><td>0.234</td><td>67</td></tr><tr><td>2</td><td>1/4</td><td>0.075</td><td>62</td></tr><tr><td>2</td><td>1/2</td><td>0.200</td><td>66</td></tr><tr><td>3</td><td>1/2</td><td>0.100</td><td>63</td></tr><tr><td>4</td><td>1/2</td><td>0.070</td><td>62</td></tr><tr><td>3</td><td>1</td><td>0.250</td><td>67</td></tr><tr><td>4</td><td>1</td><td>0.180</td><td>66</td></tr><tr><td>6</td><td>1</td><td>0.095</td><td>63</td></tr><tr><td>8</td><td>1</td><td>0.070</td><td>62</td></tr></table>	Tracks No.	Tape Width Inches	Track Width Mils	15 or 7 1/2 ips Speed db	1	1/4	0.234	67	2	1/4	0.075	62	2	1/2	0.200	66	3	1/2	0.100	63	4	1/2	0.070	62	3	1	0.250	67	4	1	0.180	66	6	1	0.095	63	8	1	0.070	62
Tracks No.	Tape Width Inches	Track Width Mils	15 or 7 1/2 ips Speed db																																						
1	1/4	0.234	67																																						
2	1/4	0.075	62																																						
2	1/2	0.200	66																																						
3	1/2	0.100	63																																						
4	1/2	0.070	62																																						
3	1	0.250	67																																						
4	1	0.180	66																																						
6	1	0.095	63																																						
8	1	0.070	62																																						
Tape Type:	<p>Specifications are based on use of Scotch Brand Dynarange recording tapes 201, 202, or 203. Adjustable bias and equalization permits accommodation of a wide range of tape characteristics.</p>																																								
Equalization:	<p>The Dynatrack system matches the NAB curve of frequency versus distortion for 15 ips above a designed reference level. The weighted 3M equalization curve is followed at low level for extended dynamic range.</p> <p>Standard machines are normally equalized for NAB 15 and 7 1/2 ips speeds. Equalizers are automatically switched when the tape speed is changed. Other forms of equalization may be provided on order.</p>																																								

Table 2. Specifications (Cont'd)

CHARACTERISTICS	SPECIFICATIONS
Frequency Response:	<p>15 ips NAB equalization</p> <p>±1 db 40 to 15,000 cycles</p> <p>±2 db 30 to 15,000 cycles</p> <p>7 1/2 ips NAB equalization</p> <p>±1 db 50 to 12,000 cycles</p> <p>±2 db 30 to 15,000 cycles</p>
Phasing:	Signal input to output polarity is maintained on all channels.
Channel Separation:	Channel to channel crosstalk separation is greater than 50 db at 500 cycles (zero VU).
Electronics Input:	20,000 ohm balanced or unbalanced line. -20 dbm to +8 dbm signal on 600-ohm bus.
Electronics Output:	Feed to 150 or 600-ohm line, terminated or unterminated at levels of +4 or +8 dbm. Convenient switch transfers output directly to monitor loud-speaker line with peak power capability of 1 watt to an 8-ohm load. Other operating levels are available on special order.
Bias and Erase Oscillator:	Master oscillator on tape transport supplies 120 kHz, through a low impedance bus to the individual bias and erase power amplifiers for each channel.
Degree of Erasure:	A 1,000 cycle signal at 3% distortion level is reduced 68 db or more by the erase head provided for NAB standard operation.
Power Input:	110 to 135 volts, 60 cycles. Internally regulated power supplies make transformer tap changes unnecessary over this range. Optional 50 cycle power.

Table 2. Specifications (Cont'd)

CHARACTERISTICS	SPECIFICATIONS															
Electronic Controls:	Operating controls provided on front panel of each electronics module: RECORD LEVEL and REPRO LEVEL gain controls with positive mechanical shaft locks. REC SELECT switch (RDY., SAFE, O. DUB), METER switch (CAL., SIGNAL, ERASE, BIAS), OUTPUT SELECT pushbutton (A or B), REC. (record) warning pilot lamp, and PHONES jack.															
MECHANICAL																
Speeds:	7 1/2 and 15 ips standard. 3 3/4 and 7 1/2 ips or 15 and 30 ips available on special order.															
Tape Width:	Normally 1-, 1/2-, or 1/4-inch tape.															
Reel Sizes:	NAB hub. Adaptable to CCIR or small plastic reel hubs. Standard reel 10 1/2-inch diameter. Alternatively, 11 1/2-inch diameter reels can be furnished for CCIR applications. Large 14-inch reel diameter capability is available.															
Flutter:	<table><tr><th>Speed (ips)</th><th>Flutter Band (Hz)</th><th>Maximum % Flutter (rms)</th></tr><tr><td>15</td><td>0.5 - 300</td><td>0.04%</td></tr><tr><td>15</td><td>0.5 - 5000</td><td>0.05%</td></tr><tr><td>7 1/2</td><td>0.5 - 300</td><td>0.07%</td></tr><tr><td>7 1/2</td><td>0.5 - 5000</td><td>0.09%</td></tr></table> <p>All measurements of flutter are made by recording a tone on the machine under test, rewinding the tape and measuring flutter on replay. Maximum additive phase case accepted as maximum flutter.</p>	Speed (ips)	Flutter Band (Hz)	Maximum % Flutter (rms)	15	0.5 - 300	0.04%	15	0.5 - 5000	0.05%	7 1/2	0.5 - 300	0.07%	7 1/2	0.5 - 5000	0.09%
Speed (ips)	Flutter Band (Hz)	Maximum % Flutter (rms)														
15	0.5 - 300	0.04%														
15	0.5 - 5000	0.05%														
7 1/2	0.5 - 300	0.07%														
7 1/2	0.5 - 5000	0.09%														
Start Time:	0.5 second to stable motion in play or record mode for 1/4-inch or 1/2-inch tape, 1.0 second for 1-inch tape.															
Stopping Time:	0.8 second from play or record mode.															
Timing Accuracy:	±0.10%															
Rewinding Time:	60 seconds for 2400 feet.															

Table 2. Specifications (Cont'd)

CHARACTERISTICS	SPECIFICATIONS
Weight/Dimensions:	Tape transport and electronics assembly have standard 19-inch wide rack mounting panels with commercial notching.
Console:	66 1/2 inches high (with four electronics modules), 26 3/4 inches wide, 24 1/4 inches deep. Approximate weight (complete) 300 lbs.
Tape Transports:	15 3/4-inch panel. Weight approximately 65 pounds.
Electronics Assembly:	5 1/4-inch panel. Weight approximately 15 pounds per assembly. (One electronics assembly required for each channel recorded: NAB or 3M Dynatrack channel).
Portable:	Complete in two drawn aluminum cases. Electronics case: 21 inches long, 11 1/4 inches wide, 18 inches high. Weight: approximately 85 pounds with three electronics modules. Tape transport case: 21 inches long, 12 inches wide, 18 inches high. Weight approximately 85 pounds.
Tape Transport Controls:	All are inoperative until tape is placed in the operating path which activates the controls and illuminates the STOP button. PLAY button starts tape in motion at running speed selected with HI-LO switch. May be activated from any other mode including high speed FORWARD or REWIND through automatic stop sequence without damage to tape. RECORD is functional only when pressed with PLAY button. Any or all channels can be locked off to prevent accidental recording. FORWARD places tape in high speed forward and operates tape lifters. REWIND similarly places tape in rewind mode and operates tape lifters. STOP refers torque to brake tape dynamically. When tape stops, braking torque is removed and slight holding torque is applied to prevent tape slack.

Table 2. Specifications (Concluded)

CHARACTERISTICS	SPECIFICATIONS
Optional Console Electronics Mounting:	Electronics modules can be mounted below the tape transport in the console cabinet. The volume level (VU) meters are then mounted side-by-side on a single panel just above the tape transport.
Editing Foot Switch:	Used during tape editing to free operator's hands for splicing tape. Permits starts, stops, and intentional tape "spills" as required for rapid editing.

INSTALLATION

RECEIPT INSPECTION

The 3M Brand Professional Audio Recorder was inspected, completely checked out, and adjusted before leaving the factory. Immediately upon receipt, inspect the equipment for any shipping damage. If any damage is noticed, notify the carrier immediately. If everything is normal, proceed with the installation.

GENERAL

As previously described, the system comes in three basic models: console, portable, and rack mounting. Console models are completely connected and ready for operation when unpacked and the power and signal connections are made. The portable models require, in addition to the power and signal connections, inter-connecting cables between the tape transport and electronics. The rack mounting models require the same electrical connection as the portable model; in addition, they must be installed in a 19-inch equipment rack.

This section contains installation instructions for each of the three models, plus instructions for each of the standard accessories.

LOCATION CONSIDERATIONS

The tape recorder system can be installed in almost any location as long as reasonable judgement is used. The system should not be installed in an extremely dusty or damp location. Strong magnetic fields should be avoided, such as from power transformers and tape degaussers. The tape recorder can probably stand high temperatures much better than its human operator; however, if the recorder is to be installed in an equipment rack, it should not be mounted above a chassis with vacuum tubes or anything which generates a large amount of heat.

The tape recorder system can be remotely controlled. The standard remote control cables are 5 and 25 feet long; however, longer cables can be used.

CONSOLE MODEL INSTALLATION

Console models are shipped from the factory ready for operation. They are crated according to standard commercial practices, depending upon their destination. In some cases, the crating may be extensive and the receiver must be careful when unpacking not to damage the equipment or discard any separately packaged accessories. When the equipment is uncrated and located in its operating position, it only requires power and signal connections to be ready for operation;

plus connection of some accessories. Instructions for making these connections are given in the following paragraphs. Dimensions of the standard console models are given in figure 10.

RACK (OR CUSTOM) MOUNTING

For rack mounting or custom installations the equipment and interconnecting cables are shipped as separate items ready for installation into a 19-inch equipment rack. Figure 11 gives the outline dimensions. Figure 12 illustrates a typical rack mounting installation. Cable connections and signal interface information is presented in the following paragraphs of this section.

The electronics assemblies and transport are packaged according to commercial practices. In addition, the transport is contained in a wooden shipping crate. To remove the transport from the wooden shipping crate, pry the top of the crate off. (It is nailed on.) There are cutouts at each end of the crate so that the transport can be grasped and lifted out.

Remove the tape transport from its shipping crate and install it as follows:

1. Position the capstan assist spring for vertical or horizontal mounting, as required. See figure 14.
2. To expose the transport mounting rails, it is necessary to remove the transport front cover plate. This is secured by two screws at the top of the transport and a lip at the bottom. Remove the two screws and slide the cover from the lip.
3. Attach the transport to the mounting rails, using eight 10-32 screws, washers, and lock washers; four on each side.
4. Reinstall the transport front cover plate.

The maximum distance between the transport and the electronics assembly is determined by the control and head cable lengths. From the transport connector to the first electronics assembly connector is 36 inches. The remaining connector loops are 12 inches apart. The head cable set is 66-inches long.

To install the electronics assembly, open the front cover and attach to the mounting rails with four 10-32 screws, washers, and lock washers. When the electronics assembly and transport are installed, make the cable connections as shown in figure 14, and listed under "Electrical Connections".

NOTE

Note that each of the cards in the electronics assembly has a number on it indicating the channel. This should be considered when arranging the electronics assemblies.




Figure 10. Outline Dimensions, Console Models




Figure 11. Outline Dimensions for Rack Mounting and Custom Installations




Figure 12. Typical Rack Mounting Layout

PORTABLE MODEL INSTALLATION

Outline dimensions for the portable models are presented in figure 13. Of course, this equipment requires no physical installation. The equipment inside is attached to the case by shock mounts. Installation consists of removing the covers and making the electrical connections shown in figure 14 and listed under "Electrical Connections," as required. Also, connection of the capstan assist spring must be considered. This is also shown in figure 14. Signal interface information is present under that heading in this section.

ELECTRICAL CONNECTIONS

As previously stated, the console model is shipped with all internal cabling connected. It only requires that the power cable and the external signal cables be connected, plus accessories such as the edit foot control and remote control. In addition, the rack mounting and portable models require connection of the power and control cable, and head cables between the transport and electronics assemblies. All of the cable connections are illustrated in figure 14, and each is detailed in the following paragraphs. Disregard any connection that does not apply to your equipment.

NOTE

The circuit boards in each of the electronics assemblies have numbers on them indicating the magnetic head channels used to set up the electronics at the factory. These numbers should match when the equipment is installed. If they do not, the electronics should be readjusted before operation. For consistency, the channel numbers, the circuit board numbers, and head channel numbers should match throughout the system.

Power and Control Cable

Connect the power and control cable to the ELECTRONICS receptacle on the tape transport and to the POWER receptacle on each of the electronics assemblies. There are two power and control cables used. Cable 23028A050 accommodates four electronics assemblies, and cable 23028A060 accommodates eight electronics assemblies. It is not necessary that all connector loops of the cable be connected. If only two electronics assemblies are used, for example, and cable 23028A050 is supplied, there will be two extra connectors on this cable.




Figure 13. Transporter Case Outline Dimensions

Head Cables

If the tape transport is shipped with magnetic heads already installed, the head cables connector will probably be installed on the transport. If it is not, the end of the head cable with the single connector and bracket must be installed in its proper position on the transport. The head connector is located in a recess to the left of the capstan as viewed from above. Orient the cable connector properly and install it by securing it with two No. 4 screws, washers, and lock washer. By attaching this cable to the transport, the head assembly can be removed and installed from above without disturbing the head cable connector.

For tapes recorded on one recorder to be compatible with tapes recorded on other recorders, the head cables must be connected to the electronics assembly as shown in table 3. Head cables marked with a P are from the play heads, and must be connected to the REPRODUCE HEAD connectors for the channels indicated. Head cables marked with an R are from the record heads and must be connected to the RECORD HEAD connectors for the channel indicated. Cables marked with an E are from the erase head and must be connected to the ERASE HEAD connectors for the channels indicated.

Signal Connectors

Connect the input and output connectors for each channel to the SIGNAL IN and SIGNAL OUT connectors. These are standard 3-wire XL type connectors. Interface information is given under that heading in this section.

Remote Meters

If remote meters have been ordered, plug them into the REMOTE METER connector. Refer to the interface information for the remote meters under that heading in this section.

Pilot Tone

If a pilot tone is to be used, make this connection to the PILOT connector. Refer to the interface information for the pilot tone under that heading in this section.

Remote Control

If a remote control unit is to be used, connect the connector from the remote control to the REMOTE connector on the tape transport.

Edit Foot Control

If an edit foot control is used, connect it to the SPILL CONTROL connector on the tape transport. It is necessary to remove a jumper plug to make this connection. Do not misplace the jumper plug, since the machine will be inoperative without it if the edit foot control is later disconnected.

Diagram illustrating the internal components and head cable connections of a tape deck.

Internal Components:

- CAPSTAN ASSIST SPRING FOR VERTICAL OPERATION - NOT USED FOR HORIZONTAL OPERATION
- STORED FOR HORIZONTAL OPERATION
- 115 VOLT, 60 Hz
- REMOTE CONTROL
- JUMPER PLUG REQUIRED WHEN EDIT FOOT CONTROL IS NOT USED
- EDIT FOOT CONTROL
- POWER AND CONTROL CABLE

Head Cable Connections:

- TERMINATION: ADD. 100 OHM, OFF, 100 OHM, ON
- HEADS: HEAD 1, HEAD 2, HEAD 3, HEAD 4, HEAD 5, HEAD 6, HEAD 7, HEAD 8, HEAD 9, HEAD 10, HEAD 11, HEAD 12, HEAD 13, HEAD 14, HEAD 15, HEAD 16, HEAD 17, HEAD 18, HEAD 19, HEAD 20, HEAD 21, HEAD 22, HEAD 23, HEAD 24, HEAD 25, HEAD 26, HEAD 27, HEAD 28, HEAD 29, HEAD 30, HEAD 31, HEAD 32, HEAD 33, HEAD 34, HEAD 35, HEAD 36, HEAD 37, HEAD 38, HEAD 39, HEAD 40, HEAD 41, HEAD 42, HEAD 43, HEAD 44, HEAD 45, HEAD 46, HEAD 47, HEAD 48, HEAD 49, HEAD 50, HEAD 51, HEAD 52, HEAD 53, HEAD 54, HEAD 55, HEAD 56, HEAD 57, HEAD 58, HEAD 59, HEAD 60, HEAD 61, HEAD 62, HEAD 63, HEAD 64, HEAD 65, HEAD 66, HEAD 67, HEAD 68, HEAD 69, HEAD 70, HEAD 71, HEAD 72, HEAD 73, HEAD 74, HEAD 75, HEAD 76, HEAD 77, HEAD 78, HEAD 79, HEAD 80, HEAD 81, HEAD 82, HEAD 83, HEAD 84, HEAD 85, HEAD 86, HEAD 87, HEAD 88, HEAD 89, HEAD 90, HEAD 91, HEAD 92, HEAD 93, HEAD 94, HEAD 95, HEAD 96, HEAD 97, HEAD 98, HEAD 99, HEAD 100, HEAD 101, HEAD 102, HEAD 103, HEAD 104, HEAD 105, HEAD 106, HEAD 107, HEAD 108, HEAD 109, HEAD 110, HEAD 111, HEAD 112, HEAD 113, HEAD 114, HEAD 115, HEAD 116, HEAD 117, HEAD 118, HEAD 119, HEAD 120, HEAD 121, HEAD 122, HEAD 123, HEAD 124, HEAD 125, HEAD 126, HEAD 127, HEAD 128, HEAD 129, HEAD 130, HEAD 131, HEAD 132, HEAD 133, HEAD 134, HEAD 135, HEAD 136, HEAD 137, HEAD 138, HEAD 139, HEAD 140, HEAD 141, HEAD 142, HEAD 143, HEAD 144, HEAD 145, HEAD 146, HEAD 147, HEAD 148, HEAD 149, HEAD 150, HEAD 151, HEAD 152, HEAD 153, HEAD 154, HEAD 155, HEAD 156, HEAD 157, HEAD 158, HEAD 159, HEAD 160, HEAD 161, HEAD 162, HEAD 163, HEAD 164, HEAD 165, HEAD 166, HEAD 167, HEAD 168, HEAD 169, HEAD 170, HEAD 171, HEAD 172, HEAD 173, HEAD 174, HEAD 175, HEAD 176, HEAD 177, HEAD 178, HEAD 179, HEAD 180, HEAD 181, HEAD 182, HEAD 183, HEAD 184, HEAD 185, HEAD 186, HEAD 187, HEAD 188, HEAD 189, HEAD 190, HEAD 191, HEAD 192, HEAD 193, HEAD 194, HEAD 195, HEAD 196, HEAD 197, HEAD 198, HEAD 199, HEAD 200, HEAD 201, HEAD 202, HEAD 203, HEAD 204, HEAD 205, HEAD 206, HEAD 207, HEAD 208, HEAD 209, HEAD 210, HEAD 211, HEAD 212, HEAD 213, HEAD 214, HEAD 215, HEAD 216, HEAD 217, HEAD 218, HEAD 219, HEAD 220, HEAD 221, HEAD 222, HEAD 223, HEAD 224, HEAD 225, HEAD 226, HEAD 227, HEAD 228, HEAD 229, HEAD 230, HEAD 231, HEAD 232, HEAD 233, HEAD 234, HEAD 235, HEAD 236, HEAD 237, HEAD 238, HEAD 239, HEAD 240, HEAD 241, HEAD 242, HEAD 243, HEAD 244, HEAD 245, HEAD 246, HEAD 247, HEAD 248, HEAD 249, HEAD 250, HEAD 251, HEAD 252, HEAD 253, HEAD 254, HEAD 255, HEAD 256, HEAD 257, HEAD 258, HEAD 259, HEAD 260, HEAD 261, HEAD 262, HEAD 263, HEAD 264, HEAD 265, HEAD 266, HEAD 267, HEAD 268, HEAD 269, HEAD 270, HEAD 271, HEAD 272, HEAD 273, HEAD 274, HEAD 275, HEAD 276, HEAD 277, HEAD 278, HEAD 279, HEAD 280, HEAD 281, HEAD 282, HEAD 283, HEAD 284, HEAD 285, HEAD 286, HEAD 287, HEAD 288, HEAD 289, HEAD 290, HEAD 291, HEAD 292, HEAD 293, HEAD 294, HEAD 295, HEAD 296, HEAD 297, HEAD 298, HEAD 299, HEAD 300, HEAD 301, HEAD 302, HEAD 303, HEAD 304, HEAD 305, HEAD 306, HEAD 307, HEAD 308, HEAD 309, HEAD 310, HEAD 311, HEAD 312, HEAD 313, HEAD 314, HEAD 315, HEAD 316, HEAD 317, HEAD 318, HEAD 319, HEAD 320, HEAD 321, HEAD 322, HEAD 323, HEAD 324, HEAD 325, HEAD 326, HEAD 327, HEAD 328, HEAD 329, HEAD 330, HEAD 331, HEAD 332, HEAD 333, HEAD 334, HEAD 335, HEAD 336, HEAD 337, HEAD 338, HEAD 339, HEAD 340, HEAD 341, HEAD 342, HEAD 343, HEAD 344, HEAD 345, HEAD 346, HEAD 347, HEAD 348, HEAD 349, HEAD 350, HEAD 351, HEAD 352, HEAD 353, HEAD 354, HEAD 355, HEAD 356, HEAD 357, HEAD 358, HEAD 359, HEAD 360, HEAD 361, HEAD 362, HEAD 363, HEAD 364, HEAD 365, HEAD 366, HEAD 367, HEAD 368, HEAD 369, HEAD 370, HEAD 371, HEAD 372, HEAD 373, HEAD 374, HEAD 375, HEAD 376, HEAD 377, HEAD 378, HEAD 379, HEAD 380, HEAD 381, HEAD 382, HEAD 383, HEAD 384, HEAD 385, HEAD 386, HEAD 387, HEAD 388, HEAD 389, HEAD 390, HEAD 391, HEAD 392, HEAD 393, HEAD 394, HEAD 395, HEAD 396, HEAD 397, HEAD 398, HEAD 399, HEAD 400, HEAD 401, HEAD 402, HEAD 403, HEAD 404, HEAD 405, HEAD 406, HEAD 407, HEAD 408, HEAD 409, HEAD 410, HEAD 411, HEAD 412, HEAD 413, HEAD 414, HEAD 415, HEAD 416, HEAD 417, HEAD 418, HEAD 419, HEAD 420, HEAD 421, HEAD 422, HEAD 423, HEAD 424, HEAD 425, HEAD 426, HEAD 427, HEAD 428, HEAD 429, HEAD 430, HEAD 431, HEAD 432, HEAD 433, HEAD 434, HEAD 435, HEAD 436, HEAD 437, HEAD 438, HEAD 439, HEAD 440, HEAD 441, HEAD 442, HEAD 443, HEAD 444, HEAD 445, HEAD 446, HEAD 447, HEAD 448, HEAD 449, HEAD 450, HEAD 451, HEAD 452, HEAD 453, HEAD 454, HEAD 455, HEAD 456, HEAD 457, HEAD 458, HEAD 459, HEAD 460, HEAD 461, HEAD 462, HEAD 463, HEAD 464, HEAD 465, HEAD 466, HEAD 467, HEAD 468, HEAD 469, HEAD 470, HEAD 471, HEAD 472, HEAD 473, HEAD 474, HEAD 475, HEAD 476, HEAD 477, HEAD 478, HEAD 479, HEAD 480, HEAD 481, HEAD 482, HEAD 483, HEAD 484, HEAD 485, HEAD 486, HEAD 487, HEAD 488, HEAD 489, HEAD 490, HEAD 491, HEAD 492, HEAD 493, HEAD 494, HEAD 495, HEAD 496, HEAD 497, HEAD 498, HEAD 499, HEAD 500, HEAD 501, HEAD 502, HEAD 503, HEAD 504, HEAD 505, HEAD 506, HEAD 507, HEAD 508, HEAD 509, HEAD 510, HEAD 511, HEAD 512, HEAD 513, HEAD 514, HEAD 515, HEAD 516, HEAD 517, HEAD 518, HEAD 519, HEAD 520, HEAD 521, HEAD 522, HEAD 523, HEAD 524, HEAD 525, HEAD 526, HEAD 527, HEAD 528, HEAD 529, HEAD 530, HEAD 531, HEAD 532, HEAD 533, HEAD 534, HEAD 535, HEAD 536, HEAD 537, HEAD 538, HEAD 539, HEAD 540, HEAD 541, HEAD 542, HEAD 543, HEAD 544, HEAD 545, HEAD 546, HEAD 547, HEAD 548, HEAD 549, HEAD 550, HEAD 551, HEAD 552, HEAD 553, HEAD 554, HEAD 555, HEAD 556, HEAD 557, HEAD 558, HEAD 559, HEAD 560, HEAD 561, HEAD 562, HEAD 563, HEAD 564, HEAD 565, HEAD 566, HEAD 567, HEAD 568, HEAD 569, HEAD 570, HEAD 571, HEAD 572, HEAD 573, HEAD 574, HEAD 575, HEAD 576, HEAD 577, HEAD 578, HEAD 579, HEAD 580, HEAD 581, HEAD 582, HEAD 583, HEAD 584, HEAD 585, HEAD 586, HEAD 587, HEAD 588, HEAD 589, HEAD 590, HEAD 591, HEAD 592, HEAD 593, HEAD 594, HEAD 595, HEAD 596, HEAD 597, HEAD 598, HEAD 599, HEAD 600, HEAD 601, HEAD 602, HEAD 603, HEAD 604, HEAD 605, HEAD 606, HEAD 607, HEAD 608, HEAD 609, HEAD 610, HEAD 611, HEAD 612, HEAD 613, HEAD 614, HEAD 615, HEAD 616, HEAD 617, HEAD 618, HEAD 619, HEAD 620, HEAD 621, HEAD 622, HEAD 623, HEAD 624, HEAD 625, HEAD 626, HEAD 627, HEAD 628, HEAD 629, HEAD 630, HEAD 631, HEAD 632, HEAD 633, HEAD 634, HEAD 635, HEAD 636, HEAD 637, HEAD 638, HEAD 639, HEAD 640, HEAD 641, HEAD 642, HEAD 643, HEAD 644, HEAD 645, HEAD 646, HEAD 647, HEAD 648, HEAD 649, HEAD 650, HEAD 651, HEAD 652, HEAD 653, HEAD 654, HEAD 655, HEAD 656, HEAD 657, HEAD 658, HEAD 659, HEAD 660, HEAD 661, HEAD 662, HEAD 663, HEAD 664, HEAD 665, HEAD 666, HEAD 667

Power Cord

Pull back the shipping restraint latch from the power receptacle and plug the power cord into the tape transport. Then connect the other end of the power cord to a 115-volt 60 Hz power source.

CAPSTAN ASSIST SPRING

When the tape transport is mounted in a vertical position, an assist spring is required to hold the capstan motor out of engagement with the flywheel when it is not running. This spring is stored across the two lugs on the supply reel motor when the tape transport is shipped, or when it is installed for horizontal operation. For vertical operation, this spring must be connected between the supply reel motor and the capstan motor bracket. See figure 14. For console and rack mounting installations, it is only necessary to consider the capstan assist spring when the equipment is installed. However, since portable models can be operated either vertically or horizontally, the position of this capstan assist spring must be considered each time the equipment is set up.

REPRODUCE ONLY ELECTRONICS ASSEMBLY CONNECTIONS

The reproduce only electronic assembly requires three different connections: power and control cable, head cables, and signal output cables. The channel numbers run from right to left, looking at the rear connector panel. The connections are as follows:

1. Connect the power and control cable from the ELECTRONICS connector on the tape transport to the connector on the electronics assembly.
2. If the head cable is not connected to the transport, attach it as described under "Electrical Connections." Connect the channel head cables to head cable connectors on the electronics assembly. Be sure that the head cable numbers and the channel numbers are the same.
3. Connect the signal output cables to the XL type connectors. Be sure that the proper channel identification is maintained. The cables should be made up as shown in figure 16. The output impedance is 600 ohms.

Table 3. Standard Dynatrack and NAB Head and Signal Cable Connections

FOR CHANNEL	USE ELECTRONICS ASSEMBLY NO.	REPRODUCE HEAD LO HI	SIGNAL OUT	PILOT	POWER	REMOTE METER	SIGNAL IN	RECORD HEAD LO HI	ERASE HEAD
DYNATRACK ONLY SYSTEMS									
1	1	P2	P1	CH 1 OUT			CH 1 IN	R2	R1 *
2	2	P4	P3	CH 2 OUT			CH 2 IN	R4	R3 *
3	3	P6	P5	CH 3 OUT			CH 3 IN	R6	R5 *
4	4	P8	P7	CH 4 OUT			CH 4 IN	R8	R7 *
CHANGING NAB TO DYNATRACK									
1	1	P2	P1	CH 1 OUT			CH 1 IN	R2	R1 *
2	3	P4	P3	CH 3 OUT			CH 3 IN	R4	R3 *
3	5	P6	P5	CH 5 OUT			CH 5 IN	R6	R5 *
4	7	P8	P7	CH 7 OUT			CH 7 IN	R8	R7 *
NAB SYSTEMS									
1	1		P1	CH 1 OUT			CH 1 IN		R1 E1
2	2		P2	CH 2 OUT			CH 2 IN		R2 E2
3	3		P3	CH 3 OUT			CH 3 IN		R3 E3
4	4		P4	CH 4 OUT			CH 4 IN		R4 E4
4	5		P5	CH 5 OUT			CH 5 IN		R5 E5
6	6		P6	CH 6 OUT			CH 6 IN		R6 E6
7	7		P7	CH 7 OUT			CH 7 IN		R7 E7
8	8		P8	CH 8 OUT			CH 8 IN		R8 E8

*Simultaneous erase and record is not provided for Dynatrack. New or bulk erased tape should be used for Dynatrack recording.

INTERFACE INFORMATION

All input and output connections and circuitry of the Professional Audio Tape Recorder are based on standard operating procedures in the recording industry. Standard 3-wire XL type connectors are used for the signal inputs and outputs. Cables should be made up in conformance to standard practice as to length, shielding, etc., with connections as in the following paragraphs.

Signal Input

To bridge a balanced studio line, connect the line to pins 2 and 3 of an XL male plug (figure 15) and insert it into the SIGNAL IN socket. Connect the ground to pin 1. Input level of -10 to +8 dbm based on the signal level in a 600-ohm line may be employed as a signal source. The load is approximately 20,000 ohms.

An unbalanced line source should be connected to pins 2 and 3 of the connector. Ground should be connected to pins 1 and 2. See figure 15. This provides a 20,000-ohm bridging input for signal levels as above. Pin 3 could be grounded rather than 2 without degradation of performance, but pin 2 is suggested as first choice in the interest of consistency.




Figure 15. Signal Input Connector Wiring

Signal Output

The output signal for connection to line facilities is to be fed from the male SIGNAL OUT connector to an XL type female connector on the outgoing cable. Use pins 2 and 3 for the signal output with pin 1 as ground. See figure 16. A balanced line may be fed from 2 and 3, or an unbalanced line may be fed by grounding either 2 or 3. In the interest of consistency, it is suggested that 2 be employed as ground and 3 as the signal lead.

Two switches are provided on the rear panel of the electronics just above the SIGNAL OUT connector. The OUTPUT IMPEDANCE switch provides for selection of 150 or 600 ohms output line impedance and the TERMINATION switch provides for proper terminating impedances for either 150 or 600 ohms, if needed. If the outgoing line is properly terminated elsewhere, set this switch to the OFF position.

Note that the positions of these switches will affect the reading of the VU meter as much as 2 db. This meter is normally calibrated to read the proper levels in a +4 dbm 600-ohm line. It may be recalibrated by adjusting resistors in the line amplifier board. A chart of values for the selectable resistors is given under the discussion of this board in the Functional Description.




Figure 16. Signal Output Connector Wiring

Remote Meter

A remote VU meter may be connected to pins 1 and 4 of this connector. See figure 17. It is essential that it be "built out" with a resistor network identical to the one set up on the Line Amplifier Board for the local meter and as shown in figure 17. Select the values of R1 and R3 from table 10 for the proper line operating level.

The remote meter will indicate the same signals, input or output, as the local VU. It will not give indications of bias and erase current. Power to illuminate lamps in the remote meter is available on pins 3 and 6. Maximum drain should be 150 ma at 28 volts. A resistor is provided for in the Meter and Power Supply Assembly (R10) which may be selected to provide different degrees of lamp brightness.




Figure 17. Remote Meter Connector Wiring

Pilot and Loudspeaker

This connector is provided to permit insertion of a reference tone, subsonic or supersonic, onto the track being recorded and to permit extraction of the tone on playback without having the level of either the recorded or reproduced pilot affected by adjustment of the front panel record or playback gain controls. The pilot tone to be recorded is applied at pin 1 with grounded return on 4. The reproduced pilot is on 2 with grounded return on 5. See figure 18.


This connector is also used to provide signal to an external monitor loudspeaker if desired. The speaker is to be connected to pins 3 and 6, and will operate at reasonable monitoring volume level when the VU is set up for +4 dbm lines. It will be 4 db louder when the VU is set for +8 dbm lines and so on. A simple attenuator may be installed on the speaker to reduce its volume.

Phones

Monitor earphones may be plugged into the PHONES jack on the front panel. High impedance phones are to be used. Neither side of the circuit is to be grounded. The phones will monitor either the input or tape playback, the same as the VU meter, which is the signal being fed to the output line.

CAUTION

A ground on either earphone lead will upset the characteristics of the line amplifier so that it will feed improper level to the meter and line and may go into oscillation.



1091

Figure 18. Pilot Connector Wiring

Auxiliary Ground

A ground terminal is furnished on the transport frame. It may sometimes be desirable to connect this to a good ground to minimize electrical noise, although this is generally unnecessary if the power cord ground is sufficiently noise-free.

OPERATING CONTROLS AND DETAILS

In this section are considered all controls which are directly accessible from the top surface of the transport and from the front surface of the electronic assemblies. Internal adjustments to be made with screwdriver or wrench are discussed in the Alignment and Adjustment section.

TAPE TRANSPORT CONTROLS

The normal operating controls are located in the lower right-hand corner of the transport. See figure 7. These five illuminated pushbuttons control all tape movement through a system of safety interlock relays that prevent malfunction because of improper operation. Any button can be pushed in any sequence, at any time, with complete safety to the tape and machine.

PLAY Button

This causes the transport to move the tape at normal forward or record speed under capstan speed control. The transport can be placed in PLAY at any time from any tape mode. For recording, both the PLAY and RECORD buttons must be pushed simultaneously when tape is either at standstill or in the normal forward, play mode.

FORWARD Button

Activates the high speed tape advance in the forward direction. The fast forward mode may be initiated without pressing the STOP button. In fast forward, the tape lifters are activated and the head shield opens. The tape lifters may be manually overridden to allow tape to be heard. When the STOP button is operated from this mode, dynamic braking is used to stop tape, then a slight holding torque is applied to maintain tape tension.

NOTE

Magnetically operated reed switches, operated from a direction sensitive vane under the takeup reel turntable, control the dynamic braking and electrical switching when the transport is taken out of FORWARD or REWIND mode. This vane is a sensor to determine the direction the tape is traveling. The appropriate reed switch then activates relay control circuits which place the transport in either FAST, FORWARD, or REWIND, preliminary to the STOP mode, depending upon the original direction.

STOP Button

This button stops all tape motion from any mode of operation. It also indicates when the transport is ready for operation. It is illuminated when the transport power is on and tape is threaded in the tape path. Without tape in the tape path, the unit will not operate and this button will not be lit. When the STOP button is activated while tape is in the high speed mode, dynamic braking is applied until the tape stops. Then, the transport goes into the STOP mode and a light holding torque is applied by both motors to maintain tape tension.

REWIND Button

Tape may be put into high speed rewind from any other mode of operation, even from fast forward, without danger of tape breakage. Tape lifters on both heads operate during high speed rewind and the headshield opens. The tape lifters may be manually overridden if you want to hear the tape.

RECORD Button

This button connects the recording circuits to the record head. To operate, the button must be pushed at the same time as the PLAY button is pushed. This must be done when tape is either at standstill or running in PLAY mode. Stopping the tape, or changing the tape mode of operation, automatically deactivates the recording circuits; and the RECORD and PLAY buttons must be pushed again to resume recording. To complete the recording circuit, the recording amplifier switch on the applicable electronic assemblies must be in RDY position.

The remaining controls are mounted in the lower left-hand of the transport.

POWER Switch

AC power to the entire recorder is controlled by this switch.

NOTE

The tape transport will not be energized and the STOP button will not light until tape is threaded into the tape path.



Do not turn the power off when the transport is in a fast tape travel mode (REWIND or FORWARD). This could throw a tape loop because the dynamic braking will not operate.

A-B OUTPUT Transfer Switch

This pair of pushbuttons provides for simultaneous transfer of the signal outputs of each electronics assembly from the input line to tape playback, or vice versa. The A button sets all channels to monitor the input signal. The B button transfers monitoring of all channels to the output signal.

RUNOUT Switch

NOTE

Apparatus associated with this switch is not normally furnished. It must be specially ordered.

This switch controls the actions of a photo sensor in the tape path. It can be set to automatically stop the tape, or to automatically rewind the tape. The switch circuits will also automatically start another tape machine. To activate the circuits, punch a 1/4 inch hole in the tape, or remove the oxide with solvent 3/8 inch above the lower edge of the tape at the point where one of the automatic operations is desired. When the hole passes the sensor, the tape will automatically stop, or rewind, depending upon the position of the switch. When the switch is in the center (NORMAL position), the automatic feature is inactive. When no hole is made in the tape, the unit will automatically shut off when the tape runs out.

SPEED Switch

The SPEED switch selects either of the two speeds at which the machine operates. These are normally 7 1/2 and 15 ips; however, other speed pairs are available.

CAUTION

This switch should not be operated with the capstan motor running. Power must be off or tape not threaded.

BALANCE Switch

This 3-position switch changes motor torque factors to compensate for reels of different weight and/or size. When both reels are identical, the switch remains in the middle, or BALANCED position. If the left reel is larger or heavier, the switch should be in the left position. If the right reel is larger or heavier, place the switch in the right position.

TAPE TRANSPORT, TAPE HANDLING COMPONENTS

The following tape components are in the capstan handling assembly area. See figure 19.

Reversing Idler

Tape is threaded around this free-wheeling idler, which helps provide an extremely short path of unsupported tape. Ridges in the idler provide for air passage during high-speed tape movement, so that the tape hugs the idler.

Editing Index

The tri-colored bars and dots on top of the reversing idler are used for precision editing, as described in the section on editing.

Head Assembly

All head stacks, erase, record and play, are mounted on a single plug-in precision plate which is mounted on the transport casting beneath this head cover. The trim plates must be removed in order to remove the head assembly.

Azimuth of record and playback heads may be adjusted by removing the head cover plate located between the capstan and reversing idler.

Tape Lifters

The tape lifters automatically move tape away from heads during high-speed tape travel to reduce head wear and cut chatter. They are electrically interlocked with the playback head shield door so that the latter opens to make room for the tape when lifters move it away from heads.

The tape lifter may be manually overridden by pressing the tape lifter and override lever. This restores the tape against the head so that it may be heard.

Head Shield Door

The head shield door provides for hum reduction and automatically drops away from head during high-speed tape travel and whenever tape is lifted from tape path. This allows easy removal of tape for editing, etc.

Capstan

The differential capstan is the basis of the patented Isoloop system for transporting tape with extremely low flutter and wow. Its function and operation is described in the General Description Section.




Figure 19. Tape Drive Components

Capstan Idler (Incoming)

This idler is designed to clamp the tape to the smaller diameter parts of the capstan. The capstan thereby unwinds tape from the supply reel and feeds it into the loop. In starting, this idler moves in slowly after initial contact so as to gently accelerate the tape to running speed. Only after tape has had sufficient time to get up to speed does the outgoing idler function.

Capstan Idler (Outgoing)

This idler pulls the tape through the head assembly at a slightly higher rate than the tape is fed in because it presses the tape to the capstan at its larger diameters. This maintains a constant tape tension across both heads, but the tension does not exceed the stretch capabilities of the tape. It is moved into position directly without retardation of dashpot as provided on the ingoing idler.

Tape-Threaded Sensor

This photoelectric circuit across the tape path provides both convenience and safety. Whenever the tape breaks the light beam, a slight holding torque is applied to the reels to maintain tape tension. When there is no tape in the path, the reel motors are deenergized, the tape turntables are free-wheeling, the head cover opens, and all pushbuttons are deactivated. This allows for easy removal of the tape for splicing. Also, when the end of the tape is reached, the motors stop quickly, minimizing tape whip-around.

Edit Post

This is a sharp edge that puts a crimp in the tape when it is pressed against the post. When used in conjunction with the editing aid on the reversing idler, it provides for easy, trouble-free editing.

Reel Holders

Standard reel holders are supplied for holding down 10-1/2 inch NAB reels. Rotating the upper portion of the holder, when a reel is in place, locks the reel on. This is useful when the machine is mounted vertically. Locking is not necessary when transport is horizontal or at a slight angle. Removal of the large center screw permits changing to different hub types. Only 1/4-inch systems are supplied with NAB reel holders, which can be removed by rotating the center post. When the NAB holder is removed, the center post will accommodate the small plastic cinema reels.

ELECTRONICS ASSEMBLIES


Electronic controls, except for the record control, are located on the electronics assembly for each channel. These controls are shown in figure 20 and their description follows.

RECORD LEVEL Control

This adjusts the signal level recorded on the tape. It may be adjusted through a line input level range of -20 dbm to +8 dbm (600 ohm line). To monitor the signal audibly, or to read the level of the incoming line, the METER switch is set to SIGNAL and the OUTPUT SELECT set to A. After the level is properly adjusted, the knob may be locked by turning the ring behind it in a clockwise direction.

REPRO. LEVEL Control

This adjusts the playback gain. It is a locking control. It is not necessary to calibrate a level setting for this control by employing a standard tape and then locking the control in place. This is because the METER switch has a calibrate (CAL.) position which substitutes a fixed pad for the REPRO LEVEL variable gain control whenever it is desired to calibrate levels. The REPRO LEVEL control is only in the normal tape playback path. The OUTPUT SELECT button B must be pressed to transfer the meter and output line to the playback circuit.



1166

Figure 20. Electronic Controls

REC. SELECT Switch

This has three positions affecting only the record circuits.

1. RDY. In this position, the circuits for the particular channel are ready to record. If the RECORD and the PLAY buttons on the transport or its remote control unit are pressed simultaneously, the record circuits will be activated and the red REC lamp will light. In an NAB configuration, the eraser and the record head for this track will be activated. In the Dynatrack configuration, no eraser is activated, but both tracks of a single channel will be energized.
2. SAFE. In this position, the erase and record circuits will be locked off so that accidental erasure or damage to a previously recorded tape will not occur should the record mode be selected at the transport or remote control.
3. O.DUB. This is the overdub position. This prevents the record and erase circuits from being energized and substitutes the record head in place of the normal playback head for this track in the NAB configuration. In the Dynatrack setup, it substitutes the HI record head in place of the normal HI playback head. The LO track remains unaffected. In the overdub position, a performer can listen to a previously recorded track while adding a new part in perfect synchronism on another track. This is because the signal he is hearing is being played from a record head in the same stack as the head he is using to add the new recording. There is thus no time separation between the two.

METER Switch

This switch has four positions affecting the function of the meter and influencing the signal output level.

1. CAL. This is a calibrate position. When it is selected, the REPRO LEVEL gain control is removed from the playback amplifier and a fixed attenuator is substituted. Thus, a known overall gain can always be checked as a reference. An adjustable gain control in the preamplifier is set to give proper meter level readings from a standard reference tape.

The switch may then be set to the SIGNAL position where the variable REPRO LEVEL control permits operating playback gain adjustments, as necessary.

2. SIGNAL. In this position, the meter monitors either the input signal, A, or the playback signal, B, depending on which OUTPUT SELECT indicator is lit, A or B. Similarly, the signal fed to the outgoing line (SIGNAL OUT) is either A or B.

3. **ERASE.** In this position, the meter shows a steady deflection, depending upon the magnitude of the high frequency current in the erase head when in the standard NAB configuration. In the Dynatrack configuration, the meter reads the magnitude of high frequency bias current in the LO track. The output signal to the line remains under the control of the A-B OUTPUT SELECT switches the same as described above under SIGNAL.
4. **BIAS.** In this position, the meter reads the magnitude of high frequency bias current in the regular NAB record head or the HI track record head in the Dynatrack system.

OUTPUT SELECT Switches

These consist of the illuminated A-B buttons mentioned above. Whenever the METER switch is in any position other than CAL, these buttons determine the source of signal to be fed to the outgoing line (SIGNAL OUT connector). When the A button is pressed and the A lamp lights, the input signal is being monitored and is the signal output. When the B button is pressed and the B lamp lights, the outgoing signal is then connected to the playback circuits to monitor the signal reproduced from tape. The A-B transfer buttons on the transport can switch all channels at the same time, but individual channels remain under control of their A-B buttons.

A small slide switch on the Line Amplifier circuit board will inactivate the automatic A-B transfer, if desired. When inactive, the transfer is solely under control of the A-B buttons on the particular electronics assembly.

REC. Indicator

This is a recording indicator lamp to show when the record and erase circuits are energized. It is under control of the RECORD button on the transport but may be locked out of service by placing the REC. SELECT switch in either the SAFE or 0. DUB position rather than its normal RDY. position.

PHONES Jack

This jack is provided to drive a high impedance earphone, which bridges across the output signal line. Since this is usually operated as a balanced circuit, neither side of these phone may be grounded.

This description of the controls on the electronics module covers all controls and indicators normally referred to in the course of operating the recorder. The front cover door hinges down to reveal a series of plug-in electronic boards which contain a number of screwdriver adjustable components. These are normally not adjusted by operating personnel. Maintenance personnel employ them to trim a machine into peak performance. They are referred to under Alignment and Adjustment, Routine Maintenance, and Circuit Descriptions.

GENERAL OPERATING PROCEDURES

PRELIMINARY

Slide the plate (see figure 7) covering the slide switches to the left so that it covers the POWER switch and reveals the three slide switches. Set the SPEED switch to either HIGH or LOW as desired. Set the RUNOUT switch to its mid-position, NORMAL. Identical large reels should be used on both reel spindles. If this is done, set the BALANCE switch to its mid-position. Slide the switch cover to the right, revealing the POWER switch and A-B OUTPUT buttons.

THREADING

Threading the recorder is extremely simple, as there are no compliance arms or other mechanical devices in the tape path. See figure 21. Also, there is no tension on the tape until it breaks the photoelectric circuit in the Isoloop assembly, so the reels are free-wheeling. To thread, first push the POWER button to turn the machine on. Place a roll of tape on the left hand spindle in such a manner that the reel rotates counterclockwise when tape is unwound. Take the tape from the supply reel, drop it between the capstan and the incoming idler, past the record head, around the reversing idler, past the play head (the head shield is open), between the capstan and outgoing idler, then onto the takeup reel. Thread the tape onto the reel hub so that it will wind in a counterclockwise direction. As the tape breaks the photoelectric light path after the outgoing idler, a slight holding torque is applied which takes up any slack in the tape. The transport is now ready to operate.

Observe that the control buttons function in the manner intended and that they are each illuminated in their operating mode. Observe that the playback head cover door closes when the machine is started in the play or record mode and that it opens when the tape lifters raise tape off the heads in fast forward or rewind modes. Observe that in standby with tape threaded in place, the head cover door will remain either open or closed when operated manually. Observe that this door, if closed in standby, will open if tape is lifted from its running path at the right hand guiding system prior to reaching the takeup reel.

MONITORING

All electronics assembly adjustments described in the following paragraphs are for a single recording channel. In multichannel machines, perform the procedure for each channel of electronics.




Figure 21. Tape Threading

Signals to be recorded and reproduced can be monitored by: (1) the VU meter on the electronics assembly, (2) an earphone (high impedance, ungrounded) plugged into the PHONES jack, (3) a loudspeaker connected directly to the PILOT connector at the rear of the electronics assembly (terminals 3 and 6), or (4) from the signal output connector on the rear panel.

To monitor the recorder input signal, set the METER switch to SIGNAL and press OUTPUT SELECT button A. The signal amplitude will be under control of the RECORD LEVEL knob.

To monitor signals reproduced from recorded tape press the OUTPUT SELECT button B. The REC. SELECT switch should be in either RDY or SAFE positions. With the METER switch in the SIGNAL position, the REPRO. LEVEL knob will determine the loudness of the monitored signal.

To determine the true magnitude of signal level on the tape, place the METER switch in the CAL. position. The loudness and meter reading are then determined by a fixed calibrated amplifier gain rather than the variable REPRO. LEVEL control. The A-B OUTPUT transfer buttons on the tape transport can switch all channels of a multichannel system at the same time.

RECORDING

Set the RECORD LEVEL knob and the REPRO LEVEL knob to minimum (fully counterclockwise).

Set the REC. SELECT switch in the RDY. position. In Dynatrack systems, previously degaussed or new tape must be used. In NAB systems with erase heads, new, degaussed, or previously recorded tape may be used.

Set the METER switch to the SIGNAL position.

Press OUTPUT SELECT button A.

Slowly increase the RECORD LEVEL control until the meter peaks at +2 VU on the loudest peaks on input program material. The signal should be clearly heard in the monitor system. Have the program source cut off by fade or switching. Listen for acceptability of residual noise, particularly low frequency hum. For truly critical applications, for which this machine is designed, a vacuum tube voltmeter should be used to determine residual circuit noise. Recorder-contributed noise in this test will generally be well below external circuit noise. Have the program feed restored at the former level.

To start recording, simultaneously press the PLAY and RECORD buttons on the tape transport. These two buttons should light and the red REC. indicator on the electronics panel should also light.

Press OUTPUT SELECT button B. Slowly increase the REPRO LEVEL control until the signal is audibly and visually the same loudness as the input signal. This can be easily determined by alternately pressing the A and B buttons. Listen critically on a good monitor speaker system to be certain the signals sound identical in either the A or B position after their levels are set as closely the same as possible.

Cut off the input signal and listen for noise. No increase in hum should be observed in the B position when compared to the A position. In NAB systems, tape noise should be the only additional source of noise observable in playback. In Dynatrack systems, even this should be extremely difficult to observe. Noise measurements are outlined under Alignment and Adjustment.

Press the STOP button. The tape should stop. The REC. indicator should go out.

If A-B transfer from the transport is not wanted, open the front panel cover of the electronics assembly, and position the upper slide switch on the line amplifier board in slot 6 to the OFF position. A-B switching is then solely under control of the A-B buttons on the electronics panel.

PLAYBACK

Playback is accomplished simply by pressing the PLAY button on the tape transport. The B output must be selected.

When the recorder is used for reproducing a previously recorded tape, it is wise to set the REC. SELECT switch in the SAFE position. Should the RECORD and PLAY buttons be pressed simultaneously in error, the recording circuits will still be locked out and the tape protected against accidental erasure.

OVERDUBBING

When ordered, the overdub feature is provided on the playback preamplifier boards. It is controlled by the REC. SELECT switch.

It provides a means of adding a second audio track in synchronism with a first track (or first set of tracks, depending on the number of channels built into the machine).

Consider a two-track NAB machine as an example. We will call the channel numbers 1 and 2. An orchestra is recorded on track number 1 and it is desired to add a synchronized vocal in track number 2 which has been left unrecorded. If track number 1 is played into earphones for the singer's benefit in the normal way from the regular playback head, the singer's voice will be recorded on track 2 displaced on the tape from the orchestra recording by the linear distance from the playback head stack back to the record head stack. The two can therefore never be played in synchronism because of the scanning time differences which arise.

Therefore, it is necessary to play the orchestra track (No. 1) from the No. 1 record head, substituting it for the No. 1 playback head. The overdub preamplifier provides proper gain and equalization to accomplish this when the REC. SELECT switch is set to the 0. DUB position. Furthermore, this position of the switch locks off its recording electronics as in the SAFE position so that the orchestra track may not be destroyed. The singer's track, No. 2 is left in the RDY. position and the recorder is started in the RECORD mode. The singer then sings in synchronism with the orchestra and both tracks No. 1 and No. 2 are vertically oriented so that there is no time displacement between them. When the singer has finished recording his part, both tracks may be played back through the regular playback head assembly by placing both No. 1 and No. 2 REC. SELECT switches to SAFE.

ERASURE

Erasure is automatic on NAB configurations, since the electronics module is constructed to feed two high-frequency circuits. One of these is the record head bias requirement and the other is the eraser. In the Dynatrack system, the

erase power source becomes the bias source for the second track required by this two track system. To take full advantage of the increased dynamic range and lower noise level provided by the 3M recorder, all recording should be done with new tape, or tape that has been very carefully bulk erased.

EDITING


Due to the basic simplicity of the Isoloop drive system, plus the advantages of dynamic braking, automatic tape tension and release, and the unique editing feature which is provided on the reversing idler, tape editing is extremely fast, accurate and easy.

To locate the cutting point, follow the normal procedure of "rocking" the reels to and fro by rotating the reel knobs. Because there is only a slight holding torque on the motors, this requires very light effort. Once the cutting point has been found, note the position of one of the colored edit dots on the top of the reversing idler in relation to one of the markings on the scale (figure 22-A). Now move the tape forward by hand approximately 2/3 of a turn of the reversing idler until an edit line of the same color as the dot is opposite the same scale marking (figure 22-B). Now, using your forefinger, press the tape against the sharp edge of the edit post (figure 22-C). This puts a light crimp in the tape, precisely marking the point of cutting. Lift the tape out of the tape path, deenergizing the reel motors and allowing the tape to be completely slack (figure 22-D). After making the splice, simply drop the tape back in the tape path. The holding torque is again applied automatically. You are now ready to advance tape to the next editing point.

This simple yet highly precise editing system eliminates completely the need for grease pencils and other makeshift marking devices which require the tape to be cleaned after editing.


NOTE

When extensive editing is to be done, the REC. SELECT switches on the electronics assemblies should be placed in SAFE position to eliminate any possibility of accidental erasure of the tape. because of inadvertent pressure of the RECORD button.




A

MOVE SIMILAR
COLORED LINE
TO THE POSITION
OF THE DOT ON
THE FIXED SCALE



B



C

MARK THE TAPE
WITH THE INDEX
FINGER AND
REMOVE FROM
THE TAPE PATH



D

1177

Figure 22. Tape Editing

ALIGNMENT AND ADJUSTMENT

TAPE TRANSPORT

The tape transport has been factory aligned for peak performance. With use it will occasionally be necessary to undertake routine inspection of the machine and check certain adjustments. The following information provides a procedure for thorough check of the tape transport. After the user has followed this procedure a few times, it may be found that certain steps may be checked at less frequent intervals. Location of transport adjustments is shown in figures 23 and 24.

1. Remove the six screws that hold the transport cover plate in place and remove the cover plate. The bottom of the cover is held in place by a lip. No reels are to be on machine.
2. Connect the input power cord to the output of a 7-1/2-amp Variac set to zero volts.
3. Increase the Variac output voltage; at approximately 90 volts, relay K1 should be heard to operate, the POWER button should light, and the tape sensor light should come on. If this does not happen, press the POWER button.
4. Continue to increase the Variac voltage until its dial indicates 115 volts. All five function control buttons should be dark and no motors, including the fan, should be operating. The illumination level of the POWER button should not change.
5. Place a piece of opaque material in the tape path between the tape sensor light and the tape-threaded sensor. This will be referred to hereafter as the "tape sensor mask." The STOP button should light. The takeup motor should rotate at approximately 55 to 80 rpm in a counterclockwise direction. The rewind motor should rotate slightly faster (approximately 60 to 85 rpm) in a clockwise direction. The capstan motor should move forward to engage the flywheel tire and it should start turning, driving the capstan in a counterclockwise direction. The fan should also start at this time.
6. Remove the tape sensor mask. The STOP button light should go out and all motors should stop. The capstan motor should move so that its shaft no longer contacts the tire on the flywheel.
7. Reinsert the tape sensor mask. Move the capstan motor SPEED switch to HI. Observe that it runs at high speed. Remove the tape sensor mask. Move the SPEED switch to LO. Reinsert the tape sensor mask. Observe that the capstan motor runs at half




Figure 23. Tape Transport Adjustments, Top View




Figure 24. Tape Transport Adjustments, Bottom View

- speed in the same direction. Remove the tape sensor mask. Return the switch to the HIGH speed position. Reinsert the tape sensor mask.
8. Set the capstan motor fine-speed screw (figure 23) so that it does not depress the foot lever from its highest position.
 9. Check the adjustment of the nut on the capstan motor solenoid coupling rod (figure 24) so that, when energized (by the tape sensor mask), the capstan motor shaft makes just sufficient contact with the flywheel tire to bring the capstan up to speed.
- CAUTION**

Do not stall the flywheel while permitting the motor to run since the rubber may be quickly damaged at the point of contact.
10. A neon indicator operated half wave from the same frequency source as the capstan motor or a stroboscopic lamp triggered from the power line frequency should now be used to check the capstan speed by lighting the strobo disc. A simple but effective circuit is shown in figure 25. The capstan should appear to run slow; that is, the strobe pattern appears to rotate very slowly in a clockwise direction. Use an improvised wire pointer as a reference and observe how many dark or light elements appear to pass beneath it per minute. Use table 4 to determine speed error with a 48-element strobe wheel on the capstan.




Figure 25. Example of Simple Stroboscope Lamp

Table 4. Capstan Speed Error (for 48 element strobe wheel)

DRIFT ELEMENTS PER MINUTE	SPEED ERROR-PERCENT	
	AT 7-1/2 IPS	AT 15 IPS
2	0.056	0.028
4	0.112	0.056
6	0.168	0.084
8	0.224	0.112
10	0.300	0.150

11. Adjust the capstan motor fine speed screw for minimum drift. This should be less than 4 elements per minute, either clockwise (speed too slow) or counterclockwise (speed too fast), when motor is driving the capstan at 15 ips, or a maximum of 2 per minute at 7-1/2 ips. As the adjusting screw is run in, some drive mechanisms show an initial on-speed indication followed by an overspeed which, with further running in of the screw, restores the speed to normal. The latter is the proper adjustment.
12. Remove and reinsert the tape sensor mask several times to assure that the motor returns to the same seated position by observing if any speed change occurs after such cycling. If there is any change, inspect the solenoid system to be certain linkages are not binding or the solenoid failing to bottom. Never adjust the motor pressure to be so heavy that the solenoid cannot seat fully.
13. Set the Variac voltage to 105 volts and repeat the previous step. If OK, return the Variac voltage to 115 volts.
14. Remove the tape sensor mask.
15. Push in the plunger of the incoming capstan pressure roller solenoid by hand (left side of capstan) and back off the pressure roller linkage adjusting screw until the pressure roller does not contact the capstan.
16. Repeat for the outgoing capstan pressure roller.
17. Insert the tape sensor mask and press the PLAY button. The PLAY button should light, and the STOP button should go out. The incoming capstan pressure roller should swing in toward the capstan. Approximately 1/2 second later, the outgoing capstan pressure roller should swing in toward the capstan. In the initial interval, the supply reel motor should accelerate in the rewind direction and the takeup reel motor should quickly race to a high speed. After the 1/2 second initial

interval, the torque on these motors should be noticeably reduced when the outgoing capstan pressure roller swings in. Because both adjusting screws were backed off, neither capstan pressure roller should rotate from contact with the capstan. The above time delay should be about 1 second on 1-inch machines.

18. Adjust the incoming linkage screw until the incoming pressure is just positively driven by the capstan. Give the screw one more full turn in the same direction. Be certain that the solenoid plunger seats completely on repeated operations.
19. Repeat the previous set for the outgoing pressure roller except give the screw a final $3/4$ turn.
20. Remove the tape sensor mask, stopping all motors and releasing the pressure rollers.
21. Reel torque measurements are performed next. For this purpose, it will be necessary to employ a 10 ounce or 1 pound spring scale, preferably with a hooked end, and an empty 10-1/2 inch reel. Drill two holes in one of the reel spokes large enough to accept the scale hook. One of these should be at 2 inches from the center of the reel, and the other at 5 inches from the center of the reel. Use the outer one for heavy torque measurements, the inner one for the low torque measurements.

Place the special reel on the supply reel side and hook the spring scale into the 5-inch radius. Holding the spring scale firmly in place, reinsert the tape sensor mask and press the REWIND button. The STOP button light should go out and the REWIND button should light. Observe the ounce inches of stall torque. See table 5. Remove the tape sensor mask.

NOTE

Table 5 converts the spring scale reading to motor torque. For values not shown in the table simply multiply the spring scale reading in ounces by the radius in inches to find the motor torque in ounce inches.

Table 5. Spring Scale Reading to Motor Torque Conversion Table

AT 5-INCH RADIUS		AT 2-INCH RADIUS	
SCALE READING	MOTOR TORQUE	SCALE READING	MOTOR TORQUE
4.0 oz.	20 oz. in.	3.00 oz.	6.0 oz. in.
4.2	21	3.25	6.5
4.4	22	3.50	7.0
4.5	23	3.75	7.5
4.8	24	4.00	8.0
5.0	25	4.25	8.5
5.2	26	4.50	9.0
5.4	27	4.75	9.5
5.6	28	5.00	10.0
5.8	29		
6.0	30		
6.2	31		
6.4	32		
6.6	33		
6.8	34		
7.0 oz.	35 oz. in.		

22. Remove the special torque measurement reel from the supply side and place it on the takeup side. Place the spring scale at the 5-inch radius. Replace tape sensor mask and, holding the spring scale firmly in place, press the FORWARD button. The STOP button light should go out and the FORWARD button should light. The torque should be the same as for the rewind motor.

NOTE

Torque of either motor will vary somewhat with angular position due to commutation, but the exact value is not critical. Plus or minus 20% is acceptable.

23. Remove the tape sensor mask, stopping the motors. Reinsert the tape sensor mask. Press the PLAY button. The starting torque of the takeup motor should be approximately as listed in table 6 for initial period until outgoing capstan pressure roller operates. The torque should then reduce to running torque values listed in table 6.

Table 6. Takeup Motor Torques

TAPE WIDTH	STARTING TORQUE	RUNNING TORQUE
1/4 in.	12 oz. in.	8 oz. in.
1/2 in.	24 oz. in.	8 oz. in.
1 in.	35 oz. in.	8 oz. in.

24. Remove the tape sensor mask. Put the special reel and spring scale on the supply reel spindle, using the 2-inch radius hole. Replace the tape sensor mask. Press the PLAY button. The starting torque should be as listed in table 7, reducing to the running torque listed in table 7 after operation of outgoing capstan pressure roller.

Table 7. Supply Motor Torques

TAPE WIDTH	STARTING TORQUE	RUNNING TORQUE
1/4 in.	7 oz. in.	5 oz. in.
1/2 in.	10 oz. in.	7 oz. in.
1 in.	15 oz. in.	10 oz. in.

25. The required torques will generally be realized if the sliders on R61 and R62 are set to maximum resistance for 1/4-inch tape, midway for 1/2-inch tape, and 3/8-inch from minimum end for 1-inch tape.
26. Remove the tape sensor mask. Remove the spring scale and reinsert the tape sensor mask. Check that the LARGE REEL switch is in the center position. Hold the takeup motor by hand so that it cannot turn. Press the FORWARD button. The supply reel motor should rotate slowly in a counterclockwise direction. Slide the LARGE REEL switch to the right. The motor should stop. Slide it to the far left. The motor should run, as in the center position. Remove the tape sensor mask. Place the LARGE REEL switch in the center position.

27. Replace the tape sensor mask and repeat the previous step, holding the supply reel motor and pressing REWIND button. The takeup reel motor should rotate slowly in a clockwise direction. Slide the LARGE REEL switch to the left. The motor should stop. Slide it to the right. The motor should run, as in the center position. Place the switch in the center position and remove the tape sensor mask.
28. Press the POWER button and shut off the power. Connect a DC volt-meter (50 volt scale) from the collector (stud) of the 2N174 regulator transistor (Q60) to ground. Be careful not to ground the test lead. Press the POWER button. It should show 26 to 28 volts. Insert the tape sensor mask and press the PLAY button. Then press the FORWARD button, and then the REWIND button. The voltage should remain at 26 to 28 volts. Reduce the input line voltage to 105 volts and repeat. Only below 105 volts input should the voltage ever drop below 26 volts. Reset the input to 115 volts.
29. Place a reel of tape on the transport, and thread the tape as described under General Operating Procedures.
30. Press the PLAY button. The head cover door should close smoothly within 3/4 second. The tape should be driven by the capstan and wound up by the takeup reel. In starting, it should accelerate smoothly without snapping from the supply reel or throwing a loose loop within the closed loop area. When properly adjusted, the incoming capstan pressure roller should move quickly to contact the tape and then slowly seat under the control of the dashpot, thereby gently increasing the tape pressure on the capstan and giving it a gentle acceleration. Generally, the dashpot must be adjusted to maximum damping. The fork tangs (as shown in figure 23) may be bent slightly, but carefully, to provide proper puck operation. The outgoing capstan pressure idler operates only after the tape is up to speed.
31. Press the STOP button. The head cover door should open instantly and the tape should stop. A reverse motion for an inch or two is permissible.
32. Press the FORWARD button. The head cover door should be open and the tape lifters should operate. Wind the tape to within 100 feet of its end. Press the STOP button. The FORWARD lamp should go out and the REWIND lamp should light, indicating reversed torque, thus bringing the tape to a standstill, at which time the REWIND lamp goes out and the STOP button lights. The tape lifters should drop back to normal.

33. Press the PLAY button. The tape should start as smoothly as it did at the beginning of the reel. If the tape does not start smoothly because the incoming roller is engaging too slowly, the adjustments in step 30 should be repeated until smooth operation is obtained. An optimum point of sufficient puck pressure and damping of puck engagement must be reached for best tape handling. After adjustment, rewind the tape and repeat all steps from 30 on.
34. Press the REWIND button. Somewhere in the middle of the reel, press the STOP button. The REWIND lamp should go out and the FORWARD button should light, indicating reversed torque is applied. When standstill is reached, the FORWARD lamp should go out, and the STOP button should light, and the tape should come to a stop. A few inches overshoot in the reverse direction is permissible.
35. Press the REWIND button. When tape is up to relatively high speed, press the PLAY button. Reverse torque is applied and, when the tape stops the machine should immediately go into the RUN mode, the tape lifters drop back, and the head cover door closes smoothly.
36. Repeat the previous step except from the FORWARD mode.
37. When in RUN mode, press the REWIND button. The pressure rollers should drop out, the head cover door should open quickly, the tape lifters should operate, and the tape should go into rewind.
38. On tape transports with the runout feature, wash off the oxide from the top half of the tape for about one inch. Head cleaning solvent may be used. Place the RUNOUT switch in the STOP position. Rewind the tape about ten feet, and then press the PLAY button. When the clear spot uncovers the incoming photocell, the machine should stop.

NOTE

All tape transports have the RUNOUT switch; but unless this feature is ordered separately, the associated circuit is not included. Its inclusion can be determined by checking for the light-sensing photocell between the two incoming tape guides.

39. Put the RUNOUT switch in the REWIND position. Rewind the tape ten feet and press the PLAY button. When the clear spot uncovers the incoming photocell, the tape should immediately go into the REWIND mode.

40. Stop the tape. Put the RUNOUT switch in its normal (middle) position. Press the PLAY button. The tape should continue in the RUN mode, past the clear spot without going into STOP or REWIND.
41. Stop the tape and then press the PLAY button. While the transport is in RUN, press the RECORD button. Nothing should happen. While holding the RECORD button depressed, press the PLAY button again. The RECORD button should light. Press the STOP button. The PLAY button and the RECORD button lights should go out.
42. Observe all white relay covers and put the transport through all normal functions looking for sparking contacts. Arcs may be seen through the translucent covers. Particularly look for sparking of contacts 1 and 9 of K1 which controls capstan motor power. Very light arcs are permissible but a bright arc indicates faulty suppressors C4 and R23. These must be functioning or the relay will fail.
43. Check the time required for the head cover door to open and to close as demanded by various functions described above. It should take from 1/2 to 3/4 seconds to close but should open immediately. Adjust the connected dashpot for proper closing time.
44. The tape lifters must swing out fully whenever the tape is in REWIND or FORWARD mode, or in the process of stopping. When released, they must fall back fully so as not to interfere with normal tape motion over the heads. Test their action at the start of a reel, in the center of a reel, and at the end of a reel to be sure they always operate fully and release fully. Check that they do not chatter when the tape reverses direction between FORWARD and REWIND modes. The tape lifters are adjusted by loosening the screw in the end of the shaft, and changing the position of the tape lifter solenoid plunger with respect to the lifter. This can be accomplished from the underside of the transport as shown in figure 24.
45. Be certain that the tape clears the reel flanges with plenty of space to assure freedom from scraping.
46. Record head and reproduce head azimuth is set during signal electronics alignment.

Flutter

Flutter is checked by recording a 3 kHz signal and then playing it back into a flutter meter. This is a simple procedure with a record and playback system. However, with record only, or reproduce only, systems it is a bit more complicated. Flutter in these systems can be checked by using the single record or reproduce head stack, but some signal conditioning is necessary. For instance, if the system is a reproduce only system, a 120-kHz bias signal must be applied along with the

3 kHz signal to the reproduce head. If the system is a record only system, a sensitive preamplifier is required to reproduce the recorded signal.

Flutter checks are useful as a troubleshooting aid in determining which component, or group of components, is contributing to the flutter. Using a D&R Ltd, Varo, or equivalent flutter meter, in which three bandpasses are provided, components contributing to flutter can be determined, as shown in table 8. The following steps are to be followed in checking the flutter of a normal machine equipped with standard NAB record and reproduce electronics.

NOTE

It is extremely important that all tape guides, heads, capstan surface, puck idlers, capstan flywheel, and capstan motor spud be thoroughly cleaned with alcohol before making flutter checks.

Table 8. Components Contributing to Flutter

WAVEBAND	COMPONENT AREA
0.5 to 30 cps	Flywheel and capstan
30 to 300 cps	Capstan motor and reversing idler
0.5 to 300 cps	Used to check overall flutter up to 300 cps

47. Connect an audio oscillator to the input of the recording electronics. Set the oscillator frequency to approximately 3 kHz (some flutter meters contain their own internal oscillator). Connect the output of the playback electronics to the flutter meter input.
48. Set the capstan motor to high speed (normally 15 ips). Position the tape so that it will start near the beginning of the reel.
49. Record the test signal at 0 VU for approximately 3 minutes. Rewind the tape to the start of the test signal recording.
50. Start the tape and calibrate the input level to the flutter meter. Check the frequency acceptability to the discriminator, then switch to the fullband flutter position (0.5 to 300 cps). Employ 0.5% full scale sensitivity. Flutter should not exceed 0.04% at 15 ips, nor 0.07% at 7-1/2 ips.
51. Since it is possible for flutter components to cancel in playback because the phase of the recorded flutter may be opposite to the same component being generated during playback, it is necessary to stop and start

the tape during playback at least 15 or 20 times and to accept the worst reading, where the recorded and reproducing phases are additive, as the true worst flutter case. This must be done on each test. Do not check flutter with a playback head while recording the carrier with another head.

52. Make each flutter measurement at about 100 feet from the beginning of the reel, near the center, and again at about 100 feet from the end of the reel.
53. Identify any prominent frequency components in observed flutter, using an oscilloscope. Sources of such components must be determined and steps taken to minimize them if they cause overall flutter readings to exceed specifications. Several sources are:
 - a. Rotation rate of the capstan. A large component at this rate indicates a faulty flywheel tire.
 - b. Rotation rate of the reversing idler (same rate as capstan).
 - c. Rotation rate of the ingoing pressure roller.
 - d. Rotation rate of the outgoing pressure roller (rate close to that of c).
 - e. Rotation rate of the capstan motor.
 - f. Rotation rate of the takeup or supply reel.
 - g. Resonant component of the reversing idler mass coupled to elasticity of the tape; approximately 100 cycles on the idler for 1/2 inch tape. Try running the tape at high speed over the reversing idler. If the latter produces considerable noise, whining, growling, or hissing, it may mean that the bearings have been damaged; in which case the idler should be replaced, since considerable flutter will otherwise be generated. Do not try to repair the idler. Replace it.
 - h. Magnetic imbalance in capstan motor causing a 60-, 120-, or 180-cycle component (60-cycle motor) or 50-, 100- or 150-cycle component (50-cycle motor). This is generally prominent at one speed and barely detectable at the other. Make tests at the speed producing the strongest component, if any, and adjust the value of R63 and C64 (see figure 24) to minimize this flutter component. Motors have been trimmed after installation at the factory to minimize this component by the addition small value 600-volt

tubular capacitors. Further adjustments should seldom be required but are made by adding or removing such trimmers.

54. Disconnect the power cord. The hinged plug cover must swing into position, making it impossible to again plug in the power cord without first lifting the hinged cover. Observe that when the cover is in place over the plug the capstan motor is locked mechanically away from the capstan flywheel so that it cannot swing back and forth in shipment.
55. Be certain the capstan motor counterbalance spring is in the proper position for vertical or horizontal service, as required (see figure 14).
56. Replace the cover plate and return the transport to service.

NAB SIGNAL ELECTRONICS ALIGNMENT

The 3M Brand Professional Audio Tape Recorder is factory aligned for peak performance. All alignment controls are behind the panel on the front of the electronics assembly and are screwdriver adjusted. See figure 26. For access, simply drop the hinged panel downward. The circuit boards and controls are illustrated by a label on the back of this panel. Alignment and adjustments are described first for NAB systems, followed by those for Dynatrack systems.

NAB Playback Alignment

In the NAB configurations, the playback circuits are normally factory aligned to match Ampex standard alignment tapes as follows:

<u>Speed (ips)</u>	<u>Tape Width (inches)</u>	<u>Stock No.</u>
15	1/4	01-31311-01
15	1/2	01-31311-05
15	1	46-90006-01
7 1/2	1/4	01-31321-01
7 1/2	1/2	01-31321-05
7 1/2	1	46-90007-01

The procedure is as follows:

1. Thoroughly degauss and clean all heads.
2. Place the 15-ips standard alignment tape on the tape transport. Be sure that card No. 7 or 7/9 is inserted into slot No. 7.
3. Set the REC. SELECT switch to SAFE and the METER switch to CAL.

NOTE

Be certain that the output impedance and termination switches on the rear of electronics assembly are in the proper position for the connected outgoing line.

4. Remove the head cover plate to expose the head azimuth adjusting screws.
5. Set the transport to operate at 15 ips and press the PLAY button. When the reference tone of 700 Hz appears, the meter should indicate zero VU. If it does within 1/4 VU, proceed to step 6. If not, adjust the GAIN CAL. control on the board in slot 7 until it does.
6. Play the 10 kHz test tone. The output shall be within $\pm 1/2$ VU of the 700 Hz reference tone. If not, perform step 9.
7. Rewind the test tape to the 15 kHz tone, and adjust the playback head azimuth (figure 27) for peak output.
8. Connect the outputs from the reproduce electronics corresponding to the top and bottom playback heads to the inputs (Vertical and Horizontal, respectively) of an oscilloscope to produce a lissajous pattern (any other appropriate method to check phasing may be used). Start the alignment tape at 2 kHz and adjust the playback head azimuth for zero phase error. Check each frequency up to and including 15 kHz for phase error. Check each combination of any two tracks and optimize the azimuth for a phase error of less than 90 degrees.
9. Play the 10 kHz test tone and adjust the HF EQ FAST control on card 7, if necessary, to obtain the output level required in step 6.
10. Run through the rest of the test tape. Overall response should be within ± 1 VU from 12,000 to 50 Hz. 15,000 may be between +2.5 VU and zero VU. 30 Hz may be ± 2 VU from the original 700 Hz reference. Low frequencies may be adjusted with the LF EQ FAST control on the preamplifier board in slot No. 7.




Figure 27. Record and Playback Head Azimuth Adjustments

11. After making the necessary equalizer adjustments, rewind and replay the standard tape to be certain that all frequencies are within limits.
12. Remove the standard tape, preferable "tails" out.

The 7-1/2-ips playback alignment is done in exactly the same manner except that the initial 700 Hz tone and the frequency run are at 10 VU below zero VU. They are followed by 700 Hz at zero VU and this should first be observed, as outlined under preceding step 6. Then rewind the tape to the first 700 Hz band, set the METER switch to SIGNAL, press the B OUTPUT transfer button and adjust the REPRO. LEVEL control to indicate -5 VU. The REPRO. LEVEL control is now set 5 VU higher than normal CAL. level, but it permits more accurate readings. Then check for ± 1 VU response 12,000 to 50 cycles and ± 2 VU 15,000 to 30 cps, as outlined in steps 9 and 10. Adjusting HF EQ SLOW and LF EQ SLOW rather than HF EQ FAST and LF EQ FAST. These are automatically switched in when the tape speed is changed. The head azimuth adjustment and GAIN CAL adjustment made at 15 ips should not be disturbed unless 7-1/2 ips is to be considered the speed of primary usage.

NAB Record Alignment

The alignment procedure to follow should be carried out, using a length of tape from the supply to be used for subsequent recording, whenever possible. The 3M Brand Professional Audio Recorder is factory aligned to use 3M types 201, 202 and 203 tape. It is essential that the preceding playback alignment be checked before record alignment.

15 IPS Tape Speed Alignment

1. Set REC. SELECT switch to RDY., the METER switch to SIGNAL and press the A transfer button. The RECORD LEVEL control need not be adjusted from its normal operating position if it has been locked in place. The LINEARIZER switch on the Hand NAB Record Board in slot 4 should be in the OFF position. Connect an audio signal generator to the recorder input (J101).
2. Set the audio signal generator to 1000 Hz and raise the level until the VU meter indicates 0 VU.
3. Check to be sure that meter continues to indicate 0 VU as the oscillator frequency is changed between 30 Hz and 15,000 Hz. If there is more than $\pm 1/2$ VU deviation in these indications, the reasons must be discovered before continuing with the checkout. Possible reasons may be unstable oscillator output versus frequency, improper termination, shunting capacitance on the input line, or capacitive feed (one lead open between the oscillator or recorder).
4. Listen with a monitor speaker or earphones to be sure no strong noise or hum component is picked up at the input terminals in addition to the oscillator tone.
5. Start the recorder in RECORD mode. Turn the METER switch to CAL.
6. Adjust the BIAS AMP control on the Bias and Erase Amplifier Board in slot 1 to give a maximum indication on the VU meter for the 1000 Hz signal. The maximum should occur at zero VU. If the meter indicates other than 0, adjust the input signal level for a 0 indication. Turn the METER switch to SIGNAL, press the A OUTPUT button and adjust the RECORD MON. CAL. control on the Hand NAB Record Board in slot 4 until it again indicates 0. Return the METER switch to the CAL position.
7. Set the oscillator to 7000 Hz. Adjust the azimuth of the record head stack to give a maximum indication on the VU meter. Reset the oscillator to 15,000 Hz and again carefully adjust the record head azimuth for maximum. Using a similar method as in step 8 of the NAB Playback Alignment, adjust the record head azimuth screw (figure 27) for less than 90 degrees phase error between any two tracks.

8. Make a frequency run from 15,000 to 30 Hz and observe the VU meter. If it lies within ± 1 VU from 40 to 15,000 Hz, and ± 2 VU at 30 Hz, the performance may be considered satisfactory.
9. If the frequency response is not within acceptable limits, adjust the HF EQ FAST control on the H and NAB Record Board in slot 4 to bring response within limits.

7-1/2 IPS Tape Speed Alignment

Having checked the playback circuit and adjusted it for flat response as outlined under NAB Playback Alignment, 7-1/2 inch speed, leave the REPRO LEVEL control set in the position established under that procedure which resulted in the standard tape signals recorded at -10 VU showing -5 VU on the meter. Then proceed as follows:

1. Perform steps 1, 2, and 3 of the procedure outlined under NAB Record Alignment, 15 ips Tape Speed Alignment.
2. Reduce the input signal level so that the meter indicates approximately -10 VU.
3. Listen with speaker or phones to be sure there is no strong noise or hum component picked up at input terminals in addition to the oscillator tone.
4. Put the recorder into record mode. Press the B OUTPUT transfer button. The meter should indicate approximately -5 VU.
5. Adjust the BIAS control on the Bias and Erase Board in slot 1 for maximum VU indication at 500 Hz. Readjust input signal level if necessary to get -5 VU.
6. Set the oscillator to 5000 Hz. Adjust the azimuth of the record head stack to give a maximum indication on the VU meter. Reset the oscillator to 15,000 Hz and carefully adjust azimuth for maximum indication. If primary speed of interest is 15 ips, skip this step.
7. Make a frequency run over the range of 30 to 15,000 cycles and observe the VU meter. If it indicates within ± 1 VU from 40 to 12,000 Hz, and ± 2 VU from 30 to 15,000 Hz, the performance may be considered satisfactory.
8. If the frequency response is not within acceptable limits, adjust the HF EQ SLOW control on the H and NAB Record Board in slot 4 to bring response within limits.

9. Return the signal generator to 500 Hz. Adjust the REPRO. LEVEL control to obtain approximately -10 VU indication. Turn the METER switch to CAL. Raise the input level to obtain 0 VU indication on meter.
10. Press the A OUTPUT transfer button and turn the METER switch to SIGNAL. The meter should indicate 0 VU. If it does not, adjust the RECORD MON. CAL. control on the H and NAB Record Board, slot 4, until a zero indication is obtained. If there is a discrepancy in this adjustment between the 7-1/2 and 15 IPS setting, adjust it for the speed most important to the application.

NOTE

The above procedure permits frequency response measurements to be made at a signal level 10 VU below the zero reference level. This is essential with low speed tapes (7-1/2 ips or slower) because of the heavy recording preemphasis used for higher frequencies.

Dynamic Range Adjustment (NAB)

1. Connect the signal generator to a calibrated attenuator box and terminate the output of the box. Feed this output to the input of the channel under test. Connect a distortion analyzer and a vtvm to the output terminals. Use a reel of tape of the type for which the recorder has been aligned. The tape speed should be 15 ips.
2. Before beginning noise measurements, it is absolutely essential to degauss and clean all heads very carefully. Turn off the main recorder power switch during degaussing. Connect a high gain power amplifier and loudspeaker to the output terminals of the recorder. Short circuit the input terminals. The METER switch should be set to ERASE with the B OUTPUT lamp lit.
3. Advance the monitor gain so that the tape noise is heard loudly.
4. Remove the 3N card. Press the RECORD button. Adjust the NOISE BAL. control on the Bias and Erase board in slot 1 to minimize thumping and popping noises. Press the STOP button.
5. Reinstall the 3N board, using an extender board. Press the RECORD button. Adjust the ERASE AMP. coupling capacitor on the 3N board to attain minimum audible noise. The point of minimum noise will be found either slightly above or below peak erase current, as observed on the meter.

6. Press the STOP button. Remove the extender board and plug board 3N into its normal position. Check again to be certain that noise has not increased.
7. Reduce the monitor gain to the normal setting. Set the oscillator to 1000 Hz and use a decade attenuator to insert a 19 db loss.
8. Set the LINEARIZER switch on the H and NAB Record Board in slot 4 to OFF.
9. Put the recorder into the RECORD mode. The B OUTPUT lamp must be lit. Readjust the input level to obtain 0 VU on the meter.
10. Measure distortion on the wave analyzer. It should be just under 1% total harmonic distortion.
11. Rewind some of the tape and play it back. Observe the distortion. If it is lower, it means that high-frequency bias current is leaking into the distortion analyzer during recording and all measurements will have to be made through a low-pass filter or during playback only.
12. Return to recording the 1000 Hz signal at 0 VU. Remove 6 db from the calibrated attenuator. The distortion meter should indicate just under 3% total harmonic distortion. Observe the vtvm indication.
13. Disconnect the oscillator from the input to the attenuator and record some tape with this input signal removed, (approximately 30 seconds of tape).
14. Play back the tape so recorded, and read the vtvm. The difference in readings between tape recorded in steps 12 and 13 represents the signal-to-noise ratio measured from the 3% distortion point without the linearization circuit in operation. Place the LINEARIZER switch to ON.

NOTE

Noise figures stated in the system specifications are obtained by the use of bandpass filters. Such filters exclude all noise outside the stated pass-band.

Miscellaneous Adjustments and Circuit Arrangements

When the METER switch is set to the BIAS position during recording, the VU meter indicates a steady level, determined by the amplitude of bias current in the

record head. When this current is optimized, the meter indication can be adjusted to a convenient reference by means of the BIAS MON. CAL. control on the Bias and Erase Board in slot 1. This provides a ready check of bias at any time.

When the METER switch is set to the ERASE position during recording, a similar check is provided for the magnitude of the erase current. This may be calibrated to read any convenient level by means of the ERASE MON. CAL. control on the NAB Erase Coupler Board in slot 3.

The recorder is normally set up to supply a 600-ohm line at the +4 dbm level. The output impedance switch can be set to select either 600 ohms or 150 ohms, and the termination switch can be set to 600, 150, or open position. If it is desired to change the working line level from +4 dbm to some other level, it is necessary to change certain resistors on the Line Amplifier Board in slot 6. A chart of values is shown in the circuit description for this board.

The use of the PILOT connector and the REMOTE METER connector are fully described under circuit descriptions.

The linearizer adjustment should be undertaken in accordance with the following outline. If the user feels the adjustment has been misset it may be disconnected by setting the LINEARIZER switch to OFF until properly aligned.

As delivered, the machine is adjusted for use with Scotch brand low-noise tape types 201, 202, and 203. Under normal conditions no adjustments should be necessary. The switch should always be in the ON position except when distortion measurements are being made. If the machine is to use a different type of tape, the LIN ADJ. control may require trimming. This is best done with aid of a wave analyzer. Adjustment is done as follows:

1. Set the METER switch to CAL position.
2. Make the frequency response and dynamic range adjustments and measurements outlined above for the type of tape used
3. Set LINEARIZER switch to OFF position.
4. Raise record level to give 3% third harmonic distortion.
5. Set LINEARIZER switch to the ON position.
6. Adjust LIN ADJ. control for minimum distortion.
7. Adjust input level to again achieve 3% third-harmonic distortion.
8. Repeat steps 5, 6, and 7 until no change in record level is necessary.

9. Adjust record level to provide zero VU playback level.
10. Press the A OUTPUT button and set METER switch to SIGNAL. Meter indication should remain at 0 VU. If it is higher or lower, adjust RECORD MON. CAL. control to obtain zero indication.

If it should be necessary to adjust the linearizer without the aid of a wave analyzer, a satisfactory approximation to the ideal adjustment can be made with a vtvm as follows:

1. Set METER switch to the CAL. position and LINEARIZER switch to OFF.
2. Using a standard alignment tape establish a reference level on the vtvm.
3. Using the desired tape type adjust the record level to obtain a signal 6 VU above 0 VU.
4. Set LINEARIZER switch to ON. Output level should rise 0.8 VU if the linearizer is properly adjusted. If not, adjust the LIN ADJ. control to achieve the difference.
5. Set the LINEARIZER switch to OFF. If output level is changed from +6 VU, readjust record level to again obtain +6 VU.
6. Repeat steps 4 and 5 until the 0.8 db difference is attained upon operation of LINEARIZER switch and the indicated operating level is +6 VU with the switch in the OFF position.
7. Reset RECORD MON. CAL. control if necessary as outlined above.

Series 400 recorders equipped to provide overdub recording capability should be set up in accordance with the following procedure:

NOTE

For maximum flexibility, it is desirable to employ a No. 7 board for normal reproduction, and a permanently installed No. 7/9 board in slot 9 to provide overdub facilities. When furnished in this manner the recorder is considered having permanent overdub capability.

1. Place a No. 7/9 board in slot 9. Position the REC. SELECT switch to the O. DUB position.

2. Set the METER switch to CAL. Press the PLAY button. Adjust the GAIN CAL control on the 7/9 card for zero VU on the meter when the 700 Hz signal is playing from the standard alignment tape. Press the STOP button.

DYNATRACK ELECTRONIC ALIGNMENT

The Dynatrack system is designed for operation only at 15 ips. Refer to pages 1 to 4 for a description of the Dynatrack system. In a normal NAB system, one track is assigned to each electronics assembly unit and provides for recording and playback of a separate signal input and output channel. In the Dynatrack system, two tracks are employed per signal channel. The heads will have been properly connected to the electronics assemblies of a factory assembled Dynatrack system but for systems delivered for NAB operation, observe the following conversion procedure. It is assumed that the Dynatrack kit has been installed in accordance with the Dynatrack installation procedure which accompanies the kit.

1. Reconnect the head cables to the electronic assemblies in accordance with the assignment shown in table 3.
2. Observe figure 26. Be sure the Dynatrack boards are installed as shown for electronic assemblies to be employed for this operation. Those not so converted should retain the NAB arrangement, also shown in figure 26. Figure 26 is reproduced on the inside of the electronics assembly cover door.
3. Set the REC. SELECT switch on all nonconverted NAB electronic assemblies to SAFE and the A-B OUTPUT selector on A. Deactivate the automatic transfer by setting the AUTO A-B switch on each no. 6 board in the NAB assemblies to OFF.
4. Put the NAB standard alignment tape for 15 ips on the transport.
5. Set the REC. SELECT switch to SAFE and the METER switch to CAL. Set the MODE switch on the 8D board to the H1 position. The pilot lamp should go out.

NOTE

Be certain output impedance and termination switches on the rear of electronics module are in proper position for the connected outgoing line.

6. Put the machine in the PLAY mode at 15 ips. When the reference tone of 700 Hz appears, the meter should indicate 0 VU. If it does within 1/4 db, proceed to step 7. If not, adjust the GAIN CAL. control on the board in slot 7 to obtain this indication.

7. Play the 15,000 Hz azimuth check tone and adjust the playback head azimuth (figure 27) for peak output as indicated on the VU meter.
8. Play the 10,000 Hz test tone, and adjust the HF EQ FAST control on board 7 to obtain 0 VU on the meter. Play through the tape, and adjust the LF EQ FAST control on board 7 so that all frequencies between 50 and 10,000 Hz fall within ± 1 VU of the 700 Hz reference level. 15,000 Hz shall be no more than +2.5 VU from the 700 Hz reference.
9. After making necessary equalizer adjustments, rewind and replay the standard tape to be certain that the response at all frequencies is within the limits specified in step 8.
10. Rewind the tape.
11. Place the MODE SWITCH on the 8D board in the LO position. The pilot lamp should light. Set the equalizer switch behind the extractor handle to the lower OFF position. (This switch is not shown in figure 26.)
12. Put the machine in the PLAY mode. When the reference tone of 700 Hz appears, the meter should indicate 0 VU. If it does, within $1/4$ VU, proceed to step 13. If it does not, adjust the GAIN control on board 8D until it is within limits.
13. Play the 10,000 Hz test tone, and adjust the HF EQ control on board 8D to obtain 0 VU on the meter. Play through the tape, and adjust the LF EQ control on board 8D so that all frequencies between 50 and 10,000 Hz fall within ± 1 VU of the 700 Hz reference level. 15,000 Hz shall be no more than +2.5 VU from the 700 Hz reference.
14. Set the MODE SWITCH on board 8D to the AUTO position (mid position). Rewind the alignment tape to permit playing the 5 kHz tone. Adjust the TRIG control on card 8D so that the neon lamp is on the verge of extinction in the presence of the tone as indicated by slight flickering.
15. Set the equalizer switch behind the extractor handle on card 8D to the upper ON position. (This switch is not shown in figure 26.)

Dynatrack Record Alignment

This alignment procedure should be carried out, using a length of tape from the supply to be used for subsequent recording. The 3M Brand Professional Recorder is factory aligned to use 3M types 201, 202, and 203 tape.

The procedure accomplishes the following. It checks the H track for alignment to NAB standards, adjusts the level and frequency response on the L track, and compares the two tracks for identity of level and frequency response.

NOTE

Do not upset any of the playback adjustments for either the L or H track which were established above.

H Track NAB Alignment

1. Set REC. SELECT switch to RDY and the METER switch to SIGNAL. Press the A OUTPUT transfer button. Place the LINEARIZER switches on the L record board (3D) and on the H record board (4) to the OFF position. Place the MODE SWITCH on the L preamplifier and switch board (8D) in the HI position.
2. The RECORD LEVEL control need not be adjusted from its normal operating position if it has been locked in place.
3. Connect an audio oscillator to the SIGNAL IN connector and set the the oscillator frequency to 400 Hz. Adjust the oscillator output level until the VU meter reads 0 VU.
4. Check that the meter continues to indicate 0 VU if the oscillator frequency is varied from 30 to 15,000 Hz. If there is more than 1/2 VU deviation in these indications, the reason must be determined before continuing. Set the oscillator to 1000 Hz.
5. Listen with a monitor speaker or earphones to be sure that there is no strong noise or hum component picked up at the input terminals in addition to the oscillator tone.
6. Put the recorder in the RECORD mode. Turn METER switch to CAL. The meter should indicate 0 VU.
7. Adjust BIAS AMP. control on board 1 to give a maximum indication on the VU meter for the 1000 Hz tone being recorded on the H track. The maximum should occur at 0 VU. If the meter indicates other than 0, adjust the oscillator output level until 0 indication is obtained. Then with the A OUTPUT lamp lit, turn the METER switch to the SIGNAL position, and adjust the RECORD MON. CAL control on board 4 until it again indicates zero. Return the METER switch to the CAL position.
8. Set the oscillator to 7000 Hz. Adjust the azimuth of the record head stack to give a maximum indication on the VU meter. Set the oscillator to 15,000 Hz and carefully trim the azimuth adjustment for maximum.

9. Make a frequency run from 15,000 to 30 Hz while observing the VU meter. If it is within ± 1 VU from 40 to 15,000 Hz and ± 2 VU at 30 Hz, the performance may be considered satisfactory.
10. If the frequency response falls outside these limits, adjust the HF EQ FAST control on board 4 to bring the response within limits. This completes frequency and amplitude alignment of the H track.

L Track Alignment

Align the L track for frequency response as follows:

1. Set the MODE switch on the 8D board to the LO position. Turn the METER switch to SIGNAL.
2. Set the oscillator to 250 Hz and reduce the input signal level by approximately 20 db below the 0 VU level by adjusting the oscillator output control or by using a step attenuator.
3. Put the machine in RECORD mode. Transfer the OUTPUT to B.
4. Raise the signal level by the REPRO. LEVEL control until a convenient playback level is indicated. Lock the control in this position. If the reading is still several db below 0 VU, an external VTVM fed from the output of the channel may be useful for making measurements.
5. Set the oscillator to 1000 Hz. Adjust the BIAS ADJ. control on the 3D board to obtain a maximum reading on the meter. Should this result in a higher meter indication, reset the oscillator output to again obtain the convenient reference as in step 4.
6. Make a frequency run from 15,000 to 30 Hz while observing the meter. If the response is within ± 1 VU (db) from 40 to 15,000 Hz and ± 2 VU (db) at 30 Hz, the performance may be considered satisfactory.
7. If the frequency response is not within acceptable limits at the high frequency end of the spectrum, adjust the BIAS ADJ. control on the 3D board slightly.

Combined H-L Dynatrack Performance

To adjust the relative amplitudes of the signals in the two tracks comprising a dynatrack channel, it must be borne in mind at this point that the playback levels of both tracks have been properly set using a standard alignment tape and that the recording level in the H or NAB track has been properly established. This leaves only the adjustment of the L track recording level to be determined.

1. Set the MODE SWITCH on the 8D board to HI, the METER switch to the SIGNAL position, and press the OUTPUT transfer B button.
2. Record 700 Hz at a level that will indicate zero VU on playback by adjusting the output amplitude of the oscillator.
3. Set the MODE SWITCH on the 8D board from HI to LO. The meter indication should not change. If it does, adjust the GAIN control on the 3D board until meter indicates zero.
4. The LINEARIZER on board 3D will probably not require adjustment. It may be checked and adjusted as outlined for the NAB track. In this case, however, use 500 Hz for the alignment procedure.
5. Unlock the REPRO. LEVEL control knob and return it to approximately the normal operating position. Return the MODE SWITCH to the AUTO position.
6. Check the operation of the trigger circuit as indicated by the neon lamp on board 8D. While in the record mode, feed various frequencies into the channel. Raise and lower the level slowly by adjusting the oscillator output in order to cause the lamp to turn off and on. At 1000 Hz, this should occur at about 0 VU and at lower levels as the frequency is raised until a level of about -15 VU causes extinction of the lamp at 15,000 Hz. There is no requirement for lamp extinction at any frequency lower than 400 Hz.
7. Listen carefully in a high level monitoring system for clicks and pops when making the tests in paragraph 6 above. They should be almost completely inaudible.
8. Return the LINEARIZER switches on the L record board (3D), and on the H record board (4) to the ON position.

Dynamic Range Measurement, Dynatrack

1. Connect signal generator to a calibrated attenuator box and terminate the output of the box. Feed this output to the input of the recorder channel under test. Connect a distortion analyzer and a vtvm to the output terminals. Connect an ASA weighting network in accordance with figure 28 in series with the input of the vtvm. Use a reel of tape of the type for which the recorder has been aligned under the above paragraphs. Select 15 ips tape speed.

2. Before beginning noise measurements, degauss all heads carefully. Turn off the recorder POWER switch during degaussing. Connect a high gain power amplifier and loudspeaker to the output terminals of the recorder. Short circuit the input terminals. Turn the METER switch to SIGNAL and press the B button. Set the MODE SWITCH on 8D board in slot 8 to HI. Set both LINEARIZER switches to the OFF position.
3. Turn up the gain so that tape noise is heard loudly.
4. Adjust NOISE BAL control on Bias and Erase Amplifier Board in slot 1 to minimize thumping and popping noises.
5. Set the MODE SWITCH to LO.
6. Adjust the NOISE BAL control on the L Record Amplifier Board in slot 3 to minimize thumping and popping noises. This test will require more gain in the loudspeaker amplifier in order to be heard.
7. Set the MODE switch to HI.




Figure 28. ASA Weighting Network and Response Curve

8. Set the oscillator to 400 Hz, and insert 19 db attenuation in the calibrated attenuator box.
9. Put the recorder in the record mode. The B OUTPUT transfer button must be lit. Readjust the oscillator gain control (not the attenuator) to obtain zero VU indication on the meter.
10. Measure the distortion on the wave analyzer. It should be just under 1%.
11. Rewind some tape and play it back. If there is a significant improvement in the distortion reading it means that high-frequency bias current is leaking into the distortion analyzer during recording. In such instances measurements must be made through a proper low pass filter or only on playback.
12. Change the oscillator frequency to 1000 Hz. Check by recording the signal to be certain that the VU meter still indicates zero level.
13. Remove 6 db of attenuation from the calibrated attenuator. The VU meter will be off scale. Readjust the distortion meter to analyze 1000 Hz. It should show 3% total harmonic distortion.
14. Observe the indication on the vtvm which is fed through the ASA weighting network from the output of the recorder.
15. Disconnect the oscillator by unplugging it from the input to the attenuator, while the recorder is still in the record mode and short circuit the input terminals. Continue to record for about 30 seconds.
16. Rewind the tape far enough so that the 3% level tone will be first reproduced, followed by tape recorded with no input signal. Set the MODE SWITCH to AUTO.
17. Play back the tape. During the tone the pilot lamp on the 8D board in slot 8 should be out. Observe the vtvm reading. When the tone runs out, the pilot lamp should light. Again read the vtvm. The difference in readings is the weighted signal-to-noise figure. It should be 80 db. This reading may be attained only after several rotations of the supply reel since a certain amount of printing from the high level (+6 VU) signal to the quiet tape is inevitable in the first few layers.
18. Return both LINEARIZER switches to the ON position.

HEADS

This recorder can be obtained with a variety of head configurations. Heads are mounted on a plate which provides azimuth adjustment of both record and playback head stacks. Erase heads are fixed in position. The plate carries a connector which mates with another permanently mounted in the transport. The transport connector has leads attached to it which connect to the electronic assemblies. All of these connectors are physically interchangeable. It is imperative that the number and letter coding be observed.

To change a head assembly, first remove the head cover trim, then the transport cover plate, and then the reversing idler (held in place by one screw under the main casting). See figure 23. Next remove the two metal trim plates (one on either side of the capstan and idler). Remove the screws that hold the head mounting plate in place. Insert two screws into the tapped holes at either end of the connector plug. As these are screwed down, they will jack up the plate and gently separate the connectors. An alternate head assembly may be installed by following the reverse procedure. Head stacks of various physical heights may be interchanged. On machines with one-half inch capstan height any heads for up to 1/2 inch tape width may be mounted in place. For machines with one-inch capstan height, any heads for up to 1 inch width may be mounted.

TAPE GUIDES

The function of the tape guides is to cause the tape to be fed into the Isoloop without lateral shifting, so that the recorded pattern remains within the NAB margins, and to cause the tape to wind evenly onto the reels so that each turn lies on top of the other and does not contact either reel flange.

The primary tape path reference is the lower flange of the ingoing guide which guides the tape into the Isoloop.

When head assemblies are changed to accomodate a different tape width, it is necessary to change the tape guides. These may be removed by unscrewing them from the main casting. Replace with guides having the appropriate height. Remember the guides having the narrower opening (a few thousandths of an inch) go on the incoming (supply) side of the capstan. The wide ones go on the takeup side.

This guide surface is set at a fixed distance from the capstan assembly machined surface, on which the heads are mounted. The desired guiding is one that feeds tape into the Isoloop with the edges touching, but not binding on the flanges of the incoming guides. The outgoing tape guides are wider. Their flanges do not guide the tape in the normal running mode.

Tape guides will not normally require adjustment unless the machine is converted for a wider, or narrower tape. New guides, heads, and reel hubs are finished as part of a conversion kit. The replacement guides are installed by their center screws. Proper flange height is established by holding machining and plating tolerances, and no shimming or threaded adjustment is required.

To assure that tape guiding is satisfactory and that no damage or misadjustment has occurred, the following examination can be made.

1. The lower edge of the tape (inner edge of the tape if the transport is mounted vertically) registers lightly on the lower (inner) flange of the incoming guide nearest the capstan. The tape does not move up or down on the reversing idler as the tape direction shifts from forward to rewind.
2. The wear pattern on the heads and guides is straight-sided. (Not keystoneed, which would indicate uneven tension across the tape.) There must be no evidence of a 1/4-inch groove on 1/2-inch guides and heads, or a 1/2-inch groove in 1-inch heads, etc.

REEL HUBS

The function of the reel tables and holddown hubs is to hold the tape reels in plane of the tape path, so that tape is fed out and spooled without scraping on either reel flange. The hub is held in place by a shaft collar on the reel motor shaft. See figure 29. Position of the collar is secured by two setscrews. After a reel is installed the finned, spring-loaded top of the knob may be turned a few degrees clockwise, which will lift the three small bevelled projections up out of the reel keyway slots to rest on the top of the reel, locking it firmly to the reel table. Reel table height should not require readjustment unless a reel motor is replaced.

A small 1/4-inch center reel table and hub is available to accommodate home-recorder type reels. To install this reel table, the large coin slot center screw in the NAB reel hub is loosened, the top lifted off, and three small Phillips screws removed. The 1/4-inch table and hub are then installed, using the three flat-head screws. The 1/4-inch reels are held in place by turning the top part of the spindle so that the bevelled keys rest on top of the reel, as in the NAB hub.




Figure 29. Reel Hub Adjustment

MAINTENANCE

Maintenance of the 3M Brand Professional Audio Recorder will normally consist of adjustment and repair as needed. Adjustments are presented in the Alignment and Adjustment section. This section contains special notes concerning maintenance and troubleshooting.

GENERAL PRECAUTIONS

The following paragraphs contain some general precautions which should be observed when performing maintenance on the recorder.

1. Do not strike the reversing idler. It is delicate and located in a vulnerable position at the front of the mechanism. If damaged, flutter will be excessively high.
2. Exercise great care in installing head mounting plates. They can be screwed into place with a head lead pinched between the mounting plate and the transport casting, thus breaking wire insulation or cutting a head lead. Be certain no leads will get in the way before installation.
3. Exercise great care in removing and replacing the mu metal cover over the playback head stack. The slot at the rear of the cover can slice head lead insulation, thereby grounding head leads or actually cutting through them. Be certain that this cover is fully seated so that the lower lip will not scrape on tape as it passes by. Otherwise tape edge may be cut and bad tracking over the heads may result.
4. Do not go from REC. to SAFE when the recorder is operating in the RECORD mode. First stop the transport. This will prevent a thump from being recorded in the tape and magnetization of the record head.
5. Do not remove any of the electronics cards when the power is on. It requires only a few seconds to turn off the power, remove a card, restore power and be ready to operate. Otherwise it is possible to magnetize a head or damage a meter.
6. It is particularly important when moving a 7/9 board from position 9 to position 7 to first turn off the power, then wait about 20 seconds before removing the board and reinstalling it.
7. Be certain to remove the power cord from the transport when moving the recorder. This is to ensure that the capstan motor lockout device will prevent the motor spud from pounding the rubber tire on the flywheel.

8. Be certain no head cables on the power boards touch the rubber tire on the flywheel at any time, either when installed or in shipment.
9. The individual electronics module power supplies are mounted behind the meter. They are accessible by pulling the meter forward. Pull the meter by the fingers applying force to the meter case below the transparent window, not above, since this may result in a cracked case.
10. Never carry an electronics assembly face downward as the power supply module may fall out, breaking the meter.
11. Do not allow reels or flanges to scrape on the painted surface of the trim plate as this will mark it badly. Scraping can be caused only by bent reels or flanges which, if they cannot be repaired should be discarded.

TROUBLESHOOTING

Failure of the recorder to operate properly may be caused by a malfunction in the recorder, or by external causes. Before troubleshooting the recorder, verify that the power and signal connections are correct, and that all of the operational controls are properly set.

Some of the troubles most likely to be encountered are presented in table 9. However, the best troubleshooting tool is a familiarity with the equipment and a thorough understanding of its theory of operation.

Table 9. Troubleshooting

SYMPTOM	CAUSE	CORRECTION
TRANSPORT		
1. Transport stops when leader tape passes photo cell V60, particularly after machine warms up.	Photo resistor V60 is too sensitive.	Temporary: mask cell or lamp with one or more thicknesses of white splicing tape. Permanent: change value of R71 to a lower value best determined by test. Be careful to avoid grounding any wiring on the circuit board or cell leads.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
2. Transport will not stop when tape runs out. STOP button lights when tape is not threaded.	Lamp DS8 low in light output.	Replace the lamp. Lamps blacken after long use. If type 313 is found in socket, replace with 1820, longer life bulb.
	Weak photo resistor V60.	Replace V60 or try raising value of R71. Try 40K. Be careful to avoid grounding any wiring on circuit board or photo cell leads.
3. Capstan motor will not start when tape is threaded and the STOP light does not go out.	V60 damaged by accidental grounding.	Replace V60.
4. Capstan motor will not start when tape is threaded, but STOP light goes out.	Plug P11 separated from J11.	Connect the two parts, P11 to J11.
	Speed change switch off normal.	Operate switch to desired speed.
5. Transport coasts to stop from play mode when stop button is pressed.	Relay K7 cannot be operated during stop sequence because the reed switch is not closed.	Adjust the flag stops and/or clearance of magnets from the switch to restore operation.
6. Transport coasts to stop from the FORWARD mode when the STOP button is pressed. Possible tape breakage.	Same as 5, above.	Same as 5, above.
7. Transport coasts to stop from the REWIND mode when stop button is pressed. Possible tape breakage.	Same as 5, above except K6.	Same as 5, above.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
8. Tape continues in REWIND when the stop button is pressed. Restores to normal after tape runs out or POWER switch is turned off and on.	Tape motion direction sensor flag binding against forward direction stop post.	Check height of flag to be sure it clears screw head and locking nut of the post.
9. Tape continues in REWIND when the stop button is pressed. Does not clear after tape runs out or POWER switch is turned off and on.	K7 hung up. Contacts 5 and 9 sticking.	Replace K7 with another relay. Interchange with K2 after burnishing contacts 5 and 9 if no other relay is available.
10. Tape continues in FORWARD when STOP button is pressed. Restores to normal after tape runs out or POWER switch is turned off and on.	Same as 8, above. Damaged CR33 or CR34 giving half wave power. Low Line Voltage.	Same as 8, above. Check diodes and replace defective unit. Arrange for higher input voltage. Use auto transformer or Variac if necessary.
11. Transport throws loop when starting in Play mode, generally worse near end of reel rather than beginning.	Ingoing Solenoid, capstan idler, dashpot needs adjusting.	Adjust so that dashpot piston is completely at end of cylinder when at rest position. Dashpot load should be picked up just as puck builds up sufficient tape pressure on capstan to cause tape to move forward. Then dashpot will allow pressure to increase as tape is accelerated to running speed. Solenoid must seat instantly when power is applied, coupling spring allows gradual buildup of puck pressure adjusted by Phillips screw in solenoid arm linkage. Dashpot adjusted by bending two tangs on fork linkage.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
12. Sluggish Solenoid operation; L1, L2.	Misalignment or in need of lubrication.	Try lubricating first with graphite or silicone. Loosening to improve alignment may change absolute position of linkages when plunger is seated necessitating their further adjustment.
13. Tape lifter hangs up.	Misalignment or in need of lubrication.	Plunger must not drag too forcefully against core of solenoid. Body should be so positioned to avoid such side drag, and to provide best compromise of depth of travel to satisfy easy override yet adequate lifting power.
14. Tape lifter difficult to override manually.	Plunger approaches full seated position too closely.	
15. Tape lifter fails to lift tape from heads.	Plunger operating too far from seated position.	Loosen two mounting screws, lubricate plunger and shift body (holes are oversize) to achieve above requirements.
16. Flutter and Wow excessive.	Numerous sources possible. Most likely are: a) Head cables dragging on flywheel tire, b) Insufficient capstan idler pressure either ingoing or outgoing, c) Defective reversing idler, d) Dirty spud on motor shaft, e) Dirty flywheel tire or f) Speed adjustment screw too loose.	Remedies are obvious; also see transport alignment for more details.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
17. Transport appears completely dead.	Blown fuse F1.	Replace with 5 amps slow blow.
	Intermittent operation of power switch S6.	Press a few times to observe if lights come on.
	C66 charged to greater than 30 volts but no 27 volt dc at collector of Q60 or at test point means Q60 is defective.	Replace Q60 after checking load resistance from collector to ground for short circuit defect. Clear defect before again applying power.
18. All lamps excessively bright and short lived.	Regulator Q60 and associate circuit, Q1, R14, R15, and CR50 not functioning.	Replace Q60. Catcher diode CR51 will also require replacement if condition persisted for more than a few seconds. Check resistance of 27 volt load to be certain Q60 will not be overloaded. Transport may be operated without CR51 until replaced.
ELECTRONICS		
1. Meter lights but no signal. Record light will not light. Regulator transistor in power supply abnormally warm.	Short circuit on plus 28 volt bus.	Remove one plug-in board at a time and reinsert to determine if fault is in cards or module wiring. C4 on power supply unit possible shorted. System may operate without C4 until replaced.
2. Playback preamp in slot 7 or 9 distorted or no output.	Bias of Q2 improper.	Collector of Q2 should be per schematic. See figure 46. Defective Q1 or Q2 causes drift.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
3. A-B transfer causes bad clicks in output (moves meter pointer).	Leaky capacitor C15 in output of record monitor amplifier on board in slot 4 or at output of preamp in slot 7 or 9. Also can be leaky input capacitor to line amplifier in slot 6 (C9).	If REPRO. LEVEL pot is noisy when turned, fault is in output of board in slot 7 or input of board 6. Extract board 7. If still noisy card 6 is at fault. If pot is not noisy when turned, trouble is probably at output of board 4 (C15). Replace faulty tantalum capacitor.
4. Loss of signal in record, reproduce or monitor circuits.	Broken leads on black tantalum capacitor, likely on any board.	These capacitors are somewhat vulnerable since they project higher off the board than other components and their leads are not flexible. Replace with identical item.
5. Loss of signal in record board.	Defective Field effect transistor Q2. Easily damaged by static charge from soldering iron or tool held in hand.	Replace Q2. Be very careful to avoid static charges. Ground soldering iron tip by flexible lead to ground bus of record board. Always use insulated screwdriver or plastic blade to adjust eq. cap C18 or C19.
6. Noise or intermittent operation in any area of electronics module.	Dirty contacts at base of card at plug.	Remove and reinsert card. Use ink eraser to clean contact surfaces of cards. Sockets are gold plated. They should be ok.
7. High distortion	Insufficient bias.	Adjust to peak per instructions in this manual.

Table 9. Troubleshooting (Cont'd)

SYMPTOM	CAUSE	CORRECTION
7. (Cont'd)	Magnetized head, either record or reproduce.	Degauss heads.
	Noise balance control misadjusted.	Adjust for minimum noise after degaussing all heads.
	Faulty record or playback amplifier biasing.	Check voltages per schematic. If drastically different at any point, find cause and remedy.
8. Poor noise figure.	Noisy Q1 or Q2 in preamplifier.	Substitute another pre-amplifier to compare noise and replace transistors.
	Head cables badly routed, near hum fields.	Reroute for minimum noise. Keep away from power cord. This can be very important.
	Head cables rubbing on flywheel.	Noise arises from microphonics of cables under vibration. Must be rerouted to clear flywheel.
	Defective playback head requiring excessive gain.	Replace head. Try break-in tape if head appears to be smeared over by magnetic material.
	Lack of good system ground can produce hum or buzzing. Third wire in power cord not always effective as good ground.	Connect frame of recorder to good effective ground.

Table 9. Troubleshooting (Concluded)

SYMPTOM	CAUSE	CORRECTION
9. Wrong output level.	Improper choice of line impedance or termination.	Set switches S105 and S106 to proper arrangement for line being fed by recorder.
	VU calibrated to wrong line level for specific application.	Check value of resistors R1, R2, R3, on board in slot 6. See table 10.
10. Meter lights brighter than normal.	Meter light socket touching ground.	Move socket slightly, and cover with insulating tape.
	Defective lamp.	Replace lamp.
11. Meter lights, A-B lights not lit. R13 on power supply hot.	Ground on brace to terminal 18.	Remove clamping screw and insert mica insulating washer. Replace screw.

FIELD SERVICE

Regular scheduled maintenance service is available from the Mincom Division service office on a contract basis. If immediate service is required, it may be obtained on an emergency basis. Every effort is made to furnish the needed repair as soon as possible. For a complete description of 3M's maintenance service plans and their costs, contact the Mincom Division service office.

FACTORY REPAIR SERVICE

If desired, the recorder or major assemblies, may be returned to the factory (transportation prepaid) for repair. When recorder or assembly is returned:

1. Indicate the symptom of defect. State as completely as possible, both on an instrument tag and on the order form, the nature of the problem encountered. Too much information is far better than too little. If the trouble is intermittent, please be specific in describing the instrument's performance history.
2. Give special instructions. If any changes in the instrument or assembly have been made, and it is desired to retain the modified form, please indicate this specifically.
3. To facilitate expeditious repair, your Contract or Purchase Order authorizing the work should be directed to Mincom Division - 3M Company - 300 South Lewis Road - Camarillo, California 93010 - Attn: Contracts Department.
4. Pack securely and label. Proper packaging saves money. The small amount of extra care and time it takes to cushion a part or instrument properly may prevent costly damage while in transit. Make certain that the address is both legible and complete; failure to do so often results in needless delay. Address all shipments and correspondence to:

Mincom Division
3M Company
300 South Lewis Road
Camarillo, California 93010

Attn: Receiving Inspection

5. Show return address on repair correspondence. Please clearly indicate the exact address the equipment should be returned to after repair is completed. Terms are net 30 days - f. o. b. , Camarillo, California.

PRINCIPLES OF OPERATION

INTRODUCTION

The 3M Brand Professional Audio Tape Recorder is an advanced audio recording instrument that incorporates the best techniques available at the present state of the art. A tape recorder consists basically of a tape transport (deck) and record and reproduce (play) electronics. The signal to be recorded is amplified and applied to a magnetic record head, which impresses a magnetic pattern in the oxide coating of the magnetic recording tape in accordance with the variation of the input signal. During reproduction (play) the variations in magnetic flux that were impressed on the tape during recording, are sensed by a reproduce head, amplified, and applied to the recorder output.


In order to record and reproduce with a minimum of distortion, a high-frequency bias is mixed with the input signal at the record head so that recording takes place in the portion of the magnetization curve that is essentially linear. The signal recovered by the reproduce head must also be equalized by circuits that compensate for the response characteristics of the reproduce head at low and high frequencies.

The high-frequency signal that is used for bias is also used to erase signals that may have previously been recorded on the tape. The erase signal is applied to a separate erase head, which is similar to the record head but applies the high-frequency signal at a much higher level. The signal applied to the erase head drives the magnetic material of the tape to complete magnetic saturation to obliterate any signal, or noise that may have been previously recorded on the tape.

The patented Isoloop tape drive maintains differential tension within the loop of tape passing over the heads and ensures that the tape remains in close contact with the heads during tape travel. This ensures that the magnetic flux impressed by the record head penetrates the oxide material uniformly and eliminates variations in amplitude that can result if the close head-to-tape contact is not maintained. Similar amplitude variations can take place if the tape is not maintained in close contact with the play head.

Tape Drive Components (See Figure 30)

Components of the tape drive system consist of a capstan drive motor, two reel drive motors, and control relays that determine the mode of operation. When in play and record modes, the tape is moved through the Isoloop by the capstan. The reel drive motors maintain constant tension on the tape as it enters and leaves the loop. When in fast-forward or rewind, tension is released within the Isoloop and the reel drive motors move the tape through the loop independently of the



1183

Figure 30. Tape Recorder, Block Diagram

capstan. Before entering and after leaving the Isoloop, the tape passes over stationary guides to ensure that it is properly aligned with the magnetic heads.

When the transport is in the play and record modes, solenoids press the capstan idlers against the tape, clamping it to the capstan to prevent it from slipping. The tape is moved past the income idler and capstan, past the erase and record heads, and around the reversing idler. From the reversing idler, it passes the play head, and the outgoing idler and capstan. During fast-forward and rewind, solenoid-actuated tape lifters hold the tape away from the tape so that signals on the tape will not be played back, which would cause an annoying squeal. The tape lifters are inactive in play, record, and stop modes.

The play head is enclosed in a magnetic shield to avoid pickup of noise from surrounding equipment and bias-frequency energy radiated by the erase and record heads. A solenoid-actuated cover is positioned over the tape as it passes the play head and serves to complete the shielding of the head. During fast-forward, rewind, and stop, the hinged cover is moved away from the head to allow the tape to be lifted by the tape lifters and allow easy threading of the tape. The cover is closed during play and record.

TAPE TRANSPORT CIRCUIT DESCRIPTIONS

The following circuit descriptions relate to figure 31 which must be used to follow the discussions. In the schematic, connector terminals are shown as small rectangles with the connector and terminal numbers inserted.

Power Circuits

A standard, three-wire power cable is provided, which must be connected at J1. The third, or ground, lead must be connected to a good earth ground; otherwise the recorder will not meet dynamic range specifications in regards to hum, harmonic buzz, or radio-frequency fields. The power is normally 60 cycles, 105 to 125 volts, but 50 cycle models for the same voltage range are available and entail only a change of capstan motor characteristics. The schematic otherwise remains unchanged. For 220 volt operation an external line transformer must be used.

The POWER switch, S6, when operated, closes both sides of the input line activating a number of circuits. These are as follows:

1. Bridge rectifier CR46 through CR49 charges capacitor C65 through R60 approximately 165 volts in the absence of a load. This voltage is applied through J7-2 and J9-1 to the fields of the takeup and rewind motors. Field returns are through J7-1, and J9-2 through J6-4, and K1 contacts 6 and 10. Relay K1 operates as soon as power is turned on unless the transport has been previously threaded with tape.

2. Power is supplied from terminals J4-11 and J4-12 to the various electronics modules through an interconnecting cable.
3. Power is supplied to step-down transformer T60 from terminals TB3-2 and TB3-1. The low-voltage secondary feeds terminals J5-2 and J5-3. A full-wave bridge on the board, consisting of CR37 and through CR40 supplies charging current through terminals J5-5 and J5-1 to C66 and regulator transistor Q60. Zener Diode CR50 is supplied from R14 and establishes a voltage reference of 27 volts, applied through R15 to the base of amplifier transistor Q1. The collector of Q1 is directly coupled to the base of Q60 and the output collector potential of Q60 establishes the emitter voltage of Q1. The two transistors thus act to regulate the bus potential (approximately 26.5 volts). When power is applied the bus potential lights POWER indicator DS6, and the tape sensing lamp DS8. If fail-safe brakes are furnished, L6 operates to release them. As the solenoid approaches the end of its stroke, S15 is opened to reduce current in L6 by insertion of R73. Without tape on the machine, light from DS8 falls on photo sensor V60. The base of Q61 is thereby held near ground potential. The collector at Q61 is then at a relatively high potential causing Q62 to increase conduction. Current flows through Q62 to relay K1 through J6-7 to operate relay K1. Through K1 contacts 11 and 7, voltage is applied through J6-9 to J3-N, to light an indicator lamp on the Remote Control; if used, to show that the machine is on but inoperative due to the absence of threaded tape. The playback head shield cover door is caused to open through CR-25, J6-14, and TB1-1 with a return path through TB1-2. Also at this time, K1 contacts 12 and 4, and 11 and 3 are open and the 27 volt bus can perform no further function. Because of this, the machine may not be put into any mode of operation until tape is threaded on the machine.
4. A path is prepared through J5-F to J5-D and P11-2J to furnish power to the capstan motor, but this is kept open by K1 contacts 1 and 9 when tape is not threaded. The capstan motor is energized through J8-7 and S8 to either J3-8 or J8-4. The quadrature winding of the motor is supplied through C64 and R63 and through S8 to either J8-5 or J8-6. Motor return leads, depending on the speed selected by S8, are through J8-1 and J8-2, or J8-1 and J8-3 back to switch S6 through P11-J1. When power is supplied to the capstan motor it is also supplied to bridge rectifier CR42 through CR45. The dc output of the bridge is applied through J5-J, R68, and TB2-3 to a solenoid, which pulls the motor pulley physically into contact with the capstan flywheel tire. Return path of the solenoid is through TB2-2 and J5-7. Filter capacitor C68 prevents induction of hum from the solenoid into the playback heads.

5. Power is applied to J3-c and J3-d for application at the remote control position, if required.
6. The fan is normally connected across TB1-4 and TB1-6 where it is operated only when the capstan motor is running. By removing the fan lead on TB1-4 and connecting it to TB1-5, the fan will run whenever the power switch is on.

Threaded Tape Condition

When a reel of tape is placed on the supply hub, the free end is passed through the incoming side of the Isoloop, past the capstan and record head, and around the reversing idler, then between the outgoing side of the capstan and its idler. When the tape is dropped into position at this point, light is cut off from V60 causing relay K1 to release. CR-1 is a surge protective diode.

When K1 contacts 11 and 7 open, the head shield cover is closed because the door solenoid is released and the remote TAPE RUNOUT lamp goes out.

Closure of K1 contacts 11 and 3, and 12 and 4 applies bus potential through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3, and K5 contacts 12 and 4 through J5-14 to light STOP lamp DS3; and a path through CR13 and R5 charges C3, and operates K4. Several other paths are likewise made ready. Opening of K1 contacts 10 and 6 inserts R9 in the return path of the reel motor fields and the voltage developed across this resistor is applied through K5 contacts 1 and 9, K6 contacts 1 and 9, K7 contacts 1 and 9 through J6-A to the armature of the rewind motor. A similar path applies the same voltage to the takeup motor through K5 contacts 2 and 10, K6 contacts 2 and 10, K7 contacts 2 and 10, and J6-2. The torque so generated is very small; sufficient to remove slack from threaded tape but not enough to cause motion of the tape from a large-diameter reel to a smaller one. When the end of the tape is threaded into the takeup reel, the transport is ready to be put into motion from its standby condition.

From Standstill to Play

Bus potential exists on switch S5 through J6-D, J2-9, and J2-10. Closure of the PLAY pushbutton applies this through J6-18 and CR4 to operate relay K3 momentarily. Through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3, and K3 contacts 8 and 12, K5 is caused to operate. Release of the PLAY pushbutton releases K3 but K5 remains locked up through K5 contacts 8 and 12, K8 contacts 3 and 11, etc. PLAY lamp DS5 remains lit through J6-17 since it is in parallel with the coil of K5. This same supply immediately operates the ingoing capstan idler solenoid through TB2-1, clamping the tape gently, under control of a dashpot, to the capstan. The break at K5 contacts 12 and 4 removes bus voltage from C3 and the coil of K4 so that after approximately 0.5 second, K4 releases. Closure of K4 contacts 11 and 3 applies bus power to J6-12 and TB2-3 and operates the outgoing capstan idler solenoid. This occurs after the tape has accelerated to

running speed under control of the ingoing solenoid. In one-inch capstan machines, C3 is rated at 500 μ F to delay the operation of the outgoing solenoid an additional 0.4 second.

When K5 operates, the transfer of K5 contacts 2 and 10, to 6 and 10, applies full dc power through K4 contacts 6 and 10, K5 contacts 6 and 10, K6 contacts 2 and 10, and K7 contacts 2 and 10 to the takeup motor armature and a reasonably high hold-back torque to the supply motor through K4 contacts 6 and 10, R8, K5 contacts 5 and 9, K6 contacts 1 and 9, and K7 contacts 1 and 9. After the tape is up to speed and K4 released, the break at K4 contacts 6 and 10 inserts resistors R61 and R62 in the armature paths to establish proper winding and holdback torques since acceleration conditions are replaced by constant-velocity operation.

From Play to Stop

Directly beneath the takeup reel hub on the takeup motor shaft is mounted a ball bearing. The outer race of this bearing is not rigidly mounted but is centered in a light-weight vane. The vane would rotate with the takeup motor shaft but is prevented from doing so by two posts. The vane rests against one post when the motor turns in one direction and shifts through an angle of about 15 degrees to rest against the other post when the motor turns in the other direction. The vane carries a small magnet, which causes operation of reed switch S13 when the motor runs in the forward direction. Switch S13 is released and S14 is caused to close when the motor turns in the reverse direction.

With the machine in the play mode, if the STOP pushbutton is pressed, the following takes place: Bus voltage is applied from K3 contacts 10 and 2 through J6-11, J2-12, J2-11, and the closed contacts of S3, through J6-8 to operate relay K8. Bus power from J6-D is applied through S13, which is closed in the forward direction, through J5-18, K8 contacts 6 and 10 to operate K7. Relay K7 closes a holding path for relay K8 through K7 contacts 12 and 8, K8 contacts 8 and 12, to K8 terminal 14, so that K5 and K6 both remain operated after pressure is removed from S3. The REWIND lamp is lit through K7 contacts 11 and 7. The break at K8 contacts 3 and 11 opens the holding circuit for K5 and it releases, extinguishing the PLAY lamp and dropping out the capstan idler solenoids so as to unclamp the tape from the capstan. Operation of K7 provides full torque power through K7 contacts 5 and 9 and through J6-A to the rewind motor, while the break at K7 contacts 2 and 10 removes all takeup motor torque, bringing the tape to standstill and attempting to start it in the reverse direction. Motion of the tape in the opposite direction, however, causes the vane in the sense switch assembly to leave its former position against the forward stop and swing toward the reverse stop. When the magnet moves away from S13, this switch opens, dropping out K7. This applies a light holding torque to the tape. When K7 releases, it releases K8 by opening K7 contacts 7 and 11. Relay K4 is held closed through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3, K5 contacts 12 and 4, CR13 and R5. It was previously operated through K7 contacts 12 and 8, CR14 and R5. With the exception of K4, all relays are de-energized and STOP lamp DS3 is lit.

From Stop to Rewind

With the machine in standby, pressing REWIND pushbutton S2 causes bus voltage to be applied through K3 contacts 10 and 2, J6-11, J2-12, J2-11, S3, S2, J5-R, and K8 contacts 2 and 10 operate K7. The relay applies rewind torque through K7 contacts 5 and 9 as outlined above, and K7 locks up to the power bus through K7 contacts 11 and 7, and K8 contacts 2 and 10. The tape accelerates in the rewind direction with full power on the armature of the rewind motor. Since this is a dc shunt motor, it would reach a certain terminal velocity at which time tape would be loosely wound except for the following feature. As the tape comes up to speed in rewind, the armature of the takeup motor is open circuited because of the break at K7 contacts 2 and 10. It operates as a dc generator without load until a definite terminal voltage is reached, the voltage rising as the speed increases. Zener diode CR53 will not pass current until the potential across it reaches 75 volts. Therefore, when the generated voltage reaches this level, current flows through J9-4, J6-S, CR32, CR53, J6-2 and J9-3 to act as a load and effective brake on the takeup motor, limiting the maximum speed at which it will supply tape and thereby providing a controlled tension in the reel being filled. Closure of K7 contacts 12 and 8 provides a path through CR24, J6-14, and TB1 to open the head shield door and through J6-15 to operate the tape lifters.

From Rewind to Stop (Tape Moving in the Rewind Direction)

Pressing STOP switch S3 operates relay K8 through K3 contacts 10 and 2, J6-11, J2-12, J2-11, S3, and J6-8. Since tape is moving in the rewind direction, the sense switch vane has caused S13 to open and S14 to close. Therefore, K6 is caused to operate through J6-D, S14, and K8 contacts 5 and 9. Relay K8 is locked up through K6 contacts 11 and 7, K8 contacts 8 and 12, and K6 is held up by S14. Relay K7, however, is released by the break at K8 contacts 10 and 2 and the fact that S13 is open. The power that was supplied to the rewind motor through K7 contacts 5 and 9 is removed by its release and transferred through operation of K6 through K6 contacts 6 and 10 to the takeup motor, which now operates to bring the tape to standstill and attempts to reverse it to the forward direction.

As soon as the sense switch vane moves away from S14 toward S13, S14 opens releasing K6 and placing all circuits in the standby condition. During the stopping interval, the REWIND lamp goes out and the FORWARD lamp is lit from release of K7 and operation of K6. In standby, the tape lifter solenoid is released and K-8 is released by the break at K-6 contact 7 and 11. The head cover door remains operated through S-12, J6-M and CR-26 unless manually overridden to break S-12. Relay K4 remains energized throughout the above action, either through K7 contacts 12 and 8, CR14; or through K6 contacts 11 and 7, CR14; or through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3 and K5 contacts 12 and 4 and CR13.

From Rewind to Stop (Tape Moving in Forward Direction)

It is possible while shuttling the tape at high speed to have the tape moving in the forward direction but to have the controls in the rewind mode. If the STOP pushbutton is pressed at this time, K8 is energized in the manner described above; however, K7 is not released in favor of K6 because the sense switch vane is in position to cause S13 to be closed and S14 open. Thus K7 remains energized and the tape comes to standstill and attempts to reverse at which time the sense switch opens S13, releasing K7 and putting the machine in standby. At this time the tape lifters are released and K8 is released by the break at K7 contacts 8 and 12. The door solenoid remains energized through S12 unless overridden manually to break S12.

From Stop to Forward

With the machine in standby, pressing the FORWARD pushbutton causes bus voltage to be applied through K3 contacts 10 and 2, J6-11, J2-12, S3, S2, S4, J5-S, CR17 and K8 contacts 1 and 9 to operate K6. Relay K6 applies full torque to the takeup motor through K6 contacts 6 and 10, K7 contacts 2 and 10, J6-2, and J9-3, causing tape to accelerate in the forward direction. Relay K6 locks up to the power bus through K8 contacts 9 and 1, K6 contacts 8 and 12, and K7 contacts 3 and 11. Motor speed is limited by the action of Zener diode CR52 as described before.

Closure of K6 contacts to 11 and 7 provides a path through CR24 to open the head shield door and through J6-15 to operate the tape lifters.

From Forward to Stop (Tape Moving in Forward Direction)

Pressing STOP switch S3 operates relay K8 through K3 contacts 10 and 2, J6-11, J2-12, J2-11, S3 and J6-8. Since tape is moving in the forward direction, the sense switch has caused S13 to be closed and S14 to be open. Thus, K7 is operated through J6-D, S13, J5-18, and K8 contacts 6 and 10. Relay K8 is locked up through K7 contacts 12 and 8, and K8 contacts 8 and 12. Relay K6, however, is released by the break at K8 contacts 9 and 1. The power that was supplied to the takeup motor through K6 contacts 6 and 10 is removed by its release and transferred through closure of K7 contacts 5 and 9 to the rewind motor, which now operates to bring the tape to standstill and attempts to reverse it to the rewind direction. As soon as the sense switch moves by reversal of tape motion, it releases S13, releasing K7 and placing all circuits in standby. During the stopping interval, the FORWARD lamp goes out and the REWIND lamp lights because of the release of K6 and operation of K7. In standby, the tape lifter solenoid is released. K8 is released by K7 contact 8 and 12. The door solenoid remains energized through S12 unless manually overridden to break S12.

From Forward to Stop (Tape Moving in Rewind Direction)

It is possible, while shuttling tape at high speed, to have the tape moving in the rewind direction but to have the controls in the forward mode. If the STOP button is pressed at this time, K8 pulls in in the manner described above. However, K6 is not released in favor of K7 because S14 is held closed by the sense switch vane while S13 is open. Thus, K6 remains operated and the tape comes to standstill and attempts to reverse, at which time the sense switch opens S14, releasing K4 and putting the mechanism in standby. At this time the lifter solenoid is released, and K8 is released by the break at K6 contact 7 and 11. The Door solenoid remains operated through S12 unless manually overridden to break S12.

From Forward to Rewind

Considering the tape to be in the forward mode regardless of its actual direction, relay K6 is energized. Pressing the REWIND pushbutton closes a circuit to operate K7 through K3 contacts 10 and 2, J6-11, S3, S2, J5-R, K8 contacts 2 and 10 to K7-14 through K7-13, CR19 and R6 to ground. Relay K7 operates, opening the holding path for K6 at K7 contacts 3 and 11, which releases, further breaking its holding circuit at K6 contacts 8 and 12. Torque power to the reel motors is therefore reversed. Relay K7 locks up through K8 contacts 10 and 2, and K7 contacts 7 and 11.

From Rewind to Forward

Considering the tape to be in the rewind mode regardless of its actual direction, relay K7 is energized. Pressing the FORWARD pushbutton closes a circuit to operate K6 through K3 contacts 10 and 2, J6-11, J2-12, J2-11, S3, S2, S4, J5-S, CR17, and K8 contacts 1 and 9 to K6-14. Because J5-S applies bus potential to CR20 as well as to CR17, the coil of K7 is effectively shorted, since the total voltage appears across R6. This releases K7, K6 remains operated over the path K7 contacts 11 and 3, K6 contacts 12 and 8, and K8 contacts 1 and 9. Torque to the reel motors is therefore reversed.

From Rewind to Play

In the rewind mode, regardless of actual direction of tape motion, relay K7 and K4 is energized. Pressing PLAY pushbutton S5 causes bus power to flow through J6-D, J2-9, J2-10, S5, J6-18, and CR4 to operate K3. A holding path is established through K7 contacts 12 and 8, K3 contacts 11 and 7, R1, CR8 and CR7 so that K3 will not release when S5 is released. Relay K3 contacts 10 and 2 open the paths to S3, S2 and S4 pushbuttons to render them inactive at this time. The potential from K7 contacts 12 and 8 through K3 contacts 11 and 7, and through R1 also feeds through CR9 to terminal 14 of K8 causing it to operate. Because this action opens the holding path of K7 through K8 contacts 10 and 2, and K7 contacts 7 and 11, an unstable condition could arise, but this is prevented by the charge in C12, which continues to hold K8 until the transfer of K7 is completed if need be. Whether K7

continues to hold or to transfer to K6 is determined by the direction the tape is moving as outlined above. In any event, operation of K8 functions to bring the tape to standby condition. When K6 or K7 is released by the sense switch as the tape reaches standstill and attempts to reverse, the break at K6 contacts 7 and 11 or K7 contacts 8 and 12 releases K8. Normally, the machine would now remain in standby, but at this time K3 is still operated even though its supply path through K3 contacts 7 and 11 is open. This is because it is held by the charge in C1 for sufficient time to perform an additional function. When K8 releases, bus power is supplied through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3, and K3 contacts 8 and 12 to operate K5. The functions from here on are as described under "From Standstill to Play."

From Forward to Play

In the fast-forward mode, regardless of actual direction of tape motion, relay K6 and K4 is energized. Pressing PLAY pushbutton S5 causes bus power to flow through J6-D, J2-9, J2-10, S5, J6-18, and CR4 to operate K3. A holding path is established for K3 through K6 contacts 11 and 7, K3 contacts 11 and 7, R1, CR8, and CR7 so that K3 will not release when S5 is released. Relay K3 opens the paths to S3, S2, and S4 pushbuttons to render them inactive at this time. The potential from K7 contacts 12 and 8 through K3 contacts 11 and 7 and R1 also feeds through CR9 to terminal 14 of K8 causing it to operate. Because this action opens the holding path for K6 through K8 contacts 9 and 1 and K6 contacts 8 and 12, an unstable condition could arise but is prevented by the charge in C12, which continues to hold K8 until the transfer of K6 is completed, if need be. Whether K6 continues to hold or to transfer to K7 is determined by the direction of tape movement. In any event, operation of K8 functions to bring the machine to a standby condition. When K6 or K7 is released by the sense switch as the tape reaches standstill and attempts to reverse direction, the break at K6 contacts 7 and 11, or K7 contacts 8 and 12, releases K8. Normally, the machine would now remain in standby but at this time K3 is still energized even though its supply path through K3 contacts 7 and 11 is open. This is because it is held by the charge in C1 for sufficient time to perform an additional function. When K8 releases, bus power is supplied through K7 contacts 11 and 3, K6 contacts 12 and 4, K8 contacts 11 and 3, and K3 contacts 8 and 12 to energize K5.

Tape Runout

When the tape runs out from any mode of operation, the light from lamp DS8 falls upon photo diode V60, causing K1 to energize. This action opens the bus supply to all other relays. All power is therefore removed from the armatures of the take-up and rewind motors. A short circuit is applied to the armature of each motor. One such circuit is through J9-4, J6-S, K1 contacts 10 and 6, J6-4, J2-1, J2-2, J5-P, K5 contacts 2 and 10, K6 contacts 2 and 10, K7 contacts 2 and 10, J6-2 and J9-3. The other circuit is through J7-4, J6-S, K1 contacts 10 and 6, J6-4, J2-1, J2-3, J5-V, K5 contacts 1 and 9, K6 contacts 1 and 9, K7 contacts 1 and 9, J6-A, and J7-3. Since the fields are fully excited, this system acts to brake the motors to a standstill since they operate as dc generators operating into a short circuit.

Record Mode Operation

The record mode can be selected only when the PLAY lamp is lit, indicating that the machine is running at normal speed. It is then necessary to press both the RECORD and RUN pushbuttons simultaneously. Bus power is applied through J6-D, J2-9, J2-10, S5, S1, J5-13, and K3 contacts 7 and 11 to operate K2, which then locks up to the holding path for K5. This path is K5 contacts 8 and 12, and K2 contacts 8 and 12. The path established to hold K2 then lights DS1 through J6-3 and supplies positive bus voltage to the electronics power cable through connector J4-9. Relay K2 contacts 11 and 7 also supply ground potential to the same connector through J6-T to J4-10. The positive potential is also applied through R16 and CR29 to the bias oscillator. Capacitor C7 is provided both for decoupling and for delayed decay after power is removed. Transistors Q2 and Q3 operate as a low power, push-pull oscillator to provide a high-frequency signal to terminals J6-U and J6-V. The electronics assembly cable conducts high-frequency bias to all bias boards in the electronics through J4-1 and J4-2. The oscillator is tuned to 120 kHz by capacitor C11.

Speed Change Switch

Speed change switch S selects windings of the capstan motor to provide either of two speeds. These are related by the ratio 2:1 and therefore can be provided for tape speeds of 3-3/4 and 7-1/2 ips, 7-1/2 and 15 ips, and 15 and 30 ips, etc. Dc bus potential is supplied to either J4-6 or J4-7 in the electronics power cable, depending on the motor speed, in order to control equalizer-select relays in the electronics circuit boards.

Reel Size Switch

Reel size switch S7 provides for adjustment of torque in fast forward or in rewind when one spindle carries the normal large reel and the other carries a light-weight reel. If both reels are the same size, the switch is left in the center BALANCE position. If the large reel is on the tape takeup side, the switch is moved toward the right, or toward the large reel (in the direction of the arrowhead on the panel). If the large reel is on the left, or supply side, the switch is moved to the left. In the center position, S7 connects J5-N to J6-1 and J5-15. If K6 is energized, putting the machine into fast forward, heavy dc current flows through the takeup motor, returning to the negative supply through R60. Thus J5-L is a few volts more negative than J6-S. This negative potential is applied through CR30, S7, and R11 to the rewind motor, causing it to develop small torque in the same direction the takeup motor tends to turn. This aids acceleration. Similarly, in rewind, R10 supplies reverse torque to the takeup motor, assisting in getting the tape up to high speed. When a small reel is on one side, however, this assistance is not desirable since it may tend to unwind tape faster than the other

reel can spool it. Thus S7 provides for breaking the negative line through R10 or R11 as needed. This feature is only applicable to 1/2 and 1-inch machines. The switch, although provided, is inactive in 1/4-inch machines.

TORQUE CONTROL RELAY (1/4-inch machines only)

Due to the light weight and inertia of the small plastic reels commonly used on 1/4-inch machines, there is a tendency for a loop to form in the tape between the outgoing tape guide and the reel receiving the tape if negative torque is applied through R10 or R11 before the tape has come to rest and started to move in the opposite direction. To prevent reverse torque from being applied until the tape has begun to travel in the direction of the selected mode, K13 is installed in the socket provided on the transport near the rewind motor. Reel size switch S7 is not connected as stated above.

Consider the tape to be in motion in the fast forward direction with K6 energized. Pressing the REWIND pushbutton energizes K7 and releases K6. Drive torque is immediately transferred from the take-up motor to the rewind motor. Due to the momentum of the reels traveling in the forward direction, the tape does not come to an immediate stop but continues to travel in the forward direction until this momentum is overcome by the dynamic braking action caused by the reverse torque applied to the rewind motor, which is attempting to pull the tape in the opposite direction. During this slow down period, directional sense switch S14 is open, which maintains K13 in the deenergized position. Therefore, the circuit path to the take-up motor armature is broken at K13 contacts 5 and 9, causing the motor to coast to a stop under the braking action of the rewind motor only. As the tape motion comes to rest and starts to reverse its direction, S14 closes. Buss power is applied to K13, providing negative torque power through contacts 5 and 9, R10, etc., to the take-up motor and causing it to turn in the same direction as the rewind motor. This action reduces the drag on the rewind motor and aids acceleration as described under "Reel Size Switch." Thus, K13, in conjunction with directional sensing switch S14, prevents negative torque power from being applied to the appropriate reel motor until the tape has come to rest and starts to accelerate in the opposite direction.

Monitor Switching

Two pushbuttons on the transport, S10 and S11, are arranged to transfer the output line amplifier and VU meter of each electronics circuit board from the incoming signal source to the playback and vice versa. Pressing A switch S10 applies bus voltage from J6-D through J2-9, J2-10, and S10 to J4-5, which is in the electronics power connector, causing operation of transfer relays in each module. Similarly B switch S11 applies bus potential to terminal J4-4 to cause reverse operation of the transfer relays. These switches are momentary-contact types and are not lighted.

Runout Switch

The runout switch is provided on all models of the machine. The sensing circuits associated with the switch are furnished on all series A transports but are furnished on B transports only on special order. When connected, it provides for automatic stopping of the tape before runout, automatic rewind at the end of the tape, and automatic starting of a second machine under either of these conditions. The circuit is actuated when light from an exciter lamp falls upon a photo sensor through a "window" in the tape.

Fail-Safe Brakes

For certain applications, it is desirable to include self-energizing mechanical brakes on the transport to prevent a tape spill if power fails. The fail-safe brakes, which are provided on special order, are released whenever power is on and are applied when the machine is turned off or power interrupted. Solenoid L6 is energized directly from the low-voltage dc supply. When it operates to lift the brakes, microswitch S15 is opened, inserting 150-ohm resistor R73 into its path to prevent overheating of the solenoid winding.

SIGNAL ELECTRONICS FUNCTIONS

Signal electronics consist of record amplifiers, which raise the input signal to a level required by the record (heads), a bias and erase frequency power supply, and equalizer circuits and amplifiers to reproduce the signal recovered by the playback heads. Each complete electronics assembly includes a power supply, controls, and a volume indicator (VU meter).

Signal processing is either in conformance to NAB standards or Dynatrack operation. In Dynatrack recording and playback, two tracks are used. One track records at the standard NAB level, this is the H track; and the other track records the identical information, but records high frequency signals at a higher level (more recording gain), employing a pre-emphasis curve rising 15 db from 400 cycles to 15,000 cycles. When the tape is reproduced, the output is switched between the L and H tracks depending upon the amplitude of the recorded signal. When the recorded signal is at a low level the L track will provide the signal output and, of course, de-emphasis of the previously pre-emphasized signal. When the amplitude of the recorded signal increase to where the distortion of the L track approaches 1 percent, the output will switch to the H track. Switch over from the L track to the H track, and vice versa, is automatic during the reproduce process. The switchover is fast enough so that no discontinuity is apparent to the listener.

The overdub feature allows a record head to be used as a playback head so that a second track can be recorded in synchronism with a pre-recorded signal. This feature avoids the time lag that would occur if the playback head were to be used for monitoring during overdub operation.

NAB ELECTRONICS

One electronics module is employed for each compatible NAB equalized track. Thus, in a 1/2-inch machine having standard four track heads four channels of NAB equalized signals may be recorded. In this case four electronic assemblies are required, equipped with the proper board for NAB service. If it is desired to employ the Dynatrack system, two tape tracks are required to each channel. Therefore, the four-track configuration permits a two channel Dynatrack system and only two electronic assemblies are employed, equipped with the proper cards for Dynatrack operation. Electronic Assemblies are readily converted from Dynatrack to NAB and vice versa by merely changing boards and head cable connectors at the rear of the assemblies. The following describes the operation of a complete electronics assembly arranged for NAB service.

The individual plug-in boards will be fully described after an outline of their function in relation to their service in the overall operation. Refer to figures 37 and 38 during the following discussion. The rectangular dashed areas represent plug-in units. The numbers in ovals represent connector pin numbers.

NAB Recording

The signal to be recorded is applied through connector J101 to the primary of transformer T1, which reflects an impedance of 20,000 ohms to the signal source. Input is through a two-wire shielded cable with the signal lines ungrounded. The secondary of T1 is connected across RECORD LEVEL control R100, which establishes the level of the signal applied to the record amplifier. This amplifier provides pre-emphasis, equalization, and linearization to the signal, and sufficient gain to drive the record head. A relay on the board selects equalization networks for the two tape speeds used. Linearization is selectable by means of a switch on the circuit board and is adjustable. The degree of linearization required depends on the signal level, and corrects for distortion that occurs as the signal level approaches the saturation level of the tape.

A pilot tone, used for tape-speed control, may be introduced by way of connector J111-1, and terminal 16 of the H and NAB Record board, to be mixed with the normal input signal. The pilot tone may be either supersonic or subsonic.

A separate amplifier is included on the H and NAB Record Board to bring the input signal to sufficient level to apply to the monitoring circuits so that this signal may be listened to and observed on the VU meter. A variable control RECORD MON. CAL. enables the meter to be adjusted so that, without the linearizer in service, 3% total harmonic distortion on playback results at 6 db above zero VU.

The main signal from the record board appears on the record relay K101 at terminal 9. It is normally grounded through K101 contact 9 and 1 but when K101 is operated the signal is applied through K101 contact 9 and 5 to the H Bias and Erase Board (1) in slot 1. Whenever the RECORD button on the transport is activated, an oscillator in the transport is energized and provides 120kHz from J110 terminal 1 and 2 to terminals 14 and 15 of this board and all other identical boards in the other electronic assemblies of a multi-channel recorder. A power amplifier feeds the 120 kHz bias signal through a variable resistor BIAS AMP to provide the proper magnitude of bias to the record head through terminal 1. The audio signal from terminal 22 is also passed to terminal 1 through a bias trap circuit which has no effect on the audio signal, but prevents drainage of bias power back through the record amplifier board. A noise balance control is provided which injects an adjustable DC component into the record head to correct for external fixed magnetic fields in the vicinity of the record head gap.

In order to monitor the bias and audio signal mixture by means of an oscilloscope or vtvm, the record head is returned to terminal 2 which is removed from ground by 10 ohms. Monitoring is at the TP BIAS test point and a variable control permits the VU meter, when connected to terminal 3, (set to BIAS) to be calibrated to a fixed number on its scale (-5 VU for example).

A second power amplifier, also driven by the 120 kHz signal, applies its output through terminal 21 to terminal 20 of the NAB Erase Coupler Board (3N) in slot 3. The signal passes through an adjustable capacitance to terminal 11, and from there to the erase head. There is a feedback path through board 3N terminal 19, and board 1 terminal 19, to control the amount of drive of the erase amplifier. The amount of feedback is controlled by the feedback resistor. The amplitude of the erase current may be monitored at the TP. ERASE test point on board 3N. The VU meter may be calibrated by variable resistor ERASE MON. CAL. which is feeding via terminal 22 to the VU monitor. Typical calibration provides 0 VU when erase current is adequate.

In addition to transferring the record amplifier output from ground to the bias amplifier board, relay K101 also causes indicator lamp DS103 to light through contacts 12 and 8 and applies +28 volts to energize the bias and erase amplifiers at terminal 12 on the H Bias and Erase board (1). Another pair of contacts is used during Dynatrack operation and is discussed under that heading. Inductive surge from the coil of K101 is suppressed by diode CR101.

NAB Reproduction

Signals recorded by the H and NAB record circuits described above are reproduced from the corresponding playback head and applied to the H and NAB preamplifier board in slot 7. The preamplifier board contains high-frequency and low-frequency amplitude equalizers for two tape speeds. The proper equalizers are selected by a relay on the board, which is energized by a voltage introduced through terminal 20. High-frequency and low-frequency equalizer networks are provided for each tape speed. Phase correction networks are selected by another relay with a separate network for each speed. This relay is energized by a voltage introduced through terminal 19. The phase correction networks are not adjustable.

At the pilot connector J111 all signals may be fed out on terminal 2 with return on 5, in order that the pilot, if any, may be extracted free from gain variations occasioned by adjustment of the GAIN CAL. potentiometer which feeds the main audio signal out on terminal 22.

A jumper loop is provided on the terminals 17 and 16 of slot 8 when machines are furnished from the factory with only NAB boards. No card is then provided for slot 8 and the signal bypasses the slot directly to the REC. SELECT switch 103. Since it is necessary to provide a preamplifier and electronic switch card in slot 8 when the Dynatrack system is employed, this loop must be clipped open and later if converted again to NAB operation an NAB conversion card (8N) must be inserted in slot 8 when the Dynatrack card is removed. This card is blank except for a jumper loop between terminals 17 and 16, to again close the loop previously clipped. It is furnished with the Dynatrack conversion kit.

When the REC. SELECT switch is in the RDY position, the record head is connected to the output of the H bias and erase board; +28 volts is supplied from the power and meter assembly in slot 5 through terminal 12 to this switch, to terminal 13 of the record relay so that it may be operated by grounding its terminal 14 through diode CR102; and to terminal 10 of J110 at the tape transport.

The signal from terminal 16 of slot 8 is routed through the REC. SELECT switch to the REPRO. LEVEL control and an attenuator comprising R104 and R105. With the METER switch in the CAL. position, the signal from the attenuator is routed to the line amplifier circuit card in slot 6, where it is amplified and applied to the outgoing line. A selector switch at the output of the line amplifier normally connects the output through terminal 21 to transformer T2, which is provided with impedance matching resistors R108 and R109. The output impedance may be set by means of switch S106 to 150 or 600 ohms. Switch S105 is a three position switch providing 150-ohm, or 600-ohm termination of the outgoing line when it is not terminated externally. The outgoing line connects to connector J102. When the selector switch at the amplifier output is set to route the signal to terminal 20, an 8-ohm loudspeaker may be driven directly from terminal 3 of PILOT connector J111.

Speaker return is to terminal 6. Earphone monitoring is provided by jack J103. This jack is "floating" and headphone leads should not be grounded. The output signal from T2 is applied through terminals 2 and 4 of the line amplifier board to an attenuator which supplies the attenuated signal for the VU meter through terminals 3 and 4, through the METER switch in positions 1 and 2, to terminals 14 and 16 on the power and meter assembly. Resistors in the attenuator may be changed to modify the working level from the +4 dbm normally provided. See table 10. Choice of 150-ohm or 600-ohm output does not appreciably modify the VU meter reading.

Since the meter attenuator is fixed for any given operating line level, and the fixed gain attenuator R104 and R105 is selected in the CAL. position of the METER switch, it is only necessary to adjust the GAIN CAL. potentiometer on the playback preamplifier board (7 and 7/9) to assure that a standard reference level tape is reproduced at the proper indicated level. Typically, such tapes provide a reference tone of 700 cycles which should read zero VU, attainable by adjustment of this control.

Having been so calibrated, the METER switch may be turned to the SIGNAL position. The REPRO. LEVEL gain control is then substituted for the calibrated attenuator, to provide convenient adjustment of playback level. When in this position, the signal output may be either the tape playback or the input signal. This transfer is provided by K102 contacts 8, 4, and 12 under control of pushbuttons S101 and S102, the A-B output selectors.

Note that when the METER switch is in the SIGNAL, ERASE, and BIAS positions, the audio signal is always fed in the same manner to the output, although the meter is connected to various circuits.

The Meter and Power Assembly, located in slot 5, is powered from the transport through J110 terminals 11 and 12. It provides regulated +28 volts at terminal 12 of all electronics. Non regulated dc is provided at terminal 18 to power the coil of K102 and the A and B lamps. 24 volts AC is provided at terminals 2 and 3 for external use, if needed. A resistor may be replaced with alternate values to provide control of the girthness of the lamps in a remote meter fed from terminals 3 and 7 through the remote meter connector J109 terminals 3 and 6.

One position of the REC. SELECT switch, S103, has been discussed, the RDY position. In the SAFE position the coil of K101 is opened so that the record electronics are locked off to provide maximum protection for previously recorded tapes. All other circuits remain normal. In the O. DUB position the record head is completely disconnected from its normal feed and becomes a playback head.

When the record head is so connected, it feeds terminals 10 and 14 of the Overdub Preamplifier (7/9) in slot 9. This preamplifier is identical to the H and NAB preamplifier previously described except for the addition of an input transformer. When the record head is used in playback it matches closely the frequency response and gain of the normal playback head. Due to its wider gap, however, the extremely high frequencies suffer some attenuation depending upon the tape speed.

If the overdub feature is desired, it is highly recommended that a separate preamplifier be employed in each position; a 7 board in slot 7 and a 7/9 board in slot 9. It is not necessary that the user have both the H and NAB Preamplifier and the Overdub Preamplifier since the latter may be extracted from slot 9 and re-inserted in slot 7. The input transformer is then bypassed and operation is identical to the normal preamplifier.

DYNATRACK ELECTRONICS

Read the above description of the NAB electronics for more details of certain aspects of the electronics common to both systems. Refer to the electronics block diagram, figure 34.

As in the description for NAB above, the signal is recorded directly on the H or NAB track. There is a tap in the H and NAB Record Board which is not used for normal NAB recording, but which feeds out the signal fully equalized for NAB operation on terminal 2. This is applied to the L Record and Bias Board (3D) in slot 3. Note that this replaces the NAB Erase Coupler Board (3D) used for NAB recording. Board 3D provides a record amplifier to drive the second, or L, record head; and it includes the special equalizer required by the Dynatrack system. It includes a linearizer as previously described. Its output through terminal 15 is fed to the record relay K101, where it is normally grounded by contacts 10 and 2.

During recording, the signal is fed from K101 contacts 10 and 6 back to terminal 16 where it passes through a tuned bias trap, and picks up bias injected at terminal 21. The signal goes out on terminal 18 to the record head for the L track. The record head return lead is to ground. TP. BIAS provides a test point and the BIAS MON CAL. control permits calibration of the VU meter to indicate proper bias current for the L track when the meter switch is in the ERASE position.

Terminals 11 and 20 have no connection on this board; these were used to furnish power to the erase head in the NAB configuration. When Dynatrack is employed no erasing facility is provided. Instead, the erase power amplifier on the board in slot 1 is used to feed power on terminal 20 to terminal 21 on the L Record and Bias Board, where the BIAS ADJ control provides adjustment of bias current in the head. The feedback resistor feeds from terminal 19 of the H Bias and Erase Board and in this case a lower resistance holds down the excitation of the amplifier to a greater degree than when it is used for erase power.

The LEVEL control on the Dynatrack L Record Amplifier board provides for proper adjustment of the recorded level of the L track with respect to the H track, for any given frequency. On playback the H track is reproduced in the normal manner by the board in slot 7 as described above. The L track, on the other hand, is reproduced by the L Preamp and Switch Board (8D) which must be inserted in

slot 8. As described above, when this is employed the NAB conversion board (8N) must be removed from slot 8 to break the connection between terminals 17 and 16. If this board was not previously provided the link between terminal 17 and 16 behind the connector must be cut, since it is necessary for the signal from the H track to pass through the electronic switch on the L preamp and Switch board.

In addition to providing a preamplifier, it is necessary for this board to provide equalization to deemphasize the specially recorded characteristic of the L track. Thus at terminal 16 the signal is identical in frequency response and level to that from the H track coming in on terminal 17.

Since the L track is recorded at a much higher level than the H track for some frequencies, it is necessary to switch from "L" to "H" at high signal levels, and this is done by the electronic switch under control of its Schmitt trigger. The switching level is determined by the setting of the TRIG. control. Following the switch an output amplifier feeds the signal to the line amplifier, etc., in exactly the same manner as previously described. The L preamplifier and switch board also includes variable equalizers to permit adjustment of overall frequency response, and phase equalization for 15 ips, since the Dynatrack system is designed to be operated only at this speed.

DETAILED CIRCUIT DESCRIPTIONS

The following paragraphs contain detailed descriptions of each of the circuit boards, and the Meter and Power Supply Assembly.

H and NAB Record Amplifier (4) (See Figure 39)

The input signal to be recorded is applied at terminal 14, after it has passed through the input transformer and level control. C1 couples it to Q1, which is biased to the proper operating point by R1 and R2. After amplification the signal is coupled by C3 to an equalizer network, producing a preemphasis characteristic at the high and low frequency extremities of the spectrum in accordance with standard NAB practice. This is accomplished as follows.

Consider R6 and R7 as an attenuator network, with R8 short circuited, as it effectively is at high frequencies because of C4 and C5. This attenuator network reduces the voltage swing at the junction of R6 and R7 from what it was at collector of Q1. However, if a bypass capacitor C18 or C19 is connected across R6 it permits the high frequencies to suffer less attenuation. The degree to which this is true depends on the setting of the variable capacitor. Practical values of C18 and C19 make it necessary for the junction of R6 and R7 to appear always as a very high impedance. Current cannot be drawn from this point without upsetting the equalization characteristic. Thus, the junction is used to drive a field effect transistor, Q2. C4 and C5 show increasing impedance as the signal frequency is lowered;

therefore, the voltage at the junction of R6 and R7 would continue to rise as the frequency drops, except that R8 provides a shelving off to prevent unnecessary sensitivity to subaudible frequencies.

Relay K1 automatically changes the high frequency equalization when tape speed is changed. The output of Q2 is applied to terminals into which may be inserted values of C8, C20, R11, and R12 to adjust for any requirement arising for shelving equalization in addition to the normal NAB equalizers just described. All four components may be eliminated in many instances, a jumper being furnished across the R11 or C20 terminals.

After this network the signal is fed to the base of Q3 whose bias is set by R13, R14, and R15. This operates with Q4 in a Darlington circuit to provide gain and low impedance output at C11 to drive the NAB record head. R18 normally provides a degree of degeneration, determined by the setting of R20, and R19 in series with C12, and C21. But the degree of degeneration can also be reduced by conduction of Q5 and Q6 when S1 is closed. Q5 and Q6 act to change the degeneration with instantaneous signal amplitude, thus they tend to deform the signal whenever its amplitude attains a value sufficient to overcome their contact potential. This results in a distortion, inverse to that which overload of the tape normally introduces. By employing Q5 and Q6 in this manner, and properly adjusting the overall degeneration by means of R20, the LIN ADJ. control it is possible to introduce the proper corrective distortion into the recording process so that the normal 3% tape distortion point shows somewhat less than 1%.

C11 feeds the record head connected at terminal 22. R22 is a resistor in series with the head to establish a constant current characteristic. R23 provides a high resistance path to ground so that the ground side of C11 will always be discharged, even when no head is connected to terminal 22. This is a means of preventing accidental record head magnetization.

The signal effective in driving the record head may be extracted at terminal 2 to be applied to the L track record amplifier when the Dynatrack system is employed.

Terminal 16 provides a point for injecting a pilot frequency for playback tape speed control. This is useful in motion picture synchronization. The pilot for either a high or low frequency system may be employed. C14 couples the input signal to Q7. The gain of Q7 is adjusted by the combination of emitter resistors R27 and R28, which is bypassed by C16 to provide the proper range of signal levels to R30. This control, RECORD MON CAL., can be conveniently adjusted to serve the input signal audio monitoring and input signal VU meter monitoring circuits. R29 and C17 are provided to give a slight rise in output at 15 kc to make up for losses in the input transformer, wiring, and meter sensitivity occurring at the extreme end of the spectrum.

L Record and Bias (3D) (See Figure 38)

Signals to be recorded are first applied to the NAB record board (H and NAB Record Amplifier) (4), and after proper equalization to obtain the NAB recording characteristic, the signal is fed to this board at terminal 2. Since this amplifier must adequately record signals of extremely low level, it is essential that it contribute a minimum of self-generated noise. Therefore, Q1 which must be fed from a comparatively high impedance source, is a field effect transistor. Its output feeds the LEVEL control whose output feeds Q2. Since R9 is a relatively high resistance, 510 ohms, degeneration is high in this stage. It is bypassed by the network R7, C5, and C6; and these capacitors begin to take effect above 400 Hz, causing the gain of the stage to rise. R7 provides a limit to the rise so that the gain of Q2 shelves off at 15 kHz, 8 db above its 400 Hz value. The output of Q2 is coupled to Q3 where a similar operation occurs with about 7 db lift at 15 kHz. These two equalizer amplifiers provide a rising frequency response starting at 400 Hz and shelving flat at 15 kHz with a total of 15 db rise. This gives the distinctive record equalization of the Dynatrack system. L1 and C8 constitute a series resonant bias trap (120 kc). The signal from Q3 is applied to the Darlington amplifier Q4 and Q5, and the output and linearity features are the same as described above for the NAB record board.

The signal output from this record amplifier goes from terminal 15 to the record relay, then returns to terminal 16, going through the bias trap L2, C19 to terminal 18 and then directly to the record head. Bias power from the bias and erase board is applied at terminal 21. C16 tunes the output stage of the bias amplifier to resonance through the return lead on terminal 13. R31, fed from C18 provides feedback control of the bias power amplifier by connection to terminal 19. R32 BIAS ADJ. adjusts the amount of bias applied to the record head.

CR1 and CR2 feed both ends of the NOISE BAL. potentiometer R28. Consider the wiper run up to the top. CR1 then supplies a positive potential directly to R29. R30 allows some current of positive polarity to leak through R32 and the record head. If the wiper is run all the way to the bottom, CR2 supplies a negative polarity and the DC current in the head is in the opposite direction. By varying the position of the arm more or less DC current can be permitted to flow through the head in either direction to balance out residual magnetization of the record head or strong external constant magnetic fields, during the recording process.

Terminals 14, 17, and 22 provide connection to the VU meter when the METER switch is in the ERASE position. R26, BIAS MON. CAL., provides for calibration of the monitoring meter when it reads the bias strength. When the recording circuit is adjusted to provide proper bias to the head for optimum performance, this control should be adjusted to read -5 VU, and then left without further adjustment for reference purposes.

Bias and Erase Amplifier (1) (See Figure 36)

Whenever the transport is put into the recording mode, a 120 kc signal is generated within the transport, and applied to all electronics assemblies where it appears on terminals 14 and 15 of each Bias and Erase Amplifier. T1 operates as a bridging transformer. It has two secondaries. One of these feeds the base of Q2 through resistor R4. This resistor is employed to permit insertion of a feedback signal from R26. Q1 amplifies the 120 kHz signal and provides sufficient power to drive the push pull amplifier Q5 and Q6. C13 and C14 tune the secondary of T4, and C16 and C17 tune the primary of T5 in order to minimize harmonic distortion. Even order harmonics are particularly objectionable since they result in increased background noise recorded into the tape.

The output of Q5 and Q6 is fed through T5 and C18 to R19 and R24, the latter variable to control the amount of 120 kHz bias signal fed through terminal 1 to the record head. The audio signal comes from the record amplifier and is applied at terminal 22. It passes without loss through the tuned circuit L2, C19, and C21 since this is only tuned to present a high impedance to 120 kHz, thus preventing loss of bias power back into the record amplifier.

CR2 and CR3 each operate as half wave rectifiers. If the arm of R23 is run to the end connected to CR2, then the upper end of R21 will have an average negative potential. Conversely, if the arm is run to the other end, then the upper end of R21 will have an average positive potential. R20 allows current set up by such potential to flow through R19 and R24 to the record head, thereby making it possible to inject a very small but adjustable DC current into the head in addition to the audio and bias frequencies to allow minimization of noise resulting from strong external magnetic fields or even even order harmonic distortion from the bias supply.

These circuits are activated by application of potential at terminal 12. In order to prevent a recorded thump when the record button is depressed, R27 and C20 are provided to permit the DC bias on the base of Q1 to rise slowly, and C15 is provided across R17 for the same purpose on Q5 and Q6. The bias envelope therefore grows to operating level in a matter of about 10 milliseconds. When the recording mode is deactivated another thump or click is avoided by allowing reservoir capacitor C2 to permit the bias waveform to decay to zero over a period of about 60 milliseconds. R1 allows C2 to charge at a reasonable rate when the circuits are activated without causing a surge on the power supply, but CR1 permits the capacitor to be connected directly to the load during discharge. L1 and C1 constitute a filter to stop bias frequency ripple on the power bus connected to terminal 12.

The amount of drive applied to Q5 and Q6 is controlled by feedback resistor R26, which also improves the waveform at the output by cancelling out internally generated distortion products.

The second winding of T1 feeds the 120 kHz signal to an almost identical circuit except that the output transistors Q3 and Q4 have a higher power rating in order to supply the erase head with sufficient drive to completely erase a saturated tape. The description above applies except for a few points. The secondary of T3 is tapped to provide two output impedances. One of these, connected to terminal 21 supplies erase power in the case of a NAB setup. In Dynatrack operation no eraser is excited and power is fed from terminal 20 to the record head of the L channel. This amplifier then operates as a bias supply rather than an erase supply. The feedback resistor, which in this case is external to the board, is connected between terminals 21 and 19 in the erase setup and between 20 and 19 in the Dynatrack setup. The resistor values are naturally different for the two cases. Erase or L bias current is monitored across the 10 ohm resistor R29 between terminals 16 and ground. The NAB or H bias current is monitored from terminal 2, the record head return lead to ground, with R25 providing the meter calibration. This bias current is read on the meter when the meter switch is in the BIAS position.

Meter calibration for the monitoring taken across R29 is accomplished by a control on the L Record Amplifier Board when Dynatrack is employed, or by a control on the NAB conversion board which fits into the slot occupied by Dynatrack's L Record Board (slot 3) when the electronics are converted to NAB operation. In the Dynatrack system the meter then indicates bias for the L track. In the NAB system it reads erase current. In either case, the reading is obtained by putting the meter switch into the ERASE position.

H and NAB Preamplifier (7) (See Figure 42)

This plug-in printed circuit board assembly provides the required signal amplification of the playback head signal to drive the output line amplifier. In addition, the assembly performs the necessary frequency equalization and phase correction for two tape speeds.

The playback head for the NAB or Dynatrack H track is connected to the assembly through terminal 4 which provides the signal path through C1 and R2 to the base of Q1, the first amplifier stage.

The collector of Q1 is direct coupled to the base of Q2, providing a signal path and DC bias to the second amplifier stage. The output of Q2 is direct coupled to the base of Q3. A feedback path is also provided from the collector of Q2 through one of two RC frequency equalization networks to the emitter of Q1. Relay K1 in the normal or deenergized condition (as shown for high speed tape operation) places C7, R18, R19, and R20 in the feedback path. When K1 is energized, C8, R21, R22, and R23 are placed in the feedback path, providing the proper frequency equalization for slow speed tape operation. C7 (or C8) with R20 (or R23) controls the point where the customary 6 db per octave correction becomes no longer effective at higher frequencies. R19 (or R22) controls the point at very low frequencies where the relation again no longer holds true and the amplifier shelves off. The proper operating point for Q1 and Q2 is maintained by the dc bias established at the junction of

R8 and R9 in the emitter circuit of Q2. This dc bias is applied through R5 to the base of Q1, thus providing a controlled amount of negative feedback to Q1 in relation to the input signal level. C4 filters out any ac component present at the junction of R8 and R9.

Q3 operates as a phase distortion correction stage. Considerable rotation of phase normally occurs in the overall process of recording and playing back tape, the situation being increasingly pronounced at shorter wavelengths. In copying tapes, the effect is compounded. Q3 and its associated circuits provide an effective correction for such distortion.

A paraphase signal output condition exists between the emitter and collector of Q3; that is, equal amplitude with 180 degree phase difference. C5, which couples the collector signal to the base of Q4, presents a high impedance to the low frequencies contained in the recorded signal. R13 (or R13 in series with R14, depending upon the state of K2) feeds the emitter signal directly to the base of Q4. As a result of this action, the low frequency phase components present at the emitter of Q3 predominate at the base of Q4 and are 180 degrees out of phase with the same signal at the collector of Q3. Conversely, capacitor C5 presents a very low impedance to the higher signal frequencies allowing them to pass readily to the base of Q4.

At intermediate frequencies, the vector sum of R13 (R13 and R14) causes the signal to be applied to the base of Q4 at some intermediate phase angle between zero and 180 degrees while the amplitude remains constant throughout the entire frequency range.

The result of this frequency/phase shift action cancels the inherent phase distortion on the signal caused by the magnetic transfer characteristics when the signal was recorded on the tape.

In fast tape speed operation, K1 is deenergized as shown. During slow tape speed operation K1 is energized which removes R14 from the circuit.

Emitter follower Q4 provides the required signal isolation and impedance output requirements. C6 couples the signal from the emitter to the gain control R17, and then out to the A-B switching relay through terminal 22. R16 and terminal 21 provide an outlet for signals bypassing the gain control. This output is provided for the extraction of any pilot signal mixed with the audio. Filtering of the pilot from the remaining signals must be accomplished externally of the signal electronics provided with the Series 400 equipment.

Q5 is a series voltage regulator which provides regulated power from the input bus terminal 12 to the four transistor stages in this assembly. R24 and R25 establishes the proper operating point for Q5, thus establishing a fixed voltage drop across Q5. C15 provides filtering of any power supply ripple on the regulated voltage. C9 filters any ripple at the base of Q5.

H and NAB Preamplifier with Overdub (7/9) (See Figure 44)

This unit is exactly the same as the "H" and NAB preamplifier described above and is interchangeable with it. It includes an input transformer which is employed when it is desired to monitor a recording using a record head as a playback head for synchronizing purposes. In this application the record head is connected to terminals 14 and 17.

The output of T1 at terminal 16 is automatically connected to input terminal 4 when this card is inserted in slot 9.

Maximum convenience is afforded if a conventional H and NAB preamplifier or an overdub preamplifier is inserted in slot 7 and an overdub preamplifier is also inserted in slot 9, since it is then only necessary to employ the record select switch to change from normal record to overdub operation. Economy but less convenience is obtained with a single overdub preamplifier, changing its location from slot 7 to slot 9 when changing the switch from normal record to overdub. Great care must be exercised to turn off the machine completely before moving the 7/9 card from slot 9 to slot 7 since the playback head may be magnetized from a charge residual on C1 unless sufficient time is permitted for it to discharge completely.

Line Amplifier (6) (See Figure 41)

This is a full-spectrum flat response amplifier which provides sufficient gain and output power to adequately drive an outgoing line at up to peak level of +28 dbm (600 ohms) or to drive a loudspeaker with up to one watt peak excitation (distortion 1% THD).

Q1 is an emitter follower accepting an input impedance of 10,000 ohms or lower, and providing low impedance excitation for Q2. Q2 drives Q3 and Q4 (complementary symmetry types) to result in push-pull excitation of Q5 and Q6. A required static potential difference between the bases of Q3 and Q4 is established by the contact potential drop across CR1, CR2, and CR3.

CR4, R20, and C12; CR5, R19, and C11 are drift compensation networks to stabilize the operating points of Q5 and Q6. DC operating point for these two transistors is set by R13, R14, and R15; and Q2, Q3, and Q4. A feedback path through C13, R21, and R22 assures minimum distortion for all signal frequencies. C15 and R23 provide a stabilization network to reduce the possibility of high frequency oscillations (parasitics) when certain types of loudspeakers are connected through S1 to terminal 20, and ground. In the alternate switch position the amplifier feeds out on either terminal 21 or 22 to the matching output transformer mounted in the main module, whose purpose is to match the amplifier to a 150 or 600 ohm line. R24 provides a small impedance in series with certain type transformers which would otherwise approach a short circuit at extremely low frequencies and thereby upset the stability of the amplifier at frequencies in the order of one cycle or less.

R1 and R3 are fixed resistors which may be readily changed to alternate values to change the working line level as indicated by the VU meter. The amplifier is normally equipped with the proper values for reading a plus four dbm 600 ohm line. To operate from a +6, +8, or +14 dbm, 600 ohm line, select $\pm 5\%$ calibrating resistors according to the following table 10.

Table 10. Line Operating Level Calibrating Resistors

LINE OPERATING LEVEL - 600 OHMS	VALUE OF CALIBRATING RESISTORS	
	R1	R3
dBm		
+4	3.9K	7.5K
+6	4.7K	6.2K
+8	6.2K	4.3K
+14*	7.5K	3.3K
* Operated in 150 ohm position with R109 on switch S106 removed.		

CR6, CR7, CR8, and S2 are associated with the automatic A-B transfer switching system. CR6 and CR7 are isolating diodes permitting all modules to be operated from pulses originating in the transport, but preventing the transfer buttons on any single module from simultaneously activating the transfer circuits of other modules. CR8 is an inductive suppression diode effectively across the coil of the A-B transfer relay.

L Preamplifier and Switch (8D) (See Figure 43)

The playback head for the L track in the Dynatrack system is connected with the signal lead at terminal 6, the signal return at terminal 7, and the shield of the connecting cable which covers these two conductors is connected to 8. By the shortest possible physical path the signal is coupled through C1 to the base of Q1. The signal and dc output of Q1 are applied to the base of Q2 where they are amplified. The signal is fed back to the emitter of Q1 through the equalizer network C11, R47, R48, and R49. C11 with R49 controls the point where the customary 6 db per octave correction becomes no longer effective at high frequencies. R48 controls the point at very low frequencies where the relation no longer holds true and the amplifier shelves off.

Q1 and Q2 are at all times properly biased due to the feedback path from emitter of Q2 to the base of Q1 through R5.

The signal is passed on to Q3 which is a phase distortion correction stage. Considerable rotation of phase normally occurs in the overall process of recording and playing back tape. The situation is increasingly pronounced at shorter wavelengths. In copying tapes the effect is compounded. Q3 provides a very effective correction for such distortion through C5 and R13. Note that the signal voltage at both the collector and emitter are identical but 180 degrees out of phase.

For low frequencies C5 is a very high impedance, and R13 feeds its signal directly to the base of Q4 which presents a high impedance since it is an emitter follower. At very high frequencies, on the other hand, C5 has a very low impedance and consequently it feeds its signal to Q4 at a phase displacement of 180° from that of R13. At intermediate frequencies the vector sum of the R13 and C5 signals result in a signal at Q4 of some intermediate phase angle between these extremes, but the amplitude remains constant which is most essential.

Emitter follower Q4 feeds the signal to the gain controls R15 and R27. The output of R15 is applied to the deemphasis network R16, R17, C7, R18, R19, and C8. Its output at C9 represents an equalization characteristic which is exactly the inverse of the preemphasis curve generated in the Dynatrack record board. In some cases C7 and C8 are trimmed by small parallel capacitors. The signal from C9 is applied to a double emitter follower circuit, Q5 and Q6. This is to provide a conveniently low impedance at the output signal terminal 16, yet provide a very high impedance to the output of the equalizer at C9. Switch S2 removes the deemphasis equalizer from the circuit so that playback from a standard NAB alignment tape may be used for aligning the adjustable equalizers. It is then only necessary to operate S2 to insert the network in order to convert the board to Dynatrack equalization.

Under normal low signal level conditions the preamplifier feeds directly through Q6 to the output. The output of the second or H track is applied at terminal 17. R50 is a photo resistor unit. The lamp is normally dark so that resistance of the photo element is very high (approximately 100 megohms). When the lamp is lit, however, it drops to a very low value, (less than 500 ohms). When this happens the high or H track provides the signal source and short circuits the high impedance junction of R18, R19.

The lamp in the photo resistor unit, R50, is controlled indirectly by the signal level at the output of Q4, as follows:

R27, TRIG., provides an adjustable amount of this signal to a transistor amplifier Q8. Q9 is normally conductive in the absence of an input signal from R32 because its base is connected to the positive bus through R33. This causes the collector to be at a low voltage due to voltage drop across R34, and since the base of Q10 is direct coupled through R36, Q10 is cut off.

If the peak excursion of the audio input signal exceeds a certain critical value in the negative-going direction, the Q9 collector current is reduced. The collector potential rises, bringing Q10 into conduction. This causes the emitter potentials to rise further cutting off Q9 and driving Q10 into saturation. There are thus two stable states for the collector of Q10. When the peak signal amplitude drops below a certain critical value, Q10 cuts off by the same process in reverse. Q9 and Q10 constitute a Schmitt trigger.

In its normal nonconductive condition Q10 applies zero volts potential through R39 as measured from base to emitter of Q11. Q11 is therefore nonconductive and the junction of C15 and R40 is at zero volts potential above ground. Whenever Q10 is rendered conductive, and this can be just a few degrees of a single cycle of any frequency up to 15 kHz, Q11 is also rendered conductive. It immediately charges C15. This capacitor does not lose its charge for about 5 milliseconds through R41.

The instant a charge is placed on C15 by conduction of Q11 this above ground potential is applied through R42 to the base of Q12 bringing it into full conduction. When C15 is discharged, Q12 is fully cut off. Q12 is a high voltage transistor operating from the 120 V DC supply at terminal 15. When Q12 is conductive the 120V supply furnishes current through R45 and R51 to the neon lamp in the photo resistor unit in parallel with R43. The lamp lights and causes the resistance of the photo resistor element to drop, permitting the signal from the H track, terminal 17, to be applied to Q5 instead of the signal from the L track since it shorts out the latter. When Q12 is cut off the collector potential rises, permitting the pilot indicator lamp DS1 to light. R43 causes the voltage across the lamp in the photo resistor unit to drop well below its extinction voltage so the resistance of the photo resistor rises to its dark value.

When Q11 becomes conductive, C15 charges very rapidly causing the lamp in the photo resistor unit to light within one millisecond after a signal component amplitude exceeds the triggering level. When Q11 cuts off, however, C15 discharges over a considerable period of time assuring that the lamp is not extinguished until the succeeding cycle of signal is observed to see if it is of sufficient amplitude to again trigger the Schmitt and keep the lamp lit. The lowest frequency of interest in this regard is about 400 Hz.

S1 has three positions. In the center AUTO position the photo resistor is controlled automatically by the incoming audio signal. In the HI position the base of Q11 is connected to ground, so as to keep DS1 off at all times and the lamp in R50 on. In the LO position the base of Q11 is connected to the positive supply, cutting it off, turning on DS1 and cutting off the lamp in R50.

Q7 is a regulator transistor intended to drop the input bus voltage by a fixed amount determined by the values of R25 and R26, and to filter out any power supply ripple by means of C18 and C17.

Meter and Power Supply Assembly (5) (See Figure 40)

This unit contains the power transformer, a large filter capacitor, the VU meter, and a regulator circuit to assure that the output of +28 volts is maintained within a few millivolts under varying load conditions.

Line voltage is applied to terminals 5 and 20, through the 1/2 ampere fuse F1 to the power transformer. The transformer secondary feeds a bridge rectifier CR1, CR2, CR3, and CR4 charging C1 through surge limiting resistor R1. Q1 is the power regulator transistor. R2 has a very low resistance and is used to monitor the load current. Its action will be described below. The regulated dc output is taken from terminal 12, positive, and terminal 9, negative and ground. R7 and R8 are in series across the output terminals. Any variation in output voltage is therefore monitored by the base of Q3 which amplifies the base voltage variation because the emitter is kept at constant potential by zener diode CR6. The amplified variation is applied to the base of Q2 where it is further amplified and applied to the base of Q1, thus compensating for the initial variation.

If the power supply is loaded too heavily, so as to possibly damage Q1, the voltage drop across R2 causes a potential difference to occur across the base and emitter of Q4. However, this is only after the drop across R2 is sufficient to exceed the contact potential of CR5, and CR5 becomes conductive. Thus this circuit is inactive until a definite load is exceeded. When Q4 becomes conductive, it takes control of the regulator circuit and causes the output voltage to drop with increasing load, thus protecting the control transistor Q1.

Terminals are provided for R9 which may be jumpered out for maximum brilliance of the meter lamps. R10 is a similar resistor or jumper for the lamps of an external remote meter.

Resistors R11, R12, and R13 are part of the A-B transfer circuit, other components of which are wired into the main assembly.

NAB Erase Coupler (3N) (See Figure 37)

This is a very simple board which connects the erase power amplifier on board 1 to the erase head and permits monitoring erase current. When switching to Dynatrack this board is replaced by the Dynatrack record amplifier which fits into the same slot and rearranges connections so that proper bias is supplied to the L track.

When this board is used, 120 kHz power from the erase amplifier is supplied to terminal 20. C1 forms a resonant circuit with the erase head to provide maximum head current. R1 is the feedback resistor controlling the overall erase amplifier drive. Terminal 17 is connected to the head return which is isolated from ground by 10 ohms in the erase amplifier chassis. This point and the test point connected to it becomes a monitoring point for 120 kHz current. R3 permits erase meter calibration.

SCHEMATICS

This section contains schematics of the tape transport, electronics assembly, and each of the circuit boards used for NAB and Dynatrack operation.

This 3M M23 manual
was
"scanned by the klettster"
as a GIFT*

to those who have these machines
and want to keep them operational


The 3M M23 was the first 3M iso-loop
tape recorder for professional use


3M M23 machines were around 45 years
old at the time this scan was made

enjoy this...
keep the reels turning

*if some opportunist charges you money for this pdf he's making money from no investment other than his time, trolling around on the interweb finding this and other docs, downloading and flipping multiple copies for cash - like a money machine... whereas the klettster has several hours and \$36 in costs (for scanning the larger pages) invested in to this... and is asking nothing... other than that you use and enjoy... maybe I am the idiot and the trolling pdf reseller is the genius...

I'll leave that for others to debate.





LAYOUT OF COMPONENTS ON LOGIC BOARD 23013B060
VIEWED FROM COMPONENT SIDE

Figure 32. Tape Transport Circuit Board Layout




Figure 33. Tape Transport Wiring Diagram






Figure 34. Electronics Block Diagram



SCHEMATIC NO. E23017A000 REV B

Figure 35. Remote Control Assembly Schematic

- NOTES, UNLESS OTHERWISE SPECIFIED
1. ALL CAPACITANCE VALUES ARE IN MICROFARADS
 2. ALL RESISTOR VALUES ARE IN OHMS, 1/2 WATT, $\pm 5\%$
 3. ALL DIODES ARE 1N270
 4. C11 SHOWN BUT NOT USED
 5. P/P VOLTAGES TAKEN WITH HIGH IMPEDANCE (10^9) PROBE




SCHEMATIC NO. E23059A020 REV.F

Figure 36. Bias and Erase Amplifier Schematic

NOTES: UNLESS OTHERWISE SPECIFIED

① R1 SHOWN BUT NOT USED.



3
N

SCHEMATIC NO. E23059A030

REV D

Figure 37. NAB Erase Coupler Schematic




Figure 38. Dynatrack L Record Amplifier Schematic





Figure 39. H and NAB Record Amplifier Schematic

NOTES, UNLESS OTHERWISE SPECIFIED:

1. ALL CAPACITANCE VALUES ARE IN MICROFARADS
2. ALL RESISTANCE VALUES ARE IN OHMS, 1/2 W, $\pm 5\%$
3. ALL DIODES ARE IN4007



SCHEMATIC NO. E23059A050 REV B

Figure 40. Electronics Assembly (Meter and) Power Supply Schematic

RESISTOR VALUES FOR VARIOUS LEVELS

LEVEL	RESISTOR	VALUE
+4	R1*	3.6K
	R2	1K
	R3*	7.5K
	R25	2.2K
+6	R14	2K
	R24	2.7
+8	R15	10K
	R21	1K
+14	R16	3K

* NORM


RESISTORS TO BE SELECTED FOR VARIOUS LINE OPERATING LEVELS AT OUTPUT OF NO. 6 BOARD		
OUTPUT LEVEL: dbm	VALUE OF R1	VALUE OF R3
+4 *	3.9K *	7.5K *
+6	4.7K	6.2K
+8	6.2K	4.3K
+14	7.5K	3.3K

* NORMAL VALUES

6

SCHEMATIC NO. E23059A06Q REV G


NOTE: UNLESS OTHERWISE SPECIFIED
ALL RESISTANCE VALUES
ARE IN OHMS, 1/2W
WATT, 5%
ALL CAPACITANCE VALUES
ARE IN MICROFARADS



7

SCHEMATIC NO. E23059A170 REV B

Figure 42. H and NAB Reproduce Preamplifier Schematic



- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL RESISTANCE VALUES ARE IN OHMS, 1/2 WATT $\pm 5\%$.
 2. ALL CAPACITANCE VALUES ARE IN MICROFARADS.


SCHEMATIC NO. E23C59A14C REV. C

Figure 43. Dynatrack L Preamplifier and Switch Schematic

- NOTES: UNLESS OTHERWISE SPECIFIED
1. ALL RESISTANCE VALUES ARE IN OHMS, 1/2 WATT, 2%
 2. ALL CAPACITANCE VALUES ARE IN MICROFARADS.


COMPONENT VALUE
TABULATION

DASH NO.	CAT. NO.	CONFIG	VALUE	
			R13	R14
-1	83-4930-2180	7.5-151PS	1.8K	1.8K
-2	83-4930-2511	15-30 IPS	910Ω	910Ω



SCHEMATIC NO. E23059B090 REV B

Figure 44. H and NAB Preamplifier with Overdub Schematic



SCHEMATIC NO.E20359A925 REV A

Figure 45. Dynatrack Power Supply Schematic

PARTS LISTS

INTRODUCTION

This section contains parts lists for the 3M Brand Professional Audio Recorder. Drawings for mechanical assemblies are included to aid in parts identification. Electrical parts are identified by reference designators on the assemblies of which they are a part.

The parts list are arranged in alphanumerical order according to their part number which is in the upper right corner. When an assembly drawing is included, it follows immediately after the parts list. The parts list and drawing numbers are the same for all assemblies with one exception: parts list 23013B990 is for drawing 23013B000.

ORDERING REPLACEMENT PARTS

Parts should be ordered through one of the Mincom Division service offices listed below. 3M recommends that whenever possible, and particularly when an instrument is used in a critical application, the user maintains a minimum stock of spare parts. The Mincom Division has specialized personnel ready to assist the user in making a selection of spares. Any additional information required can be obtained by contacting the service offices listed below.

Western U. S.	3M Company Mincom Division 300 South Lewis Road Camarillo, California 93010 (805) 482-1911
---------------	--

Eastern U. S.	3M Company Mincom Division 1750 Pennsylvania Avenue Suite 1100 Washington, D. C. 20006 (202) 298-9200
---------------	--

When ordering parts the following information should always be supplied:

1. A description of the part, obtained from the parts list.
2. The 3M catalog number.
3. The manufacturer's part number.
4. The schematic reference designator, if applicable, given on the applicable schematic and on the parts list.

5. The part or type number of the major assembly as shown on the name plate, and the serial number of that assembly.
6. The 3M sales order number applying to the complete system or order

The following table lists each of the parts lists included in this manual. To locate a parts list, determine the part number or assembly name and locate it in the following table. The referenced page number may then be used to find the parts list.

Table 11. Parts List Index

Part No.	Description	Catalog No.	Page No.
23000B000	Professional Audio Tape Recorder	83-5990-0565	168
23000A010	Interconnecting Cable Assembly	83-4570-0345	170
23000A015	Interconnecting Cable Assembly		171
23000A030-1	4 Track Reproduce Head Cable Assembly	83-4570-0389	172
23000A030-2	8 Track Reproduce Head Cable Assembly	83-4570-0390	173
23000A310	Film Sync Head Cable Assembly	83-4570-0465	174
23000A900-1	Preplay Head Accessory Kit	83-5990-0267	175
23000A900-2	2 Track 1/4" Preplay Head Accessory Kit	83-5990-0568	176
23000A900-3	2 Track 1/2" Preplay Head Accessory Kit	83-5990-0569	177
23000A900-4	3 Track 1/2" Preplay Head Accessory Kit	83-5990-0570	178
23000A900-5	4 Track 1/2" Preplay Head Accessory Kit	83-5990-0571	179
23000A900-6	4 Track 1" Preplay Head Accessory Kit	83-5990-0572	180
23000A900-7	8 Track 1" Preplay Head Accessory Kit	83-5990-0573	181
23000A902	Electronic Mounting Installation Kit	83-5990-0416	182
23000A905	Preplay Reproduce Head Mounting Assy.	83-4320-1751	183
23000A940	Narrow Cover and Trim Kit	83-5990-0440	184
23000A950	Tape Editing Switch Assembly, Foot Operated	83-4550-5298	185/186
23000A951	Foot Switch Chassis Assembly	83-3310-1135	189
23000A952	Relay Bracket	83-3320-1677	190
23000A960-1	Head Mounting Plate Connector Kit, 1/2"	83-5990-0474	191
23000A960-2	Head Mounting Plate Connector Kit, 1"	83-5990-0475	192
23000A970	Transport Tilting Kit	83-5990-0580	193
23004A000	Takeup Reel Motor Assembly	83-4560-0090	194
23004B010	Direction Sensor Printed Circuit Board Assembly	83-4930-1496	195
23004A030	Fail Safe Brake Actuator Assembly	83-4550-5402	196
23004A050	Reel Motor Rewind Assembly	83-4560-0092	197
23004A900	Brake Kit Assembly, Mechanical	83-5990-0556	198
23007C010-1	3 3/4 - 7 1/2 IPS Capstan Motor Assy.	83-4560-0149	199
23007C010-2	7 1/2 - 15 IPS Capstan Motor Assy.	83-4560-0150	200
23007C010-3	15 - 30 IPS Capstan Motor Assembly	83-4560-0151	201
23007C010-4	50 Cycle Capstan Motor Assembly	83-4560-0158	202
23007C010-5	15 - 30 IPS 50 Cycle Capstan Motor Assy.	83-4560-0159	203
23007A030-1	Tape Transport Head Cover Door Assy.	83-4330-0241	204

Table 11. Parts List Index (Cont'd)

Part No.	Description	Catalog No.	Page No.
23007A030-2	Tape Transport Head Cover, Door Assembly	83-4330-0271	205
23007A050-1	Right Hand Actuating Idler Arm Assembly	83-4210-0232	206
23007A050-2	Left Hand Actuating Idler Arm Assembly	83-4210-0256	207
23007A060-1	1/2" Tape Transport Capstan Assembly	83-5920-0819	208
23007A060-2	Tape Transport Capstan Assembly	83-5920-0833	209
23007A070	Capstan Drive Motor Mounting Bracket Assy	83-4320-1476	210
23007C410-1	30 - 60 IPS Capstan Motor Assembly	83-4560-0152	211
23007C410-2	60 - 120 IPS Capstan Motor Assembly	83-4560-0153	212
23009A000	Transport Electronics Power Supply Assy	83-5920-0820	213
23010A910	Edit Switch Assembly Kit	83-5990-0839	214
23012A000	Vernier Speed Adjust Bracket Assembly	83-4930-1002	215
23013B000	All Versions Tape Deck Assembly	83-5920-1344	216
23013A030	Transport Distribution Panel Assembly	83-4930-1003	217
23013B030	Transport Distribution Panel Assembly	83-4930-1685	218
23013A040-1	Transport Tape Lifter Arm Assembly	83-4210-0206	219
23013A040-2	Tape Lifter Arm Assembly, 1" Tape	83-4210-0242	220
23013B050	Harness Assembly, Tape Transport	83-4570-0459	221
23013B060	Bias Osc. and Logic Circuit Board Assy	83-4930-1716	223
23013A070	Incoming Sensor Printed Circuit Board Assy	83-4930-1046	225
23013B075	Printed Circuit Board Assembly, Outgoing Tape Sensor	83-4930-1691	226
23013B080	Chassis Assembly, Transport Wrap Around	83-5920-1332	227
23013A090-1	Left Hand Roller Idler Arm Assembly	83-4210-0230	228
23013A090-2	Right Hand Roller Idler Arm Assembly	83-4210-0231	229
23013A095	Head Cover Door Actuator Arm Assembly	83-4210-0237	230
23013A125-1	Tape Guide Assembly, Preplay	83-3240-0440	231
23013A125-2	Preplay Tape Guide Assembly, 1/2"	83-3240-0442	232
23013A125-3	Preplay Tape Guide Assembly, 1"	83-3240-0443	233
23013A160	Reel Hub Assembly, 1/4" Tape	83-4930-1884	234
23013A900	Capstan Area Parts Kit, 1/2"	83-5990-0426	235
23013A905	Capstan Area Parts Kit, 1"	83-5990-0427	236
23013A910	Capstan Tape Guide Kit, 1/2", 1/4"	83-5990-0428	237
23013A915	Capstan Tape Guide Kit, 1/2", 1/2"	83-5990-0429	238
23013B920	Capstan Tape Guide Kit, 1"	83-5990-0558	239
23013A930	Capstan Tape Guide Kit, 1/4", 1"	83-5990-0431	240
23013A935	Capstan Tape Guide Kit, 1/2", 1"	83-5990-0432	241
23013B940	Speed Kit, 3 3/4 - 7 1/2 IPS	83-5990-0559	242
23013B945-1	Speed Kit, 7 1/2 - 15 IPS	83-5990-0560	243
23013B945-2	Speed Kit, 50 Cycle 7 1/2 - 15 IPS	83-5990-0582	244
23013B950-1	Speed Kit, 15 - 30 IPS	83-5990-0561	245
23013B950-2	Speed Kit, 50 Cycle 15 - 30 IPS	83-5990-0581	246
23013B955	Speed Kit, 30 - 60 IPS	83-5990-0562	247
23013B960	Speed Kit, 60 - 120 IPS	83-5990-0563	248

Table 11. Parts List Index (Cont'd)

Part No.	Description	Catalog No.	Page No.
23013A970	Brake Kit, High Speed Capstan	83-5990-0438	249
23013A986	1/4" Cine Reel Hub Base	83-3240-0455	250
23013B990	Tape Deck Common Parts Kit	83-5990-0564	251
23017A000	Optional Remote Control Assembly	83-5920-0823	256
23017A010	Cable Assembly, Remote Control External	83-4570-0428	259
23017A100	Sync Remote Control Assembly	83-5920-1493	260
23028A020	Basic Cabinet Console Assembly	83-4310-0998	262
23028A050	Cable Assembly, 36" 4 Track Power	83-4570-0346	263
23028A055	Cable Assembly, 66" 4 Track Power	83-4570-0380	264
23028A060	Cable Assembly, 36" 8 Track Power	83-4570-0347	265
23028A065	Cable Assembly, 66" 8 Track Power	83-4570-0381	266
23028A070	Meter Display Assembly, 4 Bay	83-5920-1126	267
23028A075	Harness Assembly, Remote Meter	83-4570-0387	268
23028A080	Housing Assembly, 4 Track Signal Electronics	83-4310-1000	269
23028A085	Cover Assembly, Display Panel	83-3310-1157	270
23028A090	Housing Assembly, 2 Track Signal Electronics	83-4310-0999	271
23028A250	Cable Assembly, Reproducer Power	83-4570-0420	272
23028A350	Cable Assembly, Film Sync Power	83-4570-0466	273
23059A010	Housing Assembly, Signal Electronics Audio	83-5920-0842	274
23059A020	Bias Erase Printed Circuit Board Assy	83-4930-1121	281
23059A030	NAB Erase Coupler Printed Circuit Board Assembly	83-4930-1117	283
23059B040	NAB Record Printed Circuit Board Assy	83-4930-1214	284
23059A050	Signal Electronics Power Supply Assembly W/Meter	83-5920-0822	286
23059A055	Signal Electronics Power Supply Printed Circuit Board Assembly	83-4930-1014	289
23059A060	Signal Electronics Line Amplifier Printed Circuit Board Assembly	83-4930-1091	290
23059B090-1	Overdub Preamplifier Printed Circuit Board Assembly	83-4930-2180	292
23059B090-2	Overdub Preamplifier Printed Circuit Board Assembly	83-4930-2511	293
23059A110	Extender Printed Circuit Board Assembly	83-4930-1746	295
23059A130	Record Dynatrack Printed Circuit Board Assembly	83-4930-1006	296
23059A140	Reproduce Dynatrack Printed Circuit Board Assembly	83-4930-1964	298
23059A170	Reproduce NAB Preamplifier Printed Circuit Board Assembly	83-4930-1940	301

Table 11. Parts List Index (Concluded)

Part No.	Description	Catalog No.	Page No.
23059A210-2	8 Track Reproduce Only Signal Electronics Housing	83-5920-1261	302
23059A330	Record Film Sync Printed Circuit Board Assembly	83-4930-1711	307
23059A390	Reproduce Film Sync Printed Circuit Board Assembly	83-4930-1712	308
23059A920	NAB to Dynatrack Printed Circuit Board Kit	83-5990-0425	310
23059A950	Signal Electronics Film Sync Kit	83-5990-0541	311
23059A960-2	NAB Reproduce Signal Electronics Kit, 8 Track	83-5990-0567	312

TITLE TAPE RECORDER ASSY-PROF AUDIO

CATALOG NO. 83-5990-0565

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		23000A940	A MINCOM	KIT-COVER & TRIM, NARROW	83-5990-0440	AR
2		23000A970	C MINCOM	KIT-TILTING, TRANSPORT	83-5990-0580	AR
5		23028A100-1	MINCOM	CASE ASSY-CARRYING, 3 TK MOD 23	83-4130-0069	AR
6		23028A100-2	B MINCOM	CASE ASSY-CARRYING, 4 TK ELECT	83-4130-0070	AR
10		23028A046	MINCOM	PANEL-BLANK, CABINET, 5.218 WD	83-3360-1101	AR
11		23028A020	E MINCOM	CONSOLE ASSY-CAR, BASIC	83-4310-0998	AR
12		23028A090	C MINCOM	HOUSING ASSY-SIGNAL ELEC, 2TRK	83-4310-0999	AR
13		23028A080	C MINCOM	HOUSING ASSY-SIGNAL ELEC 4TRK	83-4310-1000	AR
14		23028A070	D MINCOM	DISPLAY ASSY-METER, 4 BAY	83-5920-1126	AR
15		23000A902	C MINCOM	KIT-INSTALLATION, MTG, ELECT	83-5990-0416	AR
20		23059A000	C MINCOM	SIG ELEC ASSY-MOD 23, NAB	83-5920-0944	AR
21		23059A920	B MINCOM	KIT-P.C.BD, NAB TO DYNATRACK	83-5990-0425	AR
22		23059A170	B MINCOM	P.C.BD ASSY-PREAMP, NAB, REPRO	83-4930-1940	AR
24		23059A950	B MINCOM	KIT-FILM SYNC, SIG ELEC	83-5990-0541	AR
26		23059A960-1	B MINCOM	KIT-NAB REPRO, SIG ELEC, 4 TRK	83-5990-0566	AR
27		23059A960-2	B MINCOM	KIT-NAB REPRO, SIG ELEC, 8 TRK	83-5990-0567	AR
28		23059A140	C MINCOM	P.C.BD ASSY-DYNATRACK, REPRO	83-4930-1964	AR
29		BX28N2.5-2	ACDC ELECTS	POWER SUPPLY-28VOLTS 2.5 AMPS	83-1930-1672	AR
35		23028A050	B MINCOM	CABLE ASSY-PWR, 4TRK, 36 IN	83-4570-0346	AR
36		23028A060	C MINCOM	CABLE ASSY-PWR, 8 TRK, 36 IN	83-4570-0347	AR
37		23028A055	B MINCOM	CABLE ASSY-PWR, 4 TRK, 66 IN	83-4570-0380	AR
38		23028A065	B MINCOM	CABLE ASSY-PWR, 8 TRK, 66	83-4570-0381	AR
40		23000A015	MINCOM	CABLE ASSY-INTERCONN, HDS	83-4570-0345	AR
41		23000A010-1	MINCOM	CABLE ASSY-INTERCONN, HD, 1 TRK	83-4570-0382	AR
42		23000A010-2	MINCOM	CABLE ASSY-INTERCONN, HDS, 2 TRK	83-4570-0383	AR
43		23000A010-3	MINCOM	CABLE ASSY-INTERCONN, HDS, 3 TRK	83-4570-0384	AR
44		23000A010-4	MINCOM	CABLE ASSY-INTERCONN, HDS, 4 TRK	83-4570-0385	AR
45		23000A010-8	MINCOM	CABLE ASSY-INTERCONN, HDS, 8 TRK	83-4570-0386	AR
50		23000A960-1	B MINCOM	KIT-HD MTG PLATE/CONN, 1/2 IN	83-5990-0474	AR
51		23000A960-2	B MINCOM	KIT-HD MTG PLATE/CONN, 1 IN	83-5990-0475	AR
53		23000B020-1	C MINCOM	HD SET ASSY-REC/REP/ERASE, 1 TK	83-5950-1227	AR
54		23000B020-2	C MINCOM	HD SET ASSY-REC/REP/ERASE, 2 TK	83-5950-1228	AR
55		23000B020-5	C MINCOM	HD SET ASSY-REC/REP/ERASE, 2 TK	83-5950-1231	AR
56		23000B020-3	C MINCOM	HD SET ASSY-REC/REP/ERASE, 3 TK	83-5950-1229	AR
57		23000B020-4	C MINCOM	HD SET ASSY-REC/REP/ERASE, 4 TK	83-5950-1230	AR
59		23000B020-7	C MINCOM	HD SET ASSY-REC/REP/ERASE, 4 TK	83-5950-1233	AR
61		23000B020-9	C MINCOM	HD SET ASSY-REC/REP/ERASE, 8 TK	83-5950-1235	AR
62		23000A040-1	C MINCOM	HD-MTG ASSY 4TK REP ONLY	83-5950-1162	AR
63		23000A040-2	C MINCOM	HD-MTG ASSY 8TK REP ONLY	83-5950-1163	AR
70		23017A000	B MINCOM	CONTROL ASSY-REMOTE, OPTIONAL	83-5920-0823	AR
71		23017A010	A MINCOM	CABLE ASSY-EXT, REMOTE CONTROL	83-4570-0428	AR
72		23000A950	D MINCOM	SW ASSY-TAPE EDITING, FT OPER	83-4550-5298	AR

PAGE NO. 2

P A R T S L I S T

PL 23000B000

REV E

TITLE TAPE RECORDER ASSY-PROF AUDIO

CATALOG NO. 83-5990-0565

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
75	23013A122-1	A MINCOM	COVER-TAPE DECK,10 1/2 REEL	83-3310-1137	AR
76	23013A122-2	A MINCOM	COVER-TAPE DECK,12 REEL	83-3310-1138	AR
77	23013A121	A MINCOM	COVER-TAPE DECK,PORTABLE	83-3310-1139	AR
78	23013A120-1	A MINCOM	COVER-IDLER,PREFPLAY,1/4&1/2 IN	83-3310-1131	AR
79	23013A120-2	A MINCOM	COVER-IDLER,PREFPLAY, 1.00 INCH	83-3310-1156	AR
80	23000A900-1	B MINCOM	KIT ACCESSORY,PREFPLAY HEAD	83-5990-0267	AR
81	23000A900-2	B MINCOM	KIT-ACCESS,PREFPLAY HD,2 TRK1/4	83-5990-0568	AR
82	23059A960-2	B MINCOM	KIT-NAB REPRO,SIG ELEC, 8 TRK	83-5990-0567	AR
83	23000A900-4	B MINCOM	KIT-ACCESS,PREFPLAY HD,3 TRK1/2	83-5990-0570	AR
84	23000A900-5	B MINCOM	KIT-ACCESS,PREFPLAY HD,4 TRK1/2	83-5990-0571	AR
85	23000A900-6	B MINCOM	KIT-ACCESS,PREFPLAY HD,4 TRK 1	83-5990-0572	AR
86	23000A900-7	B MINCOM	KIT-ACCESS,PREFPLAY HD,8 TRK 1	83-5990-0573	AR
100	23013B000	D MINCOM	TAPE DECK ASSY-ALL VERSIONS	83-5920-1344	AR
101	23013A986	A MINCOM	BASE-REEL HUB,1/4 CINE TOP HAT	83-3240-0455	AR
102	23013A901	A MINCOM	KIT-AUTO REWIND OR STOP,SENSOR	83-5990-0669	AR
103	23017A100	B MINCOM	CONTROL ASSY-REMOTE,SYNC	83-5920-1493	AR
104	23017A110	A MINCOM	CABLE ASSY-ADAPTER REMOTE SYNC	83-4570-0585	AR
105	23059A905	A MINCOM	KIT-REMOTE SYNC,SIGNAL ELECT	83-5990-0714	AR
106	23013A700	A MINCOM	TAPE DECK ASSY-MOD 23,150 MIL	83-5920-1587	AR
107	23010A910	A MINCOM	KIT-EDIT, SWITCH ASSY	83-5990-0839	AR
108	2300A990	MINCOM	KIT-ACCESS,BASIC, MODEL 23	83-5990-0868	1.0

M23 RRM 2-69

P A R T S L I S T

PL 23000A010-8

REV

TITLE CABLE ASSY-INTERCONN,HDS,8 TRK

CATALOG NO. 83-4570-0386

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	MRAC-25-G7	WINCHESTER	CONN-RECP,RECTANGLR,42 CON	83-1610-0817	1.0
2	100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	2.0
3	23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
4	00000A499-57	LLOYD WEST C	MARKER-IDENT,CABLE,UNMARKED	83-3550-1271	24.0
5	23000A015	MINCOM	CABLE ASSY-INTERCONN,HDS	83-4570-0345	8.0
6		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
7	TYPE YQE-91	BURNDY	SPLICE-ELECTRICAL CONDUCTOR	83-9630-0470	2.0

P A R T S L I S T

PL 23000A015

REV

TITLE CABLE ASSY-INTERCONN,HDS

CATALOG NO. 83-4570-0345

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	3106A10SL-3S	CANNON	CONN-PLUG,ELEC,STR, 3 SOC	83-1610-0595	3.0
2	100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	5.0
3	AN-3057-4	AMPHENOL	CLAMP-ELEC,STRAIN RELIEF,10,12	83-1650-0127	3.0
4		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
5	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
6	202-3932	MICRODOT	WIRE-SHIELED, TWIST. PAIR	83-7910-0420	AR
7	RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	1.0
8	GSB134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	3.0
9	GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	3.0

P A R T S L I S T

PL 23000A030-1

REV

TITLE CABLE ASSY-HD,REPRODUCE,4 TRK

CATALOG NO. 83-4570-0389

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		3106A10SL-3S	CANNON	CONN-PLUG,ELEC,STR, 3 SOC	83-1610-0595	4.0
2		MRAC-25-G7	WINCHESTER	CONN-RECP,RECTANGLR,42 CON	83-1610-0817	1.0
3		100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	8.0
4		AN-3057-4	AMPHENOL	CLAMP-ELEC,STRAIN RELIEF,10,12	83-1650-0127	4.0
5		23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
6		00000A499-57	LLOYD WEST C	MARKER-IDENT,CABLE,UNMARKED	83-3550-1271	4.0
7			NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
8		202-3932	MICRODOT	WIRE-SHIELDED, TWIST. PAIR	83-7910-0420	AR
9		RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	1.0
10		GSB134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	4.0
11		GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	4.0

P A R T S L I S T

PL 23000A030-2

REV

TITLE CABLE ASSY-HD,REPRODUCE,8 TRK

CATALOG NO. 83-4570-0390

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
	202-3932	MICRODOT	WIRE-SHIELDED, TWIST. PAIR	83-7910-0420	AR
1	3106A10SL-3S	CANNON	CONN-PLUG,ELEC,STR, 3 SOC	83-1610-0595	8.0
2	MRAC-25-G7	WINCHESTER	CONN-RECP,RECTANGLR,42 CON	83-1610-0817	1.0
3	100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	16.0
4	AN-3057-4	AMPHENOL	CLAMP-ELEC,STRAIN RELIEF,10,12	83-1650-0127	8.0
5	23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
6	00000A499-57	LLOYD WEST C	MARKER-IDENT,CABLE,UNMARKED	83-3550-1271	8.0
7		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	2.0
8	202-3932	MICRODOT	WIRE-SHIELDED, TWIST. PAIR	83-7910-0420	48.0
9	RA853	THUMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	2.0
10	G5B134C	THUM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	8.0
11	G5C194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	8.0

P A R T S L I S T

PL 23000A310

REV A

TITLE CABLE ASSY-HEAD, FILM SYNC

CATALOG NO. 83-4570-0465

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
J1	MRAC-25-G7	WINCHESTER	CONN-RECP,RECTANGLR,42 CON	83-1610-0817	1.0
P104,P105,P106,P107,P108	3106A10SL-3S	CANNON	CONN-PLUG,ELEC,STR, . 3 SOC	83-1610-0595	5.0
1	GSB134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	5.0
2	GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	5.0
3	100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	11.0
4	AN-3057-4	AMPHENOL	CLAMP-ELEC,STRAIN RELIEF,10,12	83-1650-0127	5.0
5	23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
6	00000A499-57	LLOYD WEST C	MARKER-IDENT,CABLE,UNMARKED	83-3550-1271	5.0
7		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
8		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
9	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
10	202-3932	MICRODOT	WIRE-SHIELDED, TWIST. PAIR	83-7910-0420	AR
11	RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	3.0
12	TYPE YQE-91	BURNDY	SPLICE-ELECTRICAL CONDUCTOR	83-9630-0470	1.0
13	3025-070-5/16ID	3M	TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR

P A R T S L I S T

PL 23000A900-1

REV B

TITLE KIT ACCESSORY,PREPLAY HEAD

CATALOG NO. 83-5990-0267

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2	23013A113-1	MINCOM	DOOR-PREPLAY HD	83-3330-0339	1.0
3	23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4	23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5	23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6	23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7	23013A112	MINCOM	COVER-DECORATIVE,PREPLAY	83-3310-1129	1.0
8	23013A119-1	A MINCOM	SHIELD-HEAD,PREPLAY,1.25 LG	83-3650-0475	1.0
9	23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10	23002A200-1	C MINCOM	HD-ASSY 1TK REP AUDIO 1/4 IN	83-5950-0994	1.0
11	23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD,PREPLY	83-4320-1751	1.0
12	23013A125-1	A MINCOM	TAPE GUIDE ASSY-PREPLAY	83-3240-0440	1.0
16	MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17	MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18	MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19	MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21	MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22	MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24			WASHER-FLAT,SM PATT,#2	83-9261-4011	4.0
25			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27	MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29			WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31	23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-2

REV B

TITLE KIT-ACCESS,PREPLAY HD,2 TRK1/4

CATALOG NO. 83-5990-0568

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2		23013A113-1	MINCOM	DOOR-PREPLAY HD	83-3330-0339	1.0
3		23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4		23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5		23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6		23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7		23013A112	MINCOM	COVER-DECORATIVE,PREPLAY	83-3310-1129	1.0
8		23013A119-1	A MINCOM	SHIELD-HEAD,PREPLAY,1.25 LG	83-3650-0475	1.0
9		23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10		23002A200-2	C MINCOM	HD-ASSY 2TK REP AUDIO 1/4 IN	83-5950-0999	1.0
11		23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD,PREPLY	83-4320-1751	1.0
12		23013A125-1	A MINCOM	TAPE GUIDE ASSY-PREPLAY	83-3240-0440	1.0
16		MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17		MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19		MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21		MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22		MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23		MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24				WASHER-FLAT,SM PATT,#2	83-9261-4011	2.0
25				WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27		MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29				WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31		23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-3

REV R

TITLE KIT-ACCESS,PREPLAY HD,2 TRK1/2

CATALOG NO. 83-5990-0569

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2		23013A113-1	MINCOM	DOOR--PREPLAY HD	83-3330-0339	1.0
3		23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4		23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5		23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6		23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7		23013A112	MINCOM	COVER-DECORATIVE,PREPLAY	83-3310-1129	1.0
8		23013A119-1	A MINCOM	SHIELD-HEAD,PREPLAY,1.25 LG	83-3650-0475	1.0
9		23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10		23002A200-5	C MINCOM	HD-ASSY 2TK REP AUDIO 1/2 IN	83-5950-1008	1.0
11		23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD,PREPLY	83-4320-1751	1.0
12		23013A125-2	A MINCOM	TAPE GUIDE ASSY-PREPLAY,1/2 IN	83-3240-0442	1.0
16		MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17		MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19		MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21		MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22		MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23		MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24				WASHER-FLAT,SM PATT,#2	83-9261-4011	4.0
25				WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27		MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29				WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31		23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-4

REV R

TITLE KIT-ACCESS,PREPLAY HD,3 TRK1/2

CATALOG NO. 83-5990-0570

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2		23013A113-1	MINCOM	DOOR-PREPLAY HD	83-3330-0339	1.0
3		23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4		23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5		23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6		23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7		23013A112	MINCOM	COVER-DECORATIVE, PREPLAY	83-3310-1129	1.0
8		23013A119-1	A MINCOM	SHIELD-HEAD, PREPLAY, 1.25 LG	83-3650-0475	1.0
9		23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10		23002A200-3	C MINCOM	HD-ASSY 3TK REP AUDIO 1/2 IN	83-5950-1000	1.0
11		23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD, PREPLY	83-4320-1751	1.0
12		23013A125-2	A MINCOM	TAPE GUIDE ASSY-PREPLAY, 1/2 IN	83-3240-0442	1.0
16		MS35190-222	MIL STD	SCREW-MACH, FH, 4-40 X 5/16	83-9260-6503	2.0
17		MS24693-S2	MIL STD	SCREW-MACH, FH, 4-40 X 1/4	83-9260-6554	2.0
18		MS35206-227	MIL STD	SCREW-MACH, PAN HD, 6-32 X 5/16	83-9260-4530	2.0
19		MS35207-263	MIL STD	SCREW-MACH, PAN HD, 10-32 X 1/2	83-9260-4572	1.0
20				WASHER-FLAT, GENERAL PURPSE, #10	83-9261-4006	2.0
21		MS35207-260	MIL STD	SCREW-MACH, PAN HD, 10-32 X 5/16	83-9260-4569	1.0
22		MS35206-204	MIL STD	SCREW-MACH, PAN HD, 2-56 X 5/16	83-9260-4503	2.0
23		MS35206-213	MIL STD	SCREW-MACH, PAN HD, 4-40 X 1/4	83-9260-4513	2.0
24				WASHER-FLAT, SM PATT, #2	83-9261-4011	4.0
25				WASHER-FLAT, GENERAL PURPOSE, #6	83-9261-4004	2.0
26		MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	2.0
27		MS35338-39	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #2	83-9261-4301	2.0
28		MS35338-40	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #4	83-9261-4303	2.0
29				WASHER-FLAT, RD, .125 I.D.	83-9261-4062	2.0
30		MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	1.0
31		23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-5

REV B

TITLE KIT-ACCESS,PREPLAY HD,4 TRK1/2

CATALOG NO. 83-5990-0571

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2	23013A113-1	MINCOM	DOOR-PREPLAY HD	83-3330-0339	1.0
3	23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4	23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5	23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6	23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7	23013A112	MINCOM	COVER-DECORATIVE,PREPLAY	83-3310-1129	1.0
8	23013A119-1	A MINCOM	SHIELD-HEAD,PREPLAY,1.25 LG	83-3650-0475	1.0
9	23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10	23002A200-4	C MINCOM	HD-ASSY 4TK REP AUDIO 1/2 IN	83-5950-1001	1.0
11	23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD,PREPLY	83-4320-1751	1.0
12	23013A125-2	A MINCOM	TAPE GUIDE ASSY-PREPLAY,1/2 IN	83-3240-0442	1.0
16	MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17	MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18	MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19	MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21	MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22	MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24			WASHER-FLAT,SM PATT,#2	83-9261-4011	4.0
25			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27	MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29			WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31	23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-6

REV R

TITLE KIT-ACCESS,PREPLAY HD,4 TRK 1

CATALOG NO. 83-5990-0572

M A T E R I A L R E Q U I R E M E N T S

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2		23013A113-2	D MINCOM	DOOR-PREPLAY HD	83-3330-0340	1.0
3		23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4		23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5		23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6		23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7		23013A112	MINCOM	COVER-DECORAIVE,PREPLAY	83-3310-1129	1.0
8		23013A119-2	A	SHIELD-HEAD,PREPLAY,1.75 LG	83-3650-0476	1.0
9		23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10		23002A200-7	C MINCOM	HD-ASSY 4TK REP AUDIO 1 IN	83-5950-1114	1.0
11		23000A905	A MINCOM	MOUNT ASSY-REPRODUCE HD,PREPLY	83-4320-1751	1.0
12		23013A125-3	A MINCOM	TAPE GUIDE ASSY-PREPLAY,1 INCH	83-3240-0443	1.0
16		MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17		MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19		MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21		MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22		MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23		MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24				WASHER-FLAT,SM PATT,#2	83-9261-4011	4.0
25				WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27		MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29				WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31		23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

P A R T S L I S T

PL 23000A900-7

REV B

TITLE KIT-ACCESS,PREPLAY HD,8 TRK 1

CATALOG NO. 83-5990-0573

M A T E R I A L R E Q U I R E M E N T S

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2		23013A113-2	D MINCOM	DOOR-PREPLAY HD	83-3330-0340	1.0
3		23013A118	MINCOM	SUPPORT-DOOR, PREPLAY	83-3340-0592	1.0
4		23013A115	MINCOM	SHAFT-HINGE, PREPLAY	83-3280-0610	1.0
5		23013A116	MINCOM	SPACER-AZMUTH ADJ, PREPLAY	83-3350-0535	1.0
6		23013A114	MINCOM	SUPPORT-COVER, PRE PLAY	83-3340-0591	2.0
7		23013A112	MINCOM	COVER-DECORAIVE,PREPLAY	83-3310-1129	1.0
8		23013A119-2	A	SHIELD-HEAD,PREPLAY,1.75 LG	83-3650-0476	1.0
9		23002A003-2	B MINCOM	SHOE-HEAD, REPRODUCE	83-3950-1103	1.0
10		23002A200-9	C MINCOM	HD-ASSY 8TK REP AUDIO 1 IN	83-5950-1116	1.0
11		23000A905	A MINCOM	MOUNT ASSY-REPRNDUCE HD,PREPLY	83-4320-1751	1.0
12		23013A125-3	A MINCOM	TAPE GUIDE ASSY-PREPLAY,1 INCH	83-3240-0443	1.0
16		MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0
17		MS24693-S2	MIL STD	SCREW-MACH,FH,4-40 X 1/4	83-9260-6554	2.0
18		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
19		MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	1.0
20				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
21		MS35207-260	MIL STD	SCREW-MACH,PAN HD,10-32 X 5/16	83-9260-4569	1.0
22		MS35206-204	MIL STD	SCREW-MACH,PAN HD,2-56 X 5/16	83-9260-4503	2.0
23		MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
24				WASHER-FLAT,SM PATT,#2	83-9261-4011	4.0
25				WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
26		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
27		MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
28		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
29				WASHER-FLAT,RD,.125 I.D.	83-9261-4062	2.0
30		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	1.0
31		23002A002	MINCOM	SHIELD-BASE, HEAD, REPRODUCE	83-3950-1104	1.0

TITLE KIT-INSTALLATION,MTG,ELECT

CATALOG NO. 83-5990-0416

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23028A033-1	A MINCOM	BRKT-MTG, LH, SIGNAL ELECT	83-3320-1121	1.0
2	23028A033-2	A MINCOM	BRKT-MTG, RH, SIGNAL ELECT	83-3320-1122	1.0
3	23028A023	C MINCOM	STOP-BAR,DOOR,CABINET,CONSOLE	83-3350-0389	1.0
5	A6732-5-02	ESNA	NUT-NON LKG,PL,10-32	83-9260-0059	16.0
6			SCREW-WOOD, RD HD,#6 X 7/8	83-9262-0555	4.0
7			SCREW-WOOD, RD HD,#10 X 1.00LG	83-9262-0559	8.0
8			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	4.0
9			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	8.0

P A R T S L I S T

PL 23000A905

REV A

TITLE MOUNT ASSY-REPRODUCE HD,PREPLY

CATALOG NO. 83-4320-1751

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A111	MINCOM	BASE-MOUNTING-PRE PLAY	83-3240-0439	1.0
2	23001A012	C MINCOM	MTG-PLATE REPRO HD AZIMUTH	83-3950-0962	1.0
3	MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	2.0

P A R T S L I S T

PL 23000A940

REV A

TITLE KIT-COVER & TRIM, NARROW

CATALOG NO. 83-5990-0440

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
251	23013A020	A MINCOM	COVER-SWITCH,TAPE METERING	20 83-3310-0838	1.0
252	23013A023-1	E MINCOM	COVER-TAPE DECK,10 1/2 IN REEL	20 83-3310-0850	1.0
253	23013A021	A MINCOM	PLATE-MASKING,SWTCH,TAPE TRANS	20 83-3320-1117	1.0
254	23013A022-1	D MINCOM	PLATE-MASKING,SWTCH,TAPE TRANS	20 83-3320-1118	1.0
255	23013A018-1	D MINCOM	TRIM-SWITCH PANEL,LH,TRANSPORT	20 83-3330-0243	1.0
256	23013A018-2	D MINCOM	TRIM-SWITCH PANEL,RH,TRANSPORT	20 83-3330-0244	1.0
257	23013A024	A MINCOM	TRIM-CHANNEL,TAPE DECK	20 83-3330-0245	2.0
258	MS24693-S24	MIL STD	SCREW-MACH,FH,6-32 X .250 100	20 83-9260-6571	10.0

P A R T S L I S T

PL 23000A950


REV D

TITLE SW ASSY-TAPE EDITING,FT OPER

CATALOG NO. 83-4550-5298

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	BR500-25	CORNELL DUBL	CAP-FXD,ELECT, 500UF 25V	83-1510-2044	1.0
CR1	1N4004	MOTOROLA	RECT-SI,DIF JCT,400PIV 1 AMP	83-1530-0151	1.0
CR2,CR3	1N4002	MOTOROLA	RECT-SI,SEMICON,100PIV, 1 A	83-1530-0122	2.0
K1,K2	KHP17D11	POTTR & BRUM	RELAY-4PDT,650 OHM 24VDC 3 AMP	83-1550-3550	2.0
P2	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
R1	0A781-7149	MINCOM SPEC	RES-FXD,FILM,3.3K OHM,1/2W,2% S	83-1520-7149	1.0
R2	0A781-7220	MINCOM SPEC	RES-FXD,FILM,220 OHM,1/2W,2% S	83-1520-7220	1.0
R3	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	1.0
S1	1AF4	MICRO SWITCH	SWITCH-FOOT,SPDT, NOR-OPEN	83-1550-5399	1.0
1	23000A951	A MINCOM	CHASSIS-SWITCH ASSY, FOOT	83-3310-1135	1.0
2	23000A952	A MINCOM	BRACKET-RELAY	83-3320-1677	1.0
3	23000A953	MINCOM	COVER-SWITCH ASSY	83-3310-1136	1.0
4	9KH1	POT.BRUM	SOCKET-RELAY,14CONT	83-1620-0108	2.0
5	2924	LERCO	TERM BD-GLASS,1.160WD X1.50 LG	83-1640-0075	1.0
6	51F	CINCH JONES	TERM BD- 2 CONT,.375WD X.750LG	83-1640-0242	1.0
7	#779	H.H. SMITH	CLAMP-STRAIN, .625 ID	83-7650-0064	1.0
8	N4	RICHCO	CLAMP-LOOP,.250 DIA,NYLON	83-7650-0084	1.0
9			SCREW-MACH,PH,3-48UNC-2AX 5/16	83-9260-4510	2.0
10	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	12.0
11	MS35206-214	MIL STD	SCREW-MACH,PAN HD,4-40 X 5/16	83-9260-4514	7.0
12	MS35206-229	MIL STD	SCREW-MACH,PAN HD,6-32 X 7/16	83-9260-4532	1.0
13			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	7.0
14			WASHER-FLAT,SM PATT,#6	83-9261-4013	1.0
15	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	7.0
16	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	1.0
17			NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	1.0
18			NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	1.0
19		NATL WIRE	WIRE-TYPE B,20GA WHT NYLON JKT	83-7910-0035	AR
20			LOCKWASHER-SPLIT, #3	83-9261-4302	2.0
21	AN960-3	A&N STD	WASHER-FLAT,RD, #3	83-9261-4017	2.0



DWG NO.
23000A950

REV
D

Figure 46. Tape Editing Switch Assembly

P A R T S L I S T

PL 23000A951

REV A

TITLE CHASSIS-SWITCH ASSY, FOOT

CATALOG NO. 83-3310-1135

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	FE-832	PENN ENGNRNG	NUT-CLINCH, SELF LOCK, 8-32UNC	83-9264-0431	3.0
2	1591B	USECO	FASTENER-CHAS, TAP, 4-40 X .105	83-9262-0265	4.0

P A R T S L I S T

PL 23000A952

REV A

TITLE BRACKET-RELAY

CATALOG NO. 83-3320-1677

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	CLS-440-2	PENN	ENGRNG NUT-CAPTVE,4-40X.250 OD	83-9264-0004	2.0

P A R T S L I S T

PL 23000A960-1

REV B

TITLE KIT-HD MTG PLATE/CONN,1/2 IN

CATALOG NO. 83-5990-0474

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	MRAC-25-G7	WINCHESTER	CONN-RECP,RECTANGLR,42 CON	83-1610-0817	1.0
2	100-2022S	WINCHESTER	SOCKET-CON,CONN,.766 LG,22 GA	83-1610-0818	21.0
3	100-2022P	WINCHESTER	PIN-CONTACT,CONN,.040DIA X.766	83-1610-0918	21.0
4	23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
5	23001B010-1	MINCOM	MTG PLATE ASSY-REC/REP,1/2 IN	83-5950-1236	1.0

P A R T S L I S T

PL 23000A960-2

REV B

TITLE KIT-HD MTG PLATE/CONN, 1 IN

CATALOG NO. 83-5990-0475

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	MRAC-25-G7	WINCHESTER	CONN-RECP, RECTANGLR, 42 CON	83-1610-0817	1.0
2	100-2022S	WINCHESTER	SOCKET-CON, CONN, .766 LG, 22 GA	83-1610-0818	42.0
3	100-2022P	WINCHESTER	PIN-CONTACT, CONN, .040 DIA X.766	83-1610-0918	42.0
4	23000A011	B MINCOM	BRKT MTG-HEAD CONNECTOR	83-3320-1468	2.0
5	23001B010-2	MINCOM	MTG PLATE ASSY-REC/REP, 1 IN	83-5950-1237	1.0

P A R T S L I S T

PL 23000A970

REV C

TITLE KIT-TILTING, TRANSPORT

CATALOG NO. 83-5990-0580

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23000A901	D MINCOM	KIT-INSTALLATION MTG TRANSPORT	83-5990-0415	1.0
2	23028A010	A MINCOM	HINGE-PIVOT, CABINET, CONSOLE	83-3270-0560	2.0
4	23028A005	C MINCOM	SUPPORT-TRANSPORT, CABINET	83-3340-0500	1.0
5	23028A044	A MINCOM	SPACER-PLATE, TRANSPORT SUP	83-3350-0474	2.0
6	MS35649-82	MIL STD	NUT-HEX,PLAIN,8-32 X .344 WD	83-9260-2006	4.0
7	MS24693-S51	MIL STD	SCREW-MACH,FH,8-32 X .625	83-9260-6563	4.0
8			WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4306	4.0
9	SEE DESC	A&N STD	WASHER-#8,ASA R27.2-1958 .164R	83-9261-4005	4.0
10	#9	DUCOMMUN	PLATE-MOUNTING, FLANG,3/4 THD	83-1320-1705	1.0
12	23028A116	A MINCOM	SHAFT-SPRING, COUNTER BALANCE	83-3280-0614	1.0
13	23028A114	C MINCOM	WASHER-SPRING, COUNTER BALANCE	83-3261-4350	2.0
14	23028A115	A MINCOM	SPACER-SPRING,COUNTER BALANCE	83-3350-0541	12.0
15	H31U58	HUNTER SPR	SPRING-EXTENSION,.031 THKX 2WD	83-1280-0616	1.0
19	MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	2.0
20			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	2.0
22	MS24665-2/6		PIN-COTTER,.078 DIA X 1 1/2 LG	83-7280-0617	2.0
23	23028A112	MINCOM	ARM-SUPPORT,COUNTER BALANCE	83-3210-0287	1.0
24	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	2.0
25	AN960-516L	AN STD	WASHER-FLAT,LIGHT SERIES,#5/16	83-9261-4014	1.0
26	MS35650-102	MIL STD	NUT-HEX,PLAIN,10-32 X .375 WD	83-9260-2107	2.0
27	MS24665-208	MIL STD	PIN-COTTER,.078 DIA X .500 LG	83-7280-0322	1.0

TITLE MOTOR ASSY-TAKE UP REEL

CATALOG NO. 83-4560-0090

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		LFSS-10	MIN PREC BRG	BRG-BALL,ANLR,PLAIN, .625 BORE	83-1230-0331	1.0
2		60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	4.0
3		23004A004	B MINCOM	ADAPTER-REEL HUB,REWIND MOTOR	83-3240-0303	1.0
4		23004A003	A MINCOM	PLATE-MTG,TAKE UP & REWIND MOT	83-3320-1105	1.0
6		23004B001	B MINCOM	INDICATOR-FLAG,DIRECT SENSOR	83-3550-5319	1.0
7		23004A005	A MINCOM	MOTOR-TAKE UP & REWIND,REEL	83-3560-0091	1.0
8		23004B010	A MINCOM	P.C. BD ASSY, DIRECTION SENSOR	83-4930-1496	1.0
9		MS16997-22	MIL STANDARD	SCREW-CAP,SOC HD,6-32 X 3/4	83-9261-2033	1.0
10		MS24693-S272	MIL STD	SCREW-MACH,FH,10-32 X 1/2	83-9260-6294	4.0
11		MS51017-35	MIL STD	SETSCREW-CUP PT,8-32 X 1/4	83-9261-0069	3.0
12				WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	AR
13		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	AR
14		23004A008	A MINCOM	MAGNET ASSY-BAR,IRON	83-3190-0075	1.0
15				NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	2.0
16		#772	HH SMITH	CLAMP-STRAIN, .188 ID	83-7650-0101	1.0
17		MS16997-20	MIL STD	SCREW-CAP,SOC HD,6-32 X 1/2 LG	83-9261-2031	1.0

P A R T S L I S T

PL 230048010

REV A

TITLE P.C. BD ASSY, DIRECTION SENSOR

CATALOG NO. 83-4930-1496

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
S13,S14	MRR-2	HAMLIN	SWITCH-REED,MAGNETIC,28V 470MA	83-1550-5259	2.0
1	230048011	B MINCOM	P.C. BD-DIRECTION SENSOR	83-3640-1035	1.0
2	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	3.0
3	1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
4		AUTOLITE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0180	AR

TITLE ACTUATOR ASSY-BRAKE,FAIL SAFE

CATALOG NO. 83-4550-5402

----- MATERIAL REQUIREMENTS -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
L6	42C24DC-AX	PHILLIPS CON	SOLENOID-ELECTRICAL,PUSH/PULL	83-1550-4516	1.0
R73	LITTLE DEVIL	OHMITE	RES-FXD,COMP,150 OHM 2W 5%	83-9520-5522	1.0
S15	MS24547-1	MIL STD	SWITCH-BASIC,SPDT,28VDC 7 AMP	83-1550-5067	1.0
TB6	52	CINCH-JONES	TERMINAL STRIP, LUG TYPE,2 LUG	83-1640-1112	1.0
1	JX-40	MICRO SWITCH	ACTUATOR-SWITCH,SPG LEAF TYPE	83-1550-5068	1.0
2	34013A926	MINCOM	BRACKET-SUPPORT, FAIL SAFE	83-3320-1640	1.0
3	34013A927	MINCOM	BRACKET-SWITCH MTG,FAIL SAFE	83-3320-1641	1.0
4	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	2.0
5			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	2.0
6	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
7	MS35206-241	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/4	83-9260-4547	2.0
8			WASHER-FLAT,SM PATT,#8	83-9261-4035	2.0
9			WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4306	2.0
10	RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	1.0
11	MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	2.0
12	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
13			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	2.0
14	MS35649-62	MIL STD	NUT-HEX,PLAIN,6-32 X .313 WD	83-9260-2005	2.0

P A R T S L I S T

PL 23004A050

REV R

TITLE MOTOR ASSY-REWIND,REEL

CATALOG NO. 83-4560-0092

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	4.0
2	1-480276-0	AMP INC	SHELL-CONN,RECT, .665 WD X.850	83-1610-0929	1.0
3	23004A004	B MINCOM	ADAPTER-REEL HUB,REWIND MOTOR	83-3240-0303	1.0
4	23004A003	A MINCOM	PLATE-MTG,TAKE UP & REWIND MOT	83-3320-1105	1.0
5	23004A005	A MINCOM	MOTOR-TAKE UP & REWIND,REEL	83-3560-0091	1.0
6	MS24693-S272	MIL STD	SCREW-MACH,FH,10-32 X 1/2	83-9260-6294	4.0
7	MS51017-35	MIL STD	SETSCREW-CUP PT,8-32 X 1/4	83-9261-0069	3.0
8	23013A063-1	A MINCOM	SPG-EXPAN,RET,CAPSTAN,1.810 LG	83-3280-0524	1.0
9	7166	WALSCO	TERM-LUG, UNINS,FLAT,#6	83-9630-0028	4.0

P A R T S L I S T

PL 23004A900

REV B

TITLE KIT-ASSY-MECHANICAL BRAKE

CATALOG NO. 83-5990-0556

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
	- MFGR PART NO.				
2	34013A930-3	D MINCOM	ARM ASSY-CLUTCH ROLLER, LH	83-3210-0273	1.0
3	34013A930-4	D MINCOM	ARM ASSY-CLUTCH ROLLER, RH	83-3210-0274	1.0
5	2-37-E540-8	PARKER SEAL	PKG-PREFORM,O-RING, 2.625 OD	83-1290-0063	2.0
6	23013A063-1	A MINCOM	SPG-EXPAN,RET,CAPSTAN,1.810 LG	83-3280-0524	2.0
7	34013A928	MINCOM	SPACER-ARM, CLUTCH ROLLER	83-3350-0523	2.0
8	23004A030	B MINCOM	ACTUATOR ASSY-BRAKE,FAIL SAFE	83-4550-5402	1.0
9	23004A020	A MINCOM	HUB ASSY-REEL,MOD 01123060	83-4930-1756	2.0
10	21-S-094-0437	STD PRSD STL	PIN-SPRING, .094 DIAX.437LG	83-7280-0223	1.0
11	4318	PIC	SCREW-SHOULDER,8-32 X 5/16 LG	83-9260-0030	2.0
12	MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	2.0
13			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	1.0
14	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
18	197	BIRNBACH	LUG-GROUND #10	83-9630-0061	2.0

P A R T S L I S T

PL 23007C010-1

REV F

TITLE MOTOR ASSY-CAPSTAN,3 3/4-7 1/2

CATALOG NO. 83-4560-0149

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64	200P1450	SPRAGUE	CAP-FXD,PLSTC, 2.UF 440V 10%	83-1510-4433	1.0
P8	1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1	3-36-150E	SPRAGUE	BRACKET-CAPACITOR MTG,.750 WD	83-1320-1116	2.0
2	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7	23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8	MS35206-261	MIL STD	SCR-MACH,PAN HD,10-24 X 3/8 LG	83-9260-4588	3.0
9			WASHER-FLAT,GENFRAL PURPSE,#10	83-9261-4006	3.0
10	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12	6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
14	23007A011	B MINCOM	MOTOR-CAPSTAN DRIVE,TRANSPORT	83-3560-0096	1.0
19	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21			WASHER-FLAT,GENFRAL PURPOSE #4	83-9261-4002	1.0

M23 RRM 2-69

TITLE MOTOR ASSY-CAPSTAN,7 1/2-15

CATALOG NO. 83-4560-0150

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64		200P1450	SPRAGUE	CAP-FXD,PLSTC, 2.UF 440V 10%	83-1510-4433	1.0
P8		1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63		0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1		3-36-150E	SPRAGUE	BRACKET-CAPACITOR MTG,.750 WD	83-1320-1116	2.0
2		MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3		NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4		MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5		2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6				SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7		23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8		MS35206-261	MIL STD	SCR-MACH,PAN HD,10-24 X 3/8 LG	83-9260-4588	3.0
9				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	3.0
10		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11		60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12		6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13		23007A015-1	E MINCOM	PULLEY-CAPSTAN DRIVE,.625 DIA	83-3220-0147	1.0
14		23007A011	B MINCOM	MOTOR-CAPSTAN DRIVE,TRANSPORT	83-3560-0096	1.0
15		N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16		MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	1.0
17		MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18		MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19		MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21				WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0

P A R T S L I S T

PL 23007C010-3

REV F

TITLE MOTOR ASSY-CAPSTAN,15-30

CATALOG NO. 83-4560-0151

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64	200P1450	SPRAGUE	CAP-FXD,PLSTC, 2.UF 440V 10%	83-1510-4433	1.0
P8	1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1	3-36-150E	SPRAGUE	BRACKET-CAPACITOR MTG,.750 WD	83-1320-1116	2.0
2	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7	23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8	MS35206-261	MIL STD	SCR-MACH,PAN HD,10-24 X 3/8 LG	83-9260-4588	3.0
9			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	3.0
10	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12	6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13	23007A015-2	E MINCOM	PULLEY-CAPSTAN DRIVE,1.250 DIA	83-3220-0148	1.0
14	23007A011	B MINCOM	MOTOR-CAPSTAN DRIVE,TRANSPORT	83-3560-0096	1.0
15	N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16	MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	1.0
17	MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0

P A R T S L I S T

PL 23007C010-4

REV F

TITLE MOTOR ASSY-CAPSTAN,50 CYCLE

CATALOG NO. 83-4560-0158

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64		200P1904	SPRAGUE	CAP-FXD,ELEC,5 MF 370VAC 10%	83-1510-2243	1.0
P8		1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63		0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1		36-909H	SPRAGUE	BRACKET-CAPACITOR MTG	83-1320-1587	2.0
2		MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3		NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4		MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5		2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6				SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7		23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8		MS35206-261	MIL STD	SCR-MACH,PAN HD,10-24 X 3/8 LG	83-9260-4588	3.0
9				WASHER-FLAT,GENERAL PURPOSE,#10	83-9261-4006	3.0
10		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11		60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12		6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13		23007A111	B MINCOM	PULLEY-CAPSTAN,50 CYC,7 1/2X15	83-3220-0243	1.0
14		2102-0W4	ELINCO	MOTOR-CAPSTAN DRIVE,	83-1560-0156	1.0
15		N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16				SCREW-MACH,PAN HD,8-32 X 1.375	83-9260-4559	1.0
17		MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18		MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19		MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21				WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0
22		23007A112	B MINCOM	FLYWHEEL-CAPSTAN,50 CYC,7 1/2	83-3220-0244	1.0
23		DAN280-202	WOODRUFF	KEY-STD DESIGN,1/4DIA X 1/16 W	83-1280-0094	1.0
24				NUT-PLAIN,HEX,1/2-32 X 5/8	83-9260-2417	1.0
25		AN960-816L	MIL STD	WASHER-FLAT,RD,.515ID X .875OD	83-9261-4023	1.0

P A R T S L I S T

PL 23007C010-5

REV F

TITLE MOTOR ASSY-CAPSTAN,15-30,50 CY

CATALOG NO. 83-4560-0159

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64	200P1904	SPRAGUE	CAP-FXD,ELEC,5 MF 370VAC 10%	83-1510-2243	1.0
P8	1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1	36-909H	SPRAGUE	BRACKET-CAPACITOR MTG	83-1320-1587	2.0
2	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7	23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8	MS35206-261	MIL STD	SCR-MACH,PAN HD,10-24 X 3/8 LG	83-9260-4588	3.0
9			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	3.0
10	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12	6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13	23007A015-6	E MINCOM	PULLEY-CAPSTAN DRIVE,1.503 DIA	83-3220-0191	1.0
14	2102-0W4	ELINCO	MOTOR-CAPSTAN DRIVE,	83-1560-0156	1.0
15	N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16	MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	1.0
17	MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21			WASHER-FLAT,GENFRAL PURPOSE #4	83-9261-4002	1.0

P A R T S L I S T

PL 23007A030-1

REV C

TITLE DOOR ASSY-HEAD COVER,TPE TRANS

CATALOG NO. 83-4330-0241

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2	23007A032	B MINCOM	SHAFT-ACTUATING,DOOR,HEAD COVR	83-3280-0406	1.0
3	23007B034-1	D MINCOM	DOOR-HEAD COVER, TAPE TRANS	83-3330-0263	1.0
4	23007A033	A MINCOM	SUPPORT-DOOR,HD CVR,TAPE TRANS	83-3340-0381	1.0
5	23007A036-1	B MINCOM	SHIELD-DOOR, HEAD COVER	83-3650-0367	1.0
6	GP24-125X312	GROOV-PIN	PIN-GRVD,HDLS,.125DIA X.312 LG	83-7280-0466	1.0
7	#0	GROOV-PIN	PIN-GRVD,HDED,.067 DIA X.125LG	83-7280-0477	2.0

P A R T S L I S T

PL 23007A030-2

REV C

TITLE DOOR ASSY-HD COVER,TAPE TRANS

CATALOG NO. 83-4330-0271

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
2	23007A032	B MINCOM	SHAFT-ACTUATING,DOOR,HEAD COVR	83-3280-0406	1.0
3	23007B034-2	D 3M	DOOR-HD COVER,TAPE TRANSPORT	83-3330-0269	1.0
4	23007A033	A MINCOM	SUPPORT-DOOR,HD CVR,TAPE TRANS	83-3340-0381	1.0
5	23007A036-2	B MINCOM	SHIELD-DOOR,HEAD COVER	83-3650-0384	1.0
6	GP24-125X312	GRUOV-PIN	PIN-GRVD,HOLS,.125DIA X.312 LG	83-7280-0466	1.0
7	#0	GRUOV-PIN	PIN-GRVD,HDED,.067 DIA X.125LG	83-7280-0477	2.0

P A R T S L I S T

PL 23007A050-1

REV K

TITLE ARM ASSY-IDLER, ACTUATING,RH

CATALOG NO. 83-4210-0232

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23007A051	C MINCOM	ARM-ADJUSTING,IDLER,UPPER	83-3210-0204	1.0
2	23007A052	B MINCOM	ARM-ADJUSTING,IDLER,LOWER	83-3210-0205	1.0
3	23007A053	A MINCOM	SPRING-ADJUSTABLE ARM,IDLER	83-3280-0411	1.0
5	#511	MILFORD	RIVET-SIMI-TUBULAR,.123 X.254	83-9260-0046	2.0
6	LP22D82P9	LONG LOK	SCR-SELF LKG,PAN HD,8-32X9/16	83-9262-0529	1.0
7	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
8	S-832-2	PENN ENGR	NUT-PLAIN,CLIN,8-32	83-9264-2116	1.0
9	6593	BIRNBACH	INSULATOR-WASH, NYLON,.016 TK	83-9630-0272	2.0

P A R T S L I S T

PL 23007A050-2

REV K

TITLE ARM ASSY-IDLER,ACTUATING,LH

CATALOG NO. 83-4210-0256

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23007A055	C MINCOM	ARM-ADJUSTING,IDLER,UPPER,INC	83-3210-0257	1.0
2	23007A052	B MINCOM	ARM-ADJUSTING,IDLER,LOWER	83-3210-0205	1.0
3	23007A053	A MINCOM	SPRING-ADJUSTABLE ARM,IDLER	83-3280-0411	1.0
4	52-022-093-0312	ESNA	PIN-SPRING, .093 DIAX.312LG	83-7280-0221	1.0
5	#511	MILFORD	RIVET-SIMI-TUBULAR,.123 X.254	83-9260-0046	2.0
6	LP22D82P9	LONG LOK	SCR-SELF LKG,PAN HD,8-32X9/16	83-9262-0529	1.0
7	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
8	S-832-2	PENN ENGR	NUT-PLAIN,CLIN,8-32	83-9264-2116	1.0
9	6593	BIRNBACH	INSULATOR-WASH, NYLON,.016 TK	83-9630-0272	2.0

TITLE CAPSTAN ASSY-TAPE TRANS,1/2 IN

CATALOG NO. 83-5920-0819

M A T E R I A L R E Q U I R E M E N T S

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		103S3CG-2	BARDEN	BRG-BALL,PLAIN,ANLR,.6693 BORE	83-1230-0313	1.0
2		103HDB5CG-2	BARDEN	BRG-BALL,PLAIN,.6693 BORE	83-1230-0335	1.0
4		23007A063-1	E MINCOM	TAPE DR-CAPSTAN,1/2 IN TAPE	83-3240-0292	1.0
5		19007A022	D MINCOM	CAP-FLYWHEEL,PRECISION PLATE	83-3250-0082	1.0
7		23007A064-1	E MINCOM	SHAFT-CAPSTAN,TAPE DRIVE,1/2 IN	83-3280-0409	1.0
8		23007A062	D MINCOM	HOUSING-CAPSTAN,TAPE DRIVE	83-3310-0836	1.0
9		MS16625-137	MIL STD	RING-RETNG, INT, 1.486 OD	83-7270-0382	1.0
11		00000A816	MINCOM	RING-RETNG,INT,1.526 FREE OP	83-3270-0768	1.0
12				SCR-CAP,FH,1/4X20X5/8,NYLOC	83-9262-0569	1.0
13		23007A009-1	B MINCOM	SHIM-CAPSTAN,.002 THK	83-3230-0340	AR
14		23007A009-2	B MINCOM	SHIM-CAPSTAN,.005 THK	83-3230-0368	AR
15		23007A009-3	B MINCOM	SHIM-CAPSTAN,.010 THK	83-3230-0369	AR

P A R T S L I S T

PL 23007A060-2 REV F

TITLE CAPSTAN ASSY-TAPE TRANSPORT

CATALOG NO. 83-5920-0833

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	103S3CG-2	BARDEN	BRG-BALL,PLAIN,ANLR,.6693 BORE	83-1230-0313	1.0
2	103HDB5CG-2	BARDEN	BRG-BALL,PLAIN, .6693 BORE	83-1230-0335	1.0
4	23007A063-2	E MINCOM	CAPSTAN-TAPE GUIDE, 1 IN TAPE	83-3240-0297	1.0
5	19007A022	D MINCOM	CAP-FLYWHEEL,PRECISION PLATE	83-3250-0082	1.0
7	23007A064-2	E MINCOM	SHAFT-CAPSTAN,1 IN TAPE	83-3280-0410	1.0
8	23007A062	D MINCOM	HOUSING-CAPSTAN,TAPE DRIVE	83-3310-0836	1.0
9	MS16625-137	MIL STD	RING-RETNG, INT, 1.486 OD	83-7270-0382	1.0
11	00000A816	MINCOM	RING-RETNG,INT,1.526 FREE OP	83-3270-0768	1.0
12			SCR-CAP,FH,1/4X20X5/8,NYLOC	83-9262-0569	1.0
13	23007A009-1	B MINCOM	SHIM-CAPSTAN,.002 THK	83-3230-0340	AR
14	23007A009-2	B MINCOM	SHIM-CAPSTAN, .005 THK	83-3230-0368	AR
15	23007A009-3	B MINCOM	SHIM-CAPSTAN, .010 THK	83-3230-0369	AR

P A R T S L I S T

PL 23007A070

REV C

TITLE BRKT ASSY-MOTOR MTG,CAPS DRIVE

CATALOG NO. 83-4320-1476

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23007A071	A MINCOM	SLEEVE-RUBBER,.625 ID X 1.00LG	83-3230-0393	2.0
2	23007A013	A MINCOM	BUSHING-SPLIT,MOTOR SUPPORT	83-3230-0303	2.0
3	23013A043	C MINCOM	SHAFT-SUPPORT,CAPSTAN MOTOR	83-3280-0421	1.0
4	23007A012	D MINCOM	BRACKET-MTG,CAPSTAN MOTOR	83-3320-1102	1.0
5	MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	4.0
6			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	4.0
7	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	4.0

P A R T S L I S T

PL 23007C410-1

REV B

TITLE MOTOR ASSY-CAPSTAN, 30-60

CATALOG NO. 83-4560-0152

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64	200P1450	SPRAGUE	CAP-FXD,PLSTC, 2.UF 440V 10%	83-1510-4433	1.0
P8	1-480277-0	AMP INC	SHELL-CONN,RECT, .850 WD X.905	83-1610-0930	1.0
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1	3-36-150E	SPRAGUE	BRACKET-CAPACITOR MTG,.750 WD	83-1320-1116	2.0
2	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7	23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8	MS35207-261	MIL STD	SCREW-MACH,PAN HD,10-32 X 3/8	83-9260-4570	3.0
9			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	3.0
10	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12	6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13	23007A415	B MINCOM	PULLEY-CAPSTAN DRIVE, 120 IPS	83-3220-0170	1.0
14	23007A011	B MINCOM	MOTOR-CAPSTAN DRIVE,TRANSPORT	83-3560-0096	1.0
15	N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16	MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	1.0
17	MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0

TITLE MOTOR ASSY-CAPSTAN, 60-120

CATALOG NO. 83-4560-0153

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C64	200P1904	SPRAGUE	CAP-FXD,ELEC,5 MF 370VAC 10%	83-1510-2243	1.0
P8	1-480277-0	AMP INC	SHELL-CONN,RECT,.850 WD X.905	83-1610-0930	1.0
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0
1	36-909H	SPRAGUE	BRACKET-CAPACITOR MTG	83-1320-1587	2.0
2	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0
3	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0
4	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0
5	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0
6			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
7	23007A017	D MINCOM	BRACKET-CAPACITOR MTG	83-3320-1582	1.0
8	MS35207-261	MIL STD	SCREW-MACH,PAN HD,10-32 X 3/8	83-9260-4570	3.0
9			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	3.0
10	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	3.0
11	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	8.0
12	6128	LERCO	TERMINAL-INSUL,.250 OD,4-40	83-9630-0137	1.0
13	23007A415	B MINCOM	PULLEY-CAPSTAN DRIVE, 120 IPS	83-3220-0170	1.0
14	23007A411	MINCOM	MOTOR-CAPSTAN DRIVE,TRANSPORT	83-3560-0109	1.0
15	N5001-31	TRUARC	RING-RETNG,INT,.831 I D	83-7270-0598	1.0
16	MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	1.0
17	MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	1.0
18	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	1.0
19	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
20	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
21			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0

P A R T S L I S T

PL 23009A000

REV G

TITLE PWR SUP ASSY-TRANSPORT ELECT

CATALOG NO. 83-5920-0820

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C65	CG451T200C1	MALLORY	CAP-FXD,ELECT, 450UF 200V	83-1510-2205	1.0
C66	CG23U50C1	MALLORY	CAP-FXD,ELECT, 2000UF 50V	83-1510-2206	1.0
F1	313005.	LITTELFUSE	FUSE-SLO-BLO,125V 5 AMP	83-7550-8006	1.0
J1	160-3	AMPHENOL	CONN-PLUG,ELEC,POWER, 2 PIN	83-1610-1107	1.0
J3	200512-3	AMP INC	SHELL-CONN,RECT,26 POSITIONS	83-1610-0663	1.0
Q60	2N174	MOTOROLA	TSTR-GE,PNP, PWR, 80 VCB	83-1530-2001	1.0
T60	23009A004	A MINCOM	XMFR-PWR,48-62 CPS.115V 10%	83-3540-1141	1.0
3	342004	LITTELFUSE	FUSEHOLDER-POST, AG 3 FUSE	83-1620-0083	1.0
4	201924-1	AMP INC	CLIP-SPG TENS,POSITION LOCKING	83-1620-0127	1.0
6	VR3	MALLORY	CLAMP-COMP MTG,1.375 DIA	83-1650-0371	2.0
7	23009A007	A MINCOM	SPRING-LOCKOUT,POWER SUPPLY	83-3280-0464	1.0
8	23009A001	B MINCOM	CHASSIS-TRANSPORT ELECT,MDL 23	83-3310-0830	1.0
9	23009A006	A MINCOM	BRACKET-LOCKOUT,CAPSTAN MOTOR	83-3320-1168	1.0
10	200390-4	AMP INC	RECP-GUIDE PIN,CENTER,SERIES M	83-7270-0302	1.0
11	200389-4	AMP INC	PIN-GUIDE,CENTER,AMP SERIES M	83-7280-0196	1.0
12			NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	11.0
13	MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	12.0
14	MS35206-230	MIL STD	SCREW-MACH,PAN HD,6-32 X 1/2	83-9260-4533	3.0
17			WASHER-FLAT,GENERAL PURPOSE,#6	83-9261-4004	1.0
18			WASHER-FLAT,SM PATT,#6	83-9261-4013	13.0
20	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	14.0
22	#NCGB 122-37	PIPCO INT	STRIP-GROMMET,.145 HT X.171 WD	83-9630-0008	1.0
23	RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	2.0
24	4451-C-9	USECO	TERMINAL-FEEDTHRU, .094 LG	83-9630-0559	1.0
25	23009A008	A MINCOM	STOP-CAPSTAN MOTOR,TRANSPORT	83-3350-0554	1.0
26	212-42-0183B	PLASTIGLIDE	BUSHING-ELEC COND,INSUL,NYLON	83-9630-0300	1.0
27	7274633	DELCO	KIT-TSTR MTG	83-1530-2016	1.0

P A R T S L I S T

PL 23010A910

REV A

TITLE KIT-EDIT, SWITCH ASSY

CATALOG NO. 83-5990-0839

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
DS14	327	GENERAL ELEC	LAMP-INCANDESCENT, .04 AMP	83-1550-2506	1.0
S14	1018	PENDAR	SWITCH-PUSHBUTTON, SPDT, LIGHTED	83-1550-5148	1.0
1	SP191A080	C MINCOM OOT	RELAY ASSY-EDIT SWITCH	83-4930-1908	1.0
2	SP191A082-2	A MINCOM	PLATE-MASK, SW, EDIT, LONG	83-3320-2143	1.0
3	SP191A083	A MINCOM	PLATE-SWITCH, MTG, EDIT	83-3320-2144	1.0
4	60510-4	AMP INC	CONTACT-ELEC, SOC, 18-22GA SIZE	83-1610-0927	3.0
5	23013A038-2	E MINCOM	LENS-IND LIGHT, PUSHBUTTON, EDIT	83-3550-1758	1.0
6	RAA-217	THOM & BETTS	SPLICE-CONDUCTOR, BUTT TYPE	83-9630-0382	1.0
7		NATL WIRE	WIRE-TYPE B, 22GA WHT NYLON JKT	83-7910-0043	AR

P A R T S L I S T

PL 23012A000

REV A

TITLE BRACKET ASSY-VERNIER SPEED ADJ

CATALOG NO. 83-4930-1002

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MEGR PART NO.	MEGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		ALLMETAL	PIN-STR,HDL5, .188 DIA X 1.125 LG	83-1280-0077	2.0
2	23012A001	MINCOM	ARM-SPEED ADJ,CAPSTAN DRIVE	83-3210-0199	1.0
3	23012A004	C MINCOM	LEVER-SOLENOID SHAFT,CAPSTAN	83-3210-0200	1.0
4	23012A002	MINCOM	PIVOT-SPEED ADJ,CAPSTAN DRIVE	83-3280-0386	1.0
5	23012A003	MINCOM	SPRING-SPEED ADJ,CAPSTAN DRIVE	83-3280-0387	1.0
6	5555-18	TRIARC	RING-RETNG, FXT, .181 ID	83-7270-0488	4.0

TITLE TAPE DECK ASSY-ALL VERSIONS

CATALOG NO. 83-5920-1344

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R60	TYPE RH-50	DALE PRODUCT	RES-FXD,WW, 15 OHM, 50W, 5%	83-1520-7593	AR
R71	00000A737	A MINCOM	RES-FXD,0-300K OHM 1/4W 5%	83-3520-3276	1.0
R75	1723	OHMITE	RES-FXD, WW, 200 OHM 10W 5%	83-1520-8006	AR
300	230138990	G MINCOM	KIT-COMMON PARTS,TAPE DECK	83-5990-0564	1.0
304	230138940	B MINCOM	KIT-SPEED, 3 3/4-7 1/2 IPS	83-5990-0559	AR
306	230138945-1	C MINCOM	KIT-SPEED, 7 1/2-15 IPS	83-5990-0560	AR
307	230138945-2	C MINCOM	KIT-SPEED,7 1/2-15 IPS,50 CYC	83-5990-0582	AR
308	230138950-1	C MINCOM	KIT-SPEED, 15-30 IPS	83-5990-0561	AR
309	230138950-2	C MINCOM	KIT-SPEED,15-30 IPS,50 CYCLE	83-5990-0581	AR
310	230138955	C MINCOM	KIT-SPEED, 30-60 IPS	83-5990-0562	AR
312	230138960	C MINCOM	KIT-SPEED, 60-120 IPS	83-5990-0563	AR
315	23013A970	D MINCOM	KIT-BRAKE, CAPSTAN,HIGH SPEED	83-5990-0438	AR
321	23013A900	C MINCOM	KIT-CAPSTAN AREA PARTS,1/2 IN	83-5990-0426	AR
322	23013A905	C MINCOM	KIT-CAPSTAN AREA PARTS,1 INCH	83-5990-0427	AR
327	23013A910	C MINCOM	KIT-TAPE GUIDE,1/4 IN,1/2 CAP	83-5990-0428	AR
328	23013A915	C MINCOM	KIT-TAPE GUIDE,1/2 IN,1/2 CAP	83-5990-0429	AR
329	23013A930	C MINCOM	KIT-TAPE GUIDE,1/4 IN,1 IN CAP	83-5990-0431	AR
330	23013A935	C MINCOM	KIT-TAPE GUIDE,1/2 IN,1 IN CAP	83-5990-0432	AR
331	230138920	D MINCOM	KIT-TAPE GUIDE, 1 INCH	83-5990-0558	AR
332	23004A900	B MINCOM	KIT-ASSY-MECHANICAL BRAKE	83-5990-0556	AR
333	23013A980-1	A MINCOM	KIT-HUB WOTH,W/O BK,1/4NAB&CIN	83-5990-0642	AR
334	23013A980-2	A MINCOM	KIT-HUB WOTH,W/O BK,1/2 NAB	83-5990-0643	AR
335	23013A980-3	A MINCOM	KIT-HUB WOTH,W/O BK,1 NAB	83-5990-0644	AR
336	23013A985-1	A MINCOM	KIT-HUB WOTH,WITH BK,1/4 CIN	83-5990-0645	AR
337	23013A985-2	A MINCOM	KIT-HUB WOTH,WITH BK,1/4 NAB	83-5990-0646	AR
338	23013A985-3	B MINCOM	KIT-HUB WOTH,WITH BK,1/2 NAB	83-5990-0647	AR
339	23013A985-4	B MINCOM	KIT-HUB WOTH,WITH BK,1 NAB	83-5990-0648	AR

P A R T S L I S T

PL 23013A030

REV B

TITLE PANEL ASSY-DISTRIBUTION,TRANS

CATALOG NO. 83-4930-1003

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -						
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.	
C64	200P1450	SPRAGUE	CAP-FXD,PLSTC, 2.UF 440V 10%	83-1510-4433	1.0	
C68	BR-100-150	CORNELL DUBL	CAP-FXD,ELECT, 100UF 150V	83-1510-2207	1.0	
R63	0367	OHMITE	RES-ADJ, WW, 75 OHM 25W 10%	83-1520-8306	1.0	
R68	4592	OHMITE	RES-FXD, WW,100 OHM 5W 5%	83-1520-8185	1.0	
1	3-36-150E	SPRAGUE	BRACKET-CAPACITOR MTG,.750 WD	83-1320-1116	2.0	
2	3006	H.H. SMITH	TERM BD-2.250 BETWEEN MTG HOLE	83-1640-0588	1.0	
3	23013A031	C MINCOM	PLATE-CONN MTG,DIST PANEL	83-3320-1104	1.0	
4			NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	2.0	
5			NUT-HEX,SM PATT,1/4-20 X.438WD	83-9260-2205	1.0	
6	21FK-832	STD PRSD STL	NUT-HEX,SELF LOCK,8-32 X.345WD	83-9260-2405	2.0	
7			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0	
8	MS35206-289	MIL STANDARD	SCREW-MACH,PAN HD,1/4-20 X 2.5	83-9260-4583	1.0	
9	MS35190-235	MIL STD	SCREW-MACH,FH,6-32 X 5/16	83-9260-6516	2.0	
10			WASHER-FLAT,SM PATT,#6	83-9261-4013	2.0	
11	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	2.0	
12	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	1.0	
13	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0	
14	MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	83-9261-4309	1.0	
15	2154	H.H. SMITH	INSULATOR-WASH, FIBER,.250 ID	83-9630-0046	2.0	

TITLE PANEL ASSY-DISTRIBUTION,TRANS

CATALOG NO. 83-4930-1685

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DFS. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C68	BR-100-150	CORNELL DUBL	CAP-FXD,ELECT, 100UF 150V	83-1510-2207	1.0
R68	4592	OHMITE	RES-FXD, WW,100 OHM 5W 5%	83-1520-8185	1.0
TB2	3006	H.H. SMITH	TERM BD-2.250 BETWEEN MTG HOLE	83-1640-0588	1.0
1	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	2.0
2	23013A031	C MINCOM	PLATE-CONN MTG,DIST PANEL	83-3320-1104	1.0
3			NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	2.0
4	MS35190-235	MIL STD	SCREW-MACH,FH,6-32 X 5/16	83-9260-6516	2.0
5			WASHER-FLAT,SM PATT,#6	83-9261-4013	2.0

P A R T S L I S T

PL 23013A040-1

REV C

TITLE ARM ASSY-TAPE LIFTER,TRANSPORT

CATALOG NO. 83-4210-0206

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A042	MINCOM	ARM-LIFTER,TAPE TRANSPORT	83-3210-0201	1.0
2	23013A041-1	D MINCOM	SHAFT-ARM,TAPE LIFTER,2.125 LG	83-3280-0399	1.0
3	23013A041-2	D MINCOM	SHAFT-ARM,TAPE LIFTER,1.750 LG	83-3280-0400	1.0
4	MS35206-218	MIL STD	SCREW-MACH,PAN HD,4-40 X 5/8	83-9260-4519	2.0
5			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	2.0
6	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
7	M70AS1032-8C	NYLOCK	SETSCREW-HEX,CUP PT,10-32X.50L	83-9261-4392	1.0

P A R T S L I S T

PL 23013A040-2

REV C

TITLE ARM ASSY-TAPE LIFTER,1 IN TAPE

CATALOG NO. 83-4210-0242

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A042	MINCOM	ARM-LIFTER,TAPE TRANSPORT	83-3210-0201	1.0
2	23013A041-3	D MINCOM	SHAFT-ARM,TAPE LIFTER,2.937 LG	83-3280-0401	1.0
3	23013A041-4	D 3M	SHAFT-ARM,TAPE LIFTER,2.562 LG	83-3280-0404	1.0
4	MS35206-218	MIL STD	SCREW-MACH,PAN HD,4-40 X 5/8	83-9260-4519	2.0
5			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	2.0
6	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
7	M70AS1032-8C	NYLOCK	SETSCREW-HEX,CUP PT,10-32X.50L	83-9261-4392	1.0

P A R T S L I S T

PL 23013B050

REV E

TITLE HARNESS ASSY-TAPE TRANSPORT

CATALOG NO. 83-4570-0459

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C68	BR-100-150	CORNELL DUBL	CAP-FXD,ELECT, 100UF 150V	83-1510-2207	1.0
CR77	1N4002	MOTOROLA	RECT-SI,SEMICON,100PIV, 1 A	83-1530-0122	AR
J11	1-480304-0	AMP INC	SHELL-CONN,RECT, 3 POSITION	83-1610-1137	1.0
P11	1-480305-0	AMP INC	SHELL-CONN,RECT,3 POS	83-1610-1142	1.0
R68	4592	OHMITE	RES-FXD, WW,100 OHM 5W 5%	83-1520-8185	1.0
R76	LITTLE DEVIL	OHMITE	RES-FXD,COMP,470 OHM 2W 5%	83-9520-5528	AR
S1,S2,S3,S4,S5	1018	PENDAR	SWITCH-PUSHBUTTON,SPDT,LIGHTED	83-1550-5148	5.0
S6		LIKON	SWITCH-ALTERNATE ACT,ILLUM	83-1550-5231	1.0
S7,S9	TYPE SS16	STACKPOLE	SWITCH-SLIDE,DPTT	83-1550-5232	2.0
S8	TYPE SS12	STACKPOLE	SWITCH-SLIDE,4PDT	83-1550-5230	1.0
S10,S11	513-0101-604	DIALCO	SWITCH-MOMENTARY,MAKE	83-1550-5233	2.0
1	42981-1-LP	4 AMP INC	SOCKET-CONTACT,CONN, SIZE 16	83-1610-0689	8.0
2	2VK180/1-2	VIKING	CONN-P.C.,ELEC,PIERCD, 36 CON	83-1610-0782	2.0
3	1-480273-0	AMP INC	SHELL-CONN,RECT,.565 WDX.65	83-1610-0923	1.0
4	1-480274-0	AMP INC	SHELL-CONN,RECT,.65 WD X.805	83-1610-0924	2.0
5	60510-4	AMP INC	CONTACT-ELEC,SOC,18-22GA SIZE	83-1610-0927	44.0
6	1-480275-0	AMP INC	SHELL-CONN,RECT,.650 WDX1.045	83-1610-0932	2.0
7	3006	H.H. SMITH	TERM BD-2.250 BETWEEN MTG HOLE	83-1640-0588	2.0
8	23013A017	B MINCOM	CHASSIS-SWITCH MTG,TRANSPORT	83-3310-0708	1.0
9	23013A016	C MINCOM	PLATE-SWITCH MTG,TRANSPORT	83-3320-1115	1.0
10	SE-44 BRASS	UNITED SHOE	EYELET-BRASS,FLANGED,.112X.121	83-7290-0091	6.0
11		NATL WIRE	WIRE-TYPE B,20GA WHT NYLON JKT	83-7910-0035	AR
12		NATL WIRE	WIRE-TYPE B,20GA BLK NYLON JKT	83-7910-0039	AR
13		NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0043	AR
14		NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0052	AR
15	#EXE-22-122	THERMAX	WIRE-TYPE C,22GA WHT TEFLN JKT	83-7910-0476	AR
16	#EXE-20-120	THERMAX	WIRE-TYPE C,20GA WHT TEFLN JKT	83-7910-0496	AR
17	YEC110	BURNDY	FERRULE-RF CABLE GND,.083 ID	83-9690-0181	2.0
18	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	2.0
19	42983-1-LP	AMP INC	CONTACT-ELEC,SOC, 16 SIZE	83-1610-0678	13.0
20	RAA-217	THOM & BETTS	SPLICE-CONDUCTOR,BUTT TYPE	83-9630-0382	4.0
21	RA853	THOM & BETTS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	2.0
22	RA873	THOM & BETTS	LUG-TERMINAL SOLDERLS,RING,#10	83-9630-0205	4.0
23	RB853	THOM & BETTS	TERM-LUG, INSUL,R TG, .31WD	83-9630-0206	2.0
26	23013A031	C MINCOM	PLATE-CONN MTG,DIST PANEL	83-3320-1104	1.0
28	MS35190-235	MIL STD	SCREW-MACH,FH,6-32 X 5/16	83-9260-6516	4.0
30	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	4.0

P A R T S L I S T

PL 23013R05L

REV E

TITLE HARNESS ASSY-TAPE TRANSPORT

CATALOG NO. 83-4570-0459

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
-----------------------	-----------------------------------	-----------	-----------------------	----------------	------

31			WASHER-FLAT, SM PATT, #6	83-9261-4013	2.0
32			NUT-HEX, SM PATT, 6-32 X .250 WD	83-9260-2202	4.0
33			NUT-PLAIN, HEX, 5/8-24, 3/32 THK	83-9260-0064	1.0

P A R T S L I S T

PL 23013B060

REV G

TITLE P.C. BD ASSY-LOGIC TRANSPORT

CATALOG NO. 83-4930-1716

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	TC3501	MALLORY	CAP-FXD,ELECT, 100UF 50V	83-1510-2045	1.0
C3	BR250-50	CORNELL DUBL	CAP-FXD,ELECT, 250UF 50V	83-1510-2031	1.0
C4,C5,C6	TYPE P123ZNP	AEROVOX	CAP-FXD,PAPER .47UF 400V 20%	83-1510-4072	3.0
C7	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C8,C9	TYPE P123ZNP	AEROVOX	CAP-FXD,PAPER, .01UF 200V 25%	83-1510-4046	2.0
C10	00000A748	B MINCOM	CAP-SEL VAL,.008-.015MFD,500V	83-3510-5368	1.0
C11	313-M	ARCO	CAP-VAR,MICA,1000-2155PF 500V	83-1510-5001	1.0
C12	OD475X9035B2	SPRAGUE	CAP-FXD,TA, 4.7UF 35V 10%	83-1510-6095	1.0
CR1,CR3,CR6,CR7,CR8,CR9, CR10,CR13,CR14,CR15,CR17, CR19,CR20,CR21,CR24,CR25, CR26,CR27,CR28,CR29,CR41 CR4,CR16,CR18,CR30,CR31, CR32,CR37,CR38,CR39,CR40, CR42,CR43,CR44,CR45 CR46,CR47,CR48,CR49 CR50,CR51 CR52,CR53	1N4002	MOTOROLA	RECT-SI,SEMICON,100PIV, 1 A	83-1530-0122	21.0
	IN4004	MOTOROLA	RECT -SI,DIF JCT,400PIV 1 AMP	83-1530-0151	14.0
	MR1033A	MOTOROLA	RECT-SI, 300 PRV, 3.0 AMP	83-1530-0364	4.0
	1N4750	MOTOROLA	DIODE-SI,ZENER, 27 V, 30 MA	83-1530-0365	2.0
	1N3002	MOTOROLA	DIODE-SI,ZENER, 75V 33 MA	83-1530-0301	2.0
F1	312004.	LITTELFUSE	FUSE-QUICK ACT,250V 4 AMP	83-7550-8016	1.0
K1,K2,K3,K4,K5,K6,K7,K8	KHP17D12	POT & BRUMFD	RELAY-4PDT, 24 VDC 650 OHM	83-1550-3678	8.0
Q1,Q2,Q3	2N3053	R.C.A.	TSTR-SI,NPN, PWR, 60 VCB	83-1530-2180	3.0
R1	0A781-7331	MINCOM SPEC	RES-FXD,FILM,27 OHM,1/2W,2% S	83-1520-7331	1.0
R5	0A781-7221	MINCOM SPEC	RES-FXD,FILM,100 OHM,1/2W,2% S	83-1520-7221	1.0
R6	1720	OHMITE	RES-FXD, WW,100 OHM 10W 5%	83-1520-8253	1.0
R7	0A781-7335	MINCOM SPEC	RES-FXD,FILM,39 OHM,1/2W,2% S	83-1520-7335	1.0
R8	1730	OHMITE	RES-FXD, WW,500 OHM 10W 5%	83-1520-8007	1.0
R9	LITTLE DEVIL	OHMITE	RES-FXD,COMP,100 OHM 2W 5%	83-9520-5520	1.0
R10,R11	LITTLE DEVIL	OHMITE	RES-FXD,COMP,270 OHM 1W 5%	83-9520-4091	2.0
R12,R13	LITTLE DEVIL	OHMITE	RES-FXD,COMP,2.7 OHM 1W 5%	83-9520-4000	2.0
R14	LITTLE DEVIL	OHMITE	RES-FXD,COMP,1.2K OHM 1W 5%	83-9520-4153	1.0
R15	0A781-7355	MINCOM SPEC	RES-FXD,FILM,560 OHM,1/2W,2% S	83-1520-7355	1.0
R16	LITTLE DEVIL	OHMITE	RES-FXD,COMP,150 OHM 1W 5%	83-9520-4134	1.0
R17,R18	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	2.0
R19,R20	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	2.0
R21,R22	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	2.0
R23	0A781-7325	MINCOM SPEC	RES-FXD,FILM,10 OHM,1/2W,2% S	83-1520-7325	1.0
T1	00000A721	B MINCOM	XMFR-TORROIDAL,BIFILAR	83-3540-1153	1.0

M23 RRM 2-69

223

P A R T S L I S T

PL 23013B060

REV G

TITLE P.C. BD ASSY-LOGIC TRANSPORT

CATALOG NO. 83-4930-1716

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		9KH-2	POTTR & BRUM	SOCKET-RELAY, 14 PIN	83-1620-0184	8.0
2		23013A061	G MINCOM	P.C. BD-BIAS OSCILLATR & LOGIC	83-3640-0595	1.0
3				NUT-HEX, SM PATT, 6-32 X .250 WD	83-9260-2202	2.0
5				SCREW-MACH, PAN HD, 6-32 X 2 1/4	83-9260-4594	2.0
6				WASHER-FLAT, SM PATT, #6	83-9261-4013	2.0
7		MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	5.0
10		2515	H.H. SMITH	INSULATOR-WASH, NYLON, #6	83-9630-0268	6.0
11		#EXE-22-122	THERMAX	WIRE-TYPE C, 22GA WHT TEFLN JKT	83-7910-0476	AR
12		KHP	POTTER/BRUMF	SPG-HOLD DOWN, RELAY	83-1280-0571	8.0
13		MS35206-227	MIL STD	SCREW-MACH, PAN HD, 6-32 X 5/16	83-9260-4530	3.0
14				WASHER-FLAT, GENERAL PURPOSE, #6	83-9261-4004	3.0
15		8070-E	LERCO	SPACER-SLV, HEX, TAP, .500 LG	83-9350-0063	15.0
16		4405	BUSSMANN MFG	FUSEHOLDER-BLOCK, AG 3 FUSE	83-1620-0001	1.0
17		MS35206-215	MIL STD	SCREW-MACH, PAN HD, 4-40 X 3/8	83-9260-4515	1.0
18				WASHER-FLAT, .219 OD X .125 ID	83-9261-4012	1.0
19		MS35335-29	MIL STD	WASHER-LOCK, FLAT, EXT T, #4	83-9261-4101	1.0
20				WASHER-PLAIN, .125 ID X .187 OD	83-9630-0115	1.0
21				NUT-HEX, SM PATT, 4-40 X .188 WD	83-9260-2201	4.0
21				CANCEL- 1-26-68, PER EO 12228	83-9261-2201	1.0
22		3025-005	3M	TUBING-CLEAR VINYL, .047 ID	83-7910-0272	AR
23		10160-DAP	MILTON ROSS	PAD-TRANSISTOR, FOR TO-5 CASES	83-9690-0145	1.0

P A R T S L I S T

PL 23013A070

REV C

TITLE P.C. BD ASSY-SENSOR,INCOMING

CATALOG NO. 83-4930-1046

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C67	TSD1-35-105	COMP INC	CAP-FXD,TA, 1UF 35V 20%	83-1510-6208	1.0
CR63	3P60	SOLID STATE	SEMICONDEV-PHOTO,LT ACT SHTC	83-1530-6013	1.0
CR65	1N4002	MOTOROLA	RECT-SI,SEMICONDEV,100PIV, 1 A	83-1530-0122	1.0
R67	LITTLE DEVIL	OHNITE	RES-FXD,COMP,100K OHM 1/4W 5%	83-9520-2119	1.0
1	23013A071	NIFCOM	P.C. BD-SENSOR,INCOMING,TAPE	83-3640-0608	1.0

TITLE P.C. BD ASSY-TAPE SENSOR,OUTGO

CATALOG NO. 83-4930-1691

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
061,062	2N3391	GENERAL ELEC	TSTR-SI,MPN, PWR, 25 VCB	83-1530-2226	2.0
R72	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 12K OHM 1/4W 5%	83-9520-2159	1.0
1	23013B076	C MINCOPI	P.C. BD-TAPE SENSOR, OUTGOING	83-3640-1093	1.0

P A R T S L I S T

PL 23013R080

REV C

TITLE CHASSIS ASSY-WRAP AROUND,TRANS

CATALOG NO. 83-5920-1332

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R60	P25CH	SAGE	RES-FXD, WW, 15 OHM 25W 3%	83-1520-7753	1.0
R61	0568B	OHMITE	RES-ADJ, WW, 300 OHM 50W 10%	83-1520-8311	1.0
R62	0568C	OHMITE	RES-ADJ, WW, 400 OHM 50W 10%	83-1520-8312	1.0
S12	MS24547-1	MIL STD	SWITCH-BASIC, SPDT, 28VDC 7 AMP	83-1550-5067	1.0
1	JX-40		MICRO SWITCH ACTUATOR-SWITCH, SPG LEAF TYPE	83-1550-5068	1.0
2	RE148		ROTRON FAN-TUBE AXIAL, 115 V, 100 CFM	83-1560-0104	1.0
3	3-11		LEECRAFT LAMP HOLDER-NE-51, NEON, .593 DIA	83-1620-0180	1.0
4	23007A007	B MINCOM	BRACKET-SWITCH MTG, DNR	83-3320-1158	1.0
5	23013A034-2	A MINCOM	SUPPORT-TAPE DECK, TRANSPORT	83-3340-0692	1.0
6	23013B050	E MINCOM	HARNESS ASSY-TAPE TRANSPORT	83-4570-0459	1.0
9	23013B075	C MINCOM	P.C. BD ASSY-TAPE SENSOR, OUTGO	83-4930-1691	1.0
10	23009A000	G MINCOM	PWR SUP ASSY-TRANSPORT ELECT	83-5920-0820	1.0
11	MS35649-42	MIL STD	NUT-HEX, PLAIN, 4-40 X .250 WD	83-9260-2003	2.0
12			NUT-HEX, SM PATT, 6-32 X .250 WD	83-9260-2202	10.0
13	MS35206-215	MIL STD	SCREW-MACH, PAN HD, 4-40 X 3/8	83-9260-4515	2.0
14	MS35206-228	MIL STD	SCREW-MACH, PAN HD, 6-32 X 3/8	83-9260-4531	5.0
15			SCREW-MACH, PAN HD, 6-32 X 9/16	83-9260-4534	4.0
17			WASHER-FLAT, GENERAL PURPOSE #4	83-9261-4002	2.0
18			WASHER-FLAT, GENERAL PURPOSE #6	83-9261-4004	4.0
19			WASHER-FLAT, SM PATT, #6	83-9261-4013	6.0
20	MS35338-40	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #4	83-9261-4303	2.0
21	MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	10.0
22	MS35206-229	MIL STD	SCREW-MACH, PAN HD, 6-32 X 7/16	83-9260-4532	1.0
23	23013A081	A MINCOM	SHIELD-MOTOR, FAN	83-3650-0562	1.0

P A R T S L I S T

PL 23013A090-1

REV A

TITLE ARM ASSY-IDLER,ROLLER,LH

CATALOG NO. 83-4210-0230

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A006	B MINCOM	ARM-ROLLER,IDLER	83-3210-0203	1.0
2	23013A012	MINCOM	PIN-ACTUATOR,IDLER ARM	83-3280-0408	1.0
3	GP67-125X500-12	GRUOV-PIN	PIN-GRVD,HDLS, .125 DIA X .500LG	83-7280-0202	1.0
4	CLS-440-3	PENN ENGRNG	NUT-CLINCH,PLAIN,4-40 X .250WD	83-9264-0005	1.0

P A R T S L I S T

PL 23013A090-2

REV A

TITLE ARM ASSY-IDLER,ROLLER,RH

CATALOG NO. 83-4210-0231

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A006	B MINCOM	ARM-ROLLER,IDLER	83-3210-0203	1.0
2	23013A012	MINCOM	PIN-ACTUATOR,IDLER ARM	83-3280-0408	1.0
3	GP67-125X500-12	GROOV-PIN	PIN-GRVD,HDLS, .125 DIAX.500LG	83-7280-0202	1.0
4	CLS-440-3	PENN ENGRNG	NUT-CLINCH,PLAIN,4-40 X .250WD	83-9264-0005	1.0

P A R T S L I S T

PL 23013A095

REV B

TITLE ARM ASSY-ACTUATOR, DOOR HD CVR

CATALOG NO. 83-4210-0237

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23007A031	C MINCOM	LEVER-DOOR, HEAD COVER	83-3210-0202	1.0
2	23007A035	C MINCOM	BRACKET-LEVER MTG, DASH POT	83-3320-1049	1.0

P A R T S L I S T

PL 23013A125-1

REV A

TITLE TAPE GUIDE ASSY-PREPLAY

CATALOG NO. 83-3240-0440

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A129-1	MINCOM	SHAFT-TAPE GUIDE, PREPLAY	83-3280-0612	1.0
2	23013A128-2	MINCOM	CAP-TAPE GUIDE, PREPLAY, .500 HT	83-3250-0153	1.0
3	23013A127-1	MINCOM	HOUSING-TAPE GUIDE, PREPLAY	83-3310-1132	1.0
4	23013A126	MINCOM	SPRING-WASHER, BGR PRELOAD	83-3280-0611	1.0
5	S814FCZZ7LG31		BRG-BALL, ANLR, FLNGD, .2500 BORE	83-1230-0325	2.0
6	MS35190-223	MIL STD	SCREW-MACH, FH, 4-40 X 3/8	83-9260-6504	1.0

P A R T S L I S T

PL 23013A125-2

REV A

TITLE TAPE GUIDE ASSY-PREPLAY, 1/2 IN

CATALOG NO. 83-3240-0442

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A129-1	MINCOM	SHAFT-TAPE GUIDE, PREPLAY	83-3280-0612	1.0
2	23013A128-1	MINCOM	CAP-TAPE GUIDE, PREPLAY	83-3250-0151	1.0
3	23013A127-1	MINCOM	HOUSING-TAPE GUIDE, PREPLAY	83-3310-1132	1.0
4	23013A126	MINCOM	SPRING-WASHER, BGR PRELOAD	83-3280-0611	1.0
5	S814FCZZ7LG31		BRG-BALL, ANLR, FLNGD, .2500 BORE	83-1230-0325	2.0
6	MS35190-223	MIL STD	SCREW-MACH, FH, 4-40 X 3/8	83-9260-6504	1.0

P A R T S L I S T

PL 23013A125-3

REV A

TITLE TAPE GUIDE ASSY-PREPLAY,1 INCH

CATALOG NO. 83-3240-0443

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGK PART NO.	MFGK NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A129-2	MINCOM	SHAFT-TAPE GUIDE, 1 INCH	83-3280-0619	1.0
2	23013A128-1	MINCOM	CAP-TAPE GUIDE, PREPLAY	83-3250-0151	1.0
3	23013A127-2	MINCOM	HOUSING-TAPE GUIDE,PREPLAY,1IN	83-3310-1152	1.0
4	23013A126	MINCOM	SPRING-WASHER,BGR PRELOAD	83-3280-0611	1.0
5	SR14FCZZ7LG31		BRG-BALL,ANLR,FLNGD,.2500 BORE	83-1230-0325	2.0
6	MS35190-223	MIL STD	SCREW-MACH,FH,4-40 X 3/8	83-9260-6504	1.0

P A R T S L I S T

PL 23013A160

REV A

TITLE HUB ASSY-REEL, 1/4 IN TAPE

CATALOG NO. 83-4930-1884

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A062	C MINCOM	BASE-REEL HUB, 1/4 IN TAPE	83-3240-0364	1.0
2	23013A162	A MINCOM	TIRE-BRAKE, RUBBER	83-3390-0037	1.0
3	23013A161	MINCOM	RING-BRAKE, REEL HUB, 1/4 IN	83-3220-0217	1.0
4	MS35190-223	MIL STD	SCREW-MACH, FH, 4-40 X 3/8	83-9260-6504	3.0

P A R T S L I S T

PL 23013A900

REV C

TITLE KIT-CAPSTAN AREA PARTS,1/2 IN

CATALOG NO. 83-5990-0426

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
56		23013A064-1	C MINCOM	SCREW-MTG, TAPE GUIDE	83-3262-0537	4.0
31		23007A030-1	C MINCOM	DOOR ASSY-HEAD COVER,TPE TRANS	10 83-4330-0241	1.0
32		MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	10 83-9260-4531	2.0
33		23013A056-1	A MINCOM	BLADE-TAPE EDITING,TAPE GUIDE	11 83-3330-0259	1.0
34		MS35206-212	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/16	11 83-9260-4512	1.0
35		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	11 83-9261-4303	3.0
36		23007A060-1	F MINCOM	CAPSTAN ASSY-TAPE TRANS,1/2 IN	13 83-5920-0819	1.0
37		MS16998-31	MIL STD	SCREW-SHC, 10-32X1	13 83-9261-2105	3.0
38		MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	13 83-9261-4307	3.0
39				WASHER-FLAT,SM PATT,#10	13 83-9261-4046	3.0
40		23013A040-1	C MINCOM	ARM ASSY-TAPE LIFTER,TRANSPORT	16 83-4210-0206	1.0
41			NYLOCK	SCREW-MACH,FH,100% 10-32 X 5/8	16 83-9260-0029	1.0
42		23007A040-1	B MINCOM	ROLLER ASSY-IDLER,1/2 IN INCOM	16 83-4240-0310	1.0
43		23007A040-2	B MINCOM	ROLLER ASSY-IDLER,1/2 IN OTGNG	16 83-4240-0311	1.0
44		MS35206-223	MIL STD	SCREW-MACH,PAN HD,4-40 X 1 1/2	16 83-9260-4525	2.0
46		23007A020-1	D MINCOM	IDLER ASSY-REVERSING,1/2 INCH	16 83-4240-0318	1.0
47		MS16997-66	MIL STD	SCREW-CAP,SOC HD,1/4-20 X 2.00	16 83-9261-2123	1.0
48		MS35338-44	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#1/4	16 83-9261-4309	1.0
49		AN960-416L	A & N STD	WASHER-FLAT,LIGHT SERIES,#1/4	16 83-9262-0046	1.0
50		23007A044-1	A MINCOM	SHIM-IDLER,TAPE DRIVE,.002 THK	16 83-3230-0362	AR
51		23007A044-2	A MINCOM	SHIM-IDLER,TAPE DRIVE,.005 THK	16 83-3230-0363	AR
52		23007A044-3	A MINCOM	SHIM-IDLER,TAPE DRIVE,.010 THK	16 83-3230-0364	AR
53		23007A044-4	A MINCOM	SHIM-IDLER,TAPE DRIVE,.020 THK	16 83-3230-0365	AR
54		23007A003-1	D MINCOM	COVER-IDLER,SNAP-ON,LH,1/2 IN	20 83-3310-0846	1.0
55		23007A003-2	D MINCOM	COVER-IDLER,SNAP-ON,RH,1/2 IN	20 83-3310-0847	1.0

TITLE KIT-CAPSTAN AREA PARTS, 1 INCH

CATALOG NO. 83-5990-0427

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
56	23013A064-2	C MINCOM	SCREW-MTG, TAPE GUIDE	83-3262-0538	4.0
31	23007A030-2	C MINCOM	DOOR ASSY-HD COVER, TAPE TRANS	10 83-4330-0271	1.0
32	MS35206-278	MIL STD	SCREW-MACH, PAN HD, 6-32 X 3/8	10 83-9260-4531	2.0
33	23013A056-2	A MINCOM	BLADE-TAPE EDITING, 1.12 LG	11 83-3330-0268	1.0
34	MS35206-212	MIL STD	SCREW-MACH, PAN HD, 4-40 X 3/16	11 83-9260-4512	1.0
35	MS35338-40	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #4	11 83-9261-4303	3.0
36	23007A060-2	F MINCOM	CAPSTAN ASSY-TAPE TRANSPORT	13 83-5920-0833	1.0
37	MS16998-31	MIL STD	SCREW-SHC, 10-32X1	13 83-9261-2105	3.0
38	MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	13 83-9261-4307	3.0
39			WASHER-FLAT, SM PATT, #10	13 83-9261-4046	3.0
40	23013A040-2	C MINCOM	ARM ASSY-TAPE LIFTER, 1 IN TAPE	16 83-4210-0242	1.0
41		NYLOCK	SCREW-MACH, FH, 100% 10-32 X 5/8	16 83-9260-0029	1.0
42	23007A040-3	B MINCOM	ROLLER ASSY-IDLER, 1 IN INCOM	16 83-4240-0314	1.0
43	23007A040-4	B MINCOM	ROLLER ASSY-IDLER, 1 IN OUTGO	16 83-4240-0315	1.0
44			SCREW-MACH, PAN HD, 4-40 X 2.00	16 83-9260-4604	2.0
46	23007A020-2	D MINCOM	IDLER ASSY-REV, TAPE TRANSPORT	16 83-4240-0319	1.0
47	MS16997-66	MIL STD	SCREW-CAP, SOC HD, 1/4-20 X 2.00	16 83-9261-2123	1.0
48	MS35338-44	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #1/4	16 83-9261-4309	1.0
49	AN960-416L	A & N STD	WASHER-FLAT, LIGHT SERIES, #1/4	16 83-9262-0046	1.0
50	23007A044-1	A MINCOM	SHIM-IDLER, TAPE DRIVE, .002 THK	16 83-3230-0362	AR
51	23007A044-2	A MINCOM	SHIM-IDLER, TAPE DRIVE, .005 THK	16 83-3230-0363	AR
52	23007A044-3	A MINCOM	SHIM-IDLER, TAPE DRIVE, .010 THK	16 83-3230-0364	AR
53	23007A044-4	A MINCOM	SHIM-IDLER, TAPE DRIVE, .020 THK	16 83-3230-0365	AR
54	23007A003-3	D MINCOM	COVER-IDLER, SNAP-ON, 1 IN LH	20 83-3310-0848	1.0
55	23007A003-4	C MINCOM	COVER-IDLER, SNAP-ON, 1 IN RH	20 83-3310-0849	1.0

P A R T S L I S T

PL 23013A910

REV C

TITLE KIT-TAPE GUIDE,1/4 IN,1/2 CAP

CATALOG NO. 83-5990-0428

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DFS. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
67	23013A077-1	MINCOM	SHIM-TAPE GUIDE,.002 THK	83-3230-0401	AR
68	23013A077-2	MINCOM	SHIM-TAPE GUIDE,.005 THK	83-3230-0402	AR
69	23013A077-3	MINCOM	SHIM-TAPE GUIDE,.010 THK	83-3230-0403	AR
70	23013A077-4	MINCOM	SHIM-TAPE GUIDE,.020 THK	83-3230-0404	AR
65	23013A013-1	D MINCOM	TAPE GUIDE-INCOMING,1/4 IN	11 83-3240-0326	2.0
66	23013A014-1	C MINCOM	TAPE GUIDE-OUTGOING,1/4 IN	11 83-3240-0332	2.0

TITLE KIT-TAPE GUIDE, 1/2 IN, 1/2 CAP

CATALOG NO. 83-5990-0429

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
67	23013A077-1	MINCOM	SHIM-TAPE GUIDE, .002 THK	83-3230-0401	AR
68	23013A077-2	MINCOM	SHIM-TAPE GUIDE, .005 THK	83-3230-0402	AR
69	23013A077-3	MINCOM	SHIM-TAPE GUIDE, .010 THK	83-3230-0403	AR
70	23013A077-4	MINCOM	SHIM-TAPE GUIDE, .020 THK	83-3230-0404	AR
65	23013A013-2	D MINCOM	TAPE GUIDE-INCOMNG, 1/2 IN TAPE 11	83-3240-0327	2.0
66	23013A014-2	C MINCOM	TAPE GUIDE-OUTGNG, 1/2 IN TAPE 11	83-3240-0333	2.0

P A R T S L I S T

PL 23013B920

REV D

TITLE KIT-TAPE GUIDE, 1 INCH

CATALOG NO. 83-5990-0558

----- M A T E R I A L R E Q U I R E M E N T S -----						
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.	
C3	BR500-25	CORNELL DUBL	CAP-FXD,ELECT, 500UF 25V	83-1510-2044	1.0	
K13	KHP17D11	POTTR & BRUM	RELAY-4PDT,650 OHM 24VDC 3 AMP	83-1550-3550	1.0	
65	23013A013-4	D MINCOM	TAPE GUIDE-INCOMING, 1 IN	83-3240-0331	2.0	
66	23013A014-4	C MINCOM	TAPE GUIDE-OUTGOING, 1 IN	83-3240-0335	2.0	
67	23013A077-1	MINCOM	SHIM-TAPE GUIDE,.002 THK	83-3230-0401	AR	
68	23013A077-2	MINCOM	SHIM-TAPE GUIDE,.005 THK	83-3230-0402	AR	
69	23013A077-3	MINCOM	SHIM-TAPE GUIDE,.010 THK	83-3230-0403	AR	
70	23013A077-4	MINCOM	SHIM-TAPE GUIDE,.020 THK	83-3230-0404	AR	

P A R T S L I S T

PL 23013A930

REV C

TITLE KIT-TAPE GUIDE,1/4 IN,1 IN CAP

CATALOG NO. 83-5990-0431

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
67	23013A077-1	MINCOM	SHIM-TAPE GUIDE,.002 THK	83-3230-0401	AR
68	23013A077-2	MINCOM	SHIM-TAPE GUIDE,.005 THK	83-3230-0402	AR
69	23013A077-3	MINCOM	SHIM-TAPE GUIDE, .010 THK	83-3230-0403	AR
70	23013A077-4	MINCOM	SHIM-TAPE GUIDE, .020 THK	83-3230-0404	AR
65	23013A013-5	D MINCOM	TAPE GUIDE-INC,1/4 IN TAPE	11 83-3240-0396	2.0
66	23013A014-5	C MINCOM	TAPE GUIDE-OUTGOING,1/4 IN	11 83-3240-0398	2.0

P A R T S L I S T

PL 23013A935

REV C

TITLE KIT-TAPE GUIDE,1/2 IN,1 IN CAP

CATALOG NO. 83-5990-0432

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
67	23013A077-1	MINCOM	SHIM-TAPE GUIDE,.002 THK	83-3230-0401	AR
68	23013A077-2	MINCOM	SHIM-TAPE GUIDE,.005 THK	83-3230-0402	AR
69	23013A077-3	MINCOM	SHIM-TAPE GUIDE, .010 THK	83-3230-0403	AR
70	23013A077-4	MINCOM	SHIM-TAPE GUIDE, .020 THK	83-3230-0404	AR
65	23013A013-6	D MINCOM	TAPE GUIDE-INC,1/2 IN TAPE	11 83-3240-0397	2.0
66	23013A014-6	C MINCOM	TAPE GUIDE-OUTGOING,1/2 IN	11 83-3240-0399	2.0

P A R T S L I S T

PL 23013R940

REV B

TITLE KIT-SPEED, 3 3/4-7 1/2 IPS

CATALOG NO. 83-5990-0559

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C010-1	F MINCOM	MOTOR ASSY-CAPSTAN, 3 3/4-7 1/2	83-4560-0149	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR, MODEL 23	83-3650-0363	1.0
9	MS16998-27	MIL STD	SCREW-CAP, SOC HD, 10-32 X 1/2	83-9261-2101	4.0
10			WASHER-FLAT, GENERAL PURPOSE, #10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	4.0
12	23007A061	D MINCOM	FLYWHEEL-CAPSTAN, MODEL 23	83-3220-0146	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL, PRECISION PLATE	83-3250-0082	1.0
14			SCR-CAP, FH, 1/4X20X5/8, NYLOC	83-9262-0569	1.0
15	23007A023-2	C MINCOM	CAP-IDLER, REVERSING, PLAIN	83-3250-0108	1.0

P A R T S L I S T

PL 23013B945-1

REV C

TITLE KIT-SPEED, 7 1/2-15 IPS

CATALOG NO. 83-5990-0560

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C010-2	F MINCOM	MOTOR ASSY-CAPSTAN,7 1/2-15	83-4560-0150	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR,MODEL 23	83-3650-0363	1.0
8	23007A014-1	B MINCOM	SPACER-MOTOR MTG,7 1/2-15 IPS	83-3230-0311	1.0
9	MS16998-28	MIL STD	SCREW-CAP,SOC HD,10-32 X 5/8	83-9261-2102	4.0
10			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	4.0
12	23007A061	D MINCOM	FLYWHEEL-CAPSTAN,MODEL 23	83-3220-0146	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL,PRECISION PLATE	83-3250-0082	1.0
14			SCR-CAP,FH,1/4X20X5/8,NYLOC	83-9262-0569	1.0
15	23007A023-2	C MINCOM	CAP-IDLER,REVERSING,PLAIN	83-3250-0108	1.0

P A R T S L I S T

PL 23013B945-2

REV C

TITLE KIT-SPEED, 7 1/2-15 IPS, 50 CYC

CATALOG NO. 83-5990-0582

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C010-4	F MINCOM	MOTOR ASSY-CAPSTAN, 50 CYCLE	83-4560-0158	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR, MODEL 23	83-3650-0363	1.0
8	23007A014-1	B MINCOM	SPACER-MOTOR MTG, 7 1/2-15 IPS	83-3230-0311	1.0
9	MS16998-28	MIL STD	SCREW-CAP, SOC HD, 10-32 X 5/8	83-9261-2102	4.0
10			WASHER-FLAT, GENERAL PURPSE, #10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	4.0
12	23007A061	D MINCOM	FLYWHEEL-CAPSTAN, MODEL 23	83-3220-0146	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL, PRECISION PLATE	83-3250-0082	1.0
14			SCR-CAP, FH, 1/4X20X5/8, NYLOC	83-9262-0569	1.0
15	23007B023	A MINCOM	CAP-CAPSTAN STRORE, 50 HZ	83-3250-0183	1.0

P A R T S L I S T

PL 23013B950-1

REV C

TITLE KIT-SPEED, 15-30 IPS

CATALOG NO. 83-5990-0561

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C010-3	F MINCOM	MOTOR ASSY-CAPSTAN,15-30	83-4560-0151	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR,MODEL 23	83-3650-0363	1.0
8	23007A014-2	B MINCOM	SPACER-MOTOR MTG, CAPSTAN	83-3230-0312	1.0
9	MS16998-29	MIL STD	SCREW-CAP,SOC HD,10-32 X 3/4	83-9261-2103	4.0
10			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	4.0
12	23007A061	D MINCOM	FLYWHEEL-CAPSTAN,MODEL 23	83-3220-0146	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL,PRECISION PLATE	83-3250-0082	1.0
14			SCR-CAP,FH,1/4X20X5/8,NYLUC	83-9262-0569	1.0
15	23007A023-2	C MINCOM	CAP-IDLER,REVERSING,PLAIN	83-3250-0108	1.0

P A R T S L I S T

PL 23013B950-2

REV C

TITLE KIT-SPEED,15-30 IPS,50 CYCLE

CATALOG NO. 83-5990-0581

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C010-5	F MINCOM	MOTOR ASSY-CAPSTAN,15-30,50 CY	83-4560-0159	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR,MODEL 23	83-3650-0363	1.0
8	23007A014-3	A MINCOM	SPACER-MOTOR MTG,CAPSTAN	83-3230-0469	1.0
9	MS16998-29	MIL STD	SCREW-CAP,SOC HD,10-32 X 3/4	83-9261-2103	4.0
10			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	4.0
12	23007A061	D MINCOM	FLYWHEEL-CAPSTAN,MODEL 23	83-3220-0146	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL,PRECISION PLATE	83-3250-0082	1.0
14			SCR-CAP,FH,1/4X20X5/8,NYLOC	83-9262-0569	1.0
15	23007B023	A MINCOM	CAP-CAPSTAN STROBE, 50 HZ	83-3250-0183	1.0

P A R T S L I S T

PL 23013B955

REV C

TITLE KIT-SPEED, 30-60 IPS

CATALOG NO. 83-5990-0562

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C410-1	B MINCOM	MOTOR ASSY-CAPSTAN, 30-60	83-4560-0152	1.0
7	23007A016	B MINCOM	SHIELD-CAPSTAN MOTOR, MODEL 23	83-3650-0363	1.0
9	MS16998-27	MIL STD	SCREW-CAP, SOC HD, 10-32 X 1/2	83-9261-2101	4.0
10			WASHER-FLAT, GENFRAL PURPSE, #10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	4.0
12	23007A461	E MINCOM	FLYWHEEL-CAPSTAN, 120 IPS	83-3220-0171	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL, PRECISION PLATE	83-3250-0082	1.0
14			SCREW-SELF LOCK, FH, 1/4-20 X 3/4	83-9262-0204	1.0
15	23007A023-2	C MINCOM	CAP-IDLER, REVERSING, PLAIN	83-3250-0108	1.0

TITLE KIT-SPEED, 60-120 IPS

CATALOG NO. 83-5990-0563

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
6	23007C410-2	B MINCOM	MOTOR ASSY-CAPSTAN, 60-120	83-4560-0153	1.0
9	MS16998-27	MIL STD	SCREW-CAP, SOC HD, 10-32 X 1/2	83-9261-2101	4.0
10			WASHER-FLAT, GENERAL PURPOSE, #10	83-9261-4006	4.0
11	MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	4.0
12	23007A461	E MINCOM	FLYWHEEL-CAPSTAN, 120 IPS	83-3220-0171	1.0
13	19007A022	D MINCOM	CAP-FLYWHEEL, PRECISION PLATE	83-3250-0082	1.0
14			SCREW-SELF LOCK, FH, 1/4-20 X3/4	83-9262-0204	1.0
15	23007A023-2	C MINCOM	CAP-IDLER, REVERSING, PLAIN	83-3250-0108	1.0

P A R T S L I S T

PL 23013A970

REV D

TITLE KIT-BRAKE, CAPSTAN,HIGH SPEED

CATALOG NO. 83-5990-0438

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C71	36D552G025AB	SPRAGUE	CAP-FXD,ELECT,5500 UF 25 V	83-1510-2171	1.0
C72	200P1904	SPRAGUE	CAP-FXD,ELEC,5 MF 370VAC 10%	83-1510-2243	1.0
L6	42C115DC-AX	PHILLIPS CON	SOLENOID-LINEAR, 115 VOLTS	83-1550-4517	1.0
1	36-909H	SPRAGUE	BRACKET-CAPACITOR MTG	83-1320-1587	2.0
2	21FK-832	STD PRSD STL	NUT-HEX,SELF LOCK,8-32 X.345WD	83-9260-2405	2.0
3			SCREW-MACH,PAN HD,8-32 X 9/16	83-9260-4552	2.0
4	MS27183-7	MIL STD	WASHER-FLAT,RD,#8,GEN PURPOSE	83-9261-4038	2.0
5	60510-4	AMP INC	CONTACT-ELEC,SOC,18-22GA SIZE	83-1610-0927	1.0
6	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	1.0
76	AN742D-22		CLAMP-LOOP,CABLE SPT,2.047 LG	83-1650-0393	2.0
77			NUT-HEX,SM PATT,8-32 X .313 WD	83-9260-2203	2.0
78	MS35206-245	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/2	83-9260-4551	2.0
79			WASHER-FLAT,SM PATT,#8	83-9261-4035	2.0
80			WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4306	2.0
81	23013B065	E MINCOM	DELAY RELAY ASSY-3 RELAYS	83-4930-1478	1.0
82	MS35207-263	MIL STD	SCREW-MACH,PAN HD,10-32 X 1/2	83-9260-4572	2.0
83	RAA-217	THOM & BETTS	SPLICE-CONDUCTOR,BUTT TYPE	83-9630-0382	12.0
86	23013A403	A MINCOM	ADAPTER-SOLENOID,BRAKE,	83-3240-0365	1.0
87	23013A402	B MINCOM	BRACKET-SUPPORT,BRAKE,120 IPS	83-3320-1293	1.0
88	23013A404	C MINCOM	PAD-BRAKE,CAPSTAN MOTOR,120	83-3350-0452	1.0
89	21-S-094-0437	STD PRSD STL	PIN-SPRING, .094 DIA X.437LG	83-7280-0223	1.0
90	MS16998-27	MIL STD	SCREW-CAP,SOC HD,10-32 X 1/2	83-9261-2101	2.0
91			SCREW-SHC, 8-32X1/4	83-9261-2057	2.0
92			WASHER-FLAT,SM PATT,#8	83-9261-4035	2.0
93			WASHER-FLAT,SM PATT,#10	83-9261-4046	2.0
94			WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4306	2.0
95	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	2.0
96	23013A405	A MINCOM	SPRING-RETURN,SOLENOID,BRAKE	83-3280-0567	1.0

P A R T S L I S T

PL 23013A986

REV A

TITLE BASE-REEL HUB, 1/4 CINE TOP HAT

CATALOG NO. 83-3240-0455

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23013A160	A MINCOM	HUB ASSY-REEL, 1/4 IN TAPE	83-4930-1884	1.0
2	04020.108	H MINCOM	STANDOFF-CHASSIS MTG, .875 LG	83-3350-0022	1.0
3	MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	1.0
4			SCREW-MACH, BIND H, 6-32 X 3/8	83-9260-4294	1.0

P A R T S L I S T

PL 230138990

REV G

TITLE KIT-COMMON PARTS,TAPE DECK

CATALOG NO. 83-5990-0564

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
DS1,DS2,DS3,DS4,DS5,DS6	327	GENERAL ELEC	LAMP-INCANDESCENT, .04 AMP	83-1550-2506	6.0
DS8	1820	GE	LAMP-INCANDESCENT, 28 V,.10 A	83-1550-2602	1.0
F1	313005.	LITTELFUSE	FUSE-SLO-RLO,125V 5 AMP	83-7550-8006	1.0
L1,L2	42C24DC-AX	PHILLIPS CON	SOLENOID-ELECTRICAL,PUSH/PULL	83-1550-4516	2.0
L3	128281	G.H. LELAND	SOLENOID-115 VDC	83-1550-4515	1.0
L4	128264-001	LEDEX	SOLENOID-ROTARY	83-1550-4514	1.0
L5	42C24DC-AU	PHILLIPS CON	SOLENOID-ELECTRICAL,PUSH/PULL	83-1550-4513	1.0
101	23013A002	L MINCOM	PLATE-TAPE DECK,TRANSPORT	83-3320-1027	1.0
102	GP67-125X500-12	GRUOV-PIN	PIN-GRVD,HDLS, .125 DIA X.500LG	83-7280-0202	3.0
103	GP7-125X1000-12	GRUOV-PIN	PIN-GRVD,HDLS,.125 X 1.000 LG	83-7280-0212	1.0
104	GP4-125X0500-12	GRUOV-PIN	PIN-GRND,HDLS, .125 DIA X.500LG	83-7280-0484	3.0
106	AMF5DD-FS160	FAFNIR	BRG-BALL,ANLR,FLNGD,.3125 BORE	83-1230-0178	6.0
107	23013A035	B MINCOM	SHAFT-ARM,IDLER,TAPE TRANSPORT	83-3280-0407	2.0
108	23013B036	A MINCOM	SHAFT-MTG, TAPE LIFTER	83-3280-0536	1.0
109	RF51624	PALNUT	NUT-HEX,STMPD,5/16-24 X .500WD	83-9260-2404	3.0
114	1126	BIRNBACH	SPACER-RD,#6 SCREW SIZE,.375LG	83-9350-0099	2.0
115	23013A067	B MINCOM	ARM-ACTUATOR, TAPE LIFTER	83-3210-0253	1.0
116	23013A028	D MINCOM	BRACKET-MTG,SOLENOID,TPE TRANS	83-3320-1107	1.0
117	23013A011	D MINCOM	BRACKET-MTG,SOLENOID,RH	83-3320-1108	1.0
118	23013A048	A MINCOM	BRACKET-SOLENOID MTG,CAPSTAN	83-3320-1159	1.0
119	23013A047	A MINCOM	BRACKET-SOLENOID MTG,TAPE LIFT	83-3320-1167	1.0
120	23013A025	A MINCOM	SUPPORT-DASHPOT,DOOR,HEAD COVR	83-3340-0382	1.0
121	23013A055	A MINCOM	SPACER-COVER PLATE,TRANSPORT	83-3350-0414	2.0
122	TRUARC	MIL STD	RING-RETAINING,EXT,.225 I.D.	83-7270-0118	1.0
123	#775	H.H. SMITH	CLAMP-CABLE,NYLON,.479 DIA	83-7650-0058	1.0
125	MS35206-241	MIL STD	SCREW-MACH,PAN HD,8-32 X 1/4	83-9260-4547	1.0
126	MS35206-243	MIL STD	SCREW-MACH,PAN HD,8-32 X 3/8	83-9260-4549	1.0
127	MS51017-26	MIL STD	SETSCREW-CUP PT,6-32 X 1/2	83-9261-0051	2.0
128			SCREW-SHC, 8-32X1/4	83-9261-2057	4.0
129	MS16998-26	MIL STD	SCREW-CAP,SOC HD,10-32 X 3/8	83-9261-2100	2.0
136	23013A045	A MINCOM	SPACER-PWR SUP MTG,1.430 LG	83-3350-0412	1.0
137	23013B080	C MINCOM	CHASSIS ASSY-WRAP AROUND,TRANS	83-5920-1332	1.0
138	MS35206-217	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/2	83-9260-4517	4.0
139	MS35206-237	MIL STD	SCREW-MACH,PAN HD,6-32 X 1.750	83-9260-4544	1.0
140	23013A172	B MINCOM	BRACKET ASSY-PHOTOCELL	83-4320-1679	1.0
146	23013A044	A MINCOM	SPRING-RETURN,IDLER ARM,CAPSTN	83-3280-0422	3.0
147	23007A054	A MINCOM	SPRING-SHOCK ABSORBING-IDLER	83-3280-0542	1.0
148	23013A090-1	A MINCOM	ARM ASSY-IDLER,ROLLER,LH	83-4210-0230	1.0
149	23013A090-2	A MINCOM	ARM ASSY-IDLER,ROLLER,RH	83-4210-0231	1.0

TITLE KIT-COMMON PARTS,TAPE DECK

CATALOG NO. 83-5990-0564

----- MATERIAL REQUIREMENTS -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
150	23007A050-1	K MINCOM	ARM ASSY-IDLER, ACTUATING,RH	83-4210-0232	1.0
151	23007A050-2	K MINCOM	ARM ASSY-IDLER,ACTUATING,LH	83-4210-0256	1.0
152		RUBBERCRAFT	BUMPER-RUB,SLV,.125 ID X .313	83-7230-0337	1.0
153		MIL STD	RING-RETAINING,TYPE E,1/4 ID	83-7270-0413	2.0
154	21-S-094-0437	STD PRSD STL	PIN-SPRING, .094 DIA X .437 LG	83-7280-0223	3.0
155	6593	BIRNBACH	INSULATOR-WASH, NYLON,.016 TK	83-9630-0272	5.0
156	23013A074	B MINCOM	BUMPER-RUB SLV,.06 ID X .310 LG	83-3230-0390	1.0
157	23013A073	A MINCOM	SPACER-MACHINED,DAMPENER,TEF	83-3230-0391	1.0
161	303-85-15-1.25	ELEC REGULTR	DASHPOT-AIR DAMPING CYLINDER	83-1270-0491	1.0
162	23013A046	C MINCOM	ARM-DAMPENING,IDLER	83-3210-0223	1.0
163	5555-12	TRUARC	RING-RETN, EXT, .120 ID	83-7270-0503	3.0
166	303-85-15-1000	ELEC REGULTR	DASHPOT-AIR DAMPING CYLINDER	83-1270-0490	1.0
167	23013A095	B MINCOM	ARM ASSY-ACTUATOR,DOOR HD CVR	83-4210-0237	1.0
171	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	3.0
172			SETSCREW-LGLK,HEX,CUP,10-32X1.	83-9261-0271	1.0
174	J-7219-8	LORD	MOUNT-RESILIENT,RUBBER	83-1320-1096	1.0
175	23013A068	A MINCOM	BRACKET-VERTICAL MTG,TRANSPORT	83-3320-1675	1.0
177	23007A070	C MINCOM	BRKT ASSY-MOTOR MTG,CAPS DRIVE	83-4320-1476	1.0
178	23012A000	A MINCOM	BRACKET ASSY-VERNIER SPEED ADJ	83-4930-1002	1.0
179	MS16998-31	MIL STD	SCREW-SHC, 10-32X1	83-9261-2105	1.0
180	NAS1352-06	NYLOK CORP	SCREW-CAP,SOC HD,6-32 X 1.00	83-9261-2135	1.0
181	MS35690-602	MIL STD	NUT-HEX,PLAIN,3/8-16 X .563 WD	83-9260-2011	1.0
182	AN960-616	AN STANDARD	WASHER-FLAT,GENERAL PURP,#3/8	83-9261-4015	1.0
183	MS35333-42	MIL STD	WASHER-LOCK,FLAT,INT T,#3/8	83-9261-4211	1.0
186	01123060	REVERE	HUB ASSY-REEL,MODEL 23	83-1930-0959	2.0
188	23004A000	F MINCOM	MOTOR ASSY-TAKE UP REEL	83-4560-0090	1.0
189	23004A050	B MINCOM	MOTOR ASSY-REWIND,REEL	83-4560-0092	1.0
191	23013A085	A MINCOM	CONN-PLUG,SHORTING,TAPE TRANS	83-4610-1136	1.0
192	23013B060	G MINCOM	P.C. BD ASSY-LOGIC TRANSPORT	83-4930-1716	1.0
196	185-1873	DIALCO	LENS-CAP ASSY,1/2 IN SQ,AMBER	83-1550-5243	1.0
197	185-1872	DIALCO	LENS-CAP ASSY,1/2 IN SQ,GREEN	83-1550-5244	1.0
199	23013A004	B MINCOM	COVER-LAMP,DECORATIVE	83-3310-0833	1.0
200	16049A015-3	L MINCOM	LENS-INDICATOR LIGHT,*REWIND*	83-3550-1207	1.0
201	16049A015-4	L MINCOM	LENS-INDICATOR LIGHT,*FORWARD*	83-3550-1208	1.0
202	23013A005	C MINCOM	LENS-LAMP,TAPE SENSOR	83-3550-1406	2.0
203	23013A027	C MINCOM	LENS-LIGHTED SWITCH,PUSHBUTTON	83-3550-1408	1.0
204	23013A038-1	E MINCOM	LENS-IND LT,ENGRAVED STOP	83-3550-1417	1.0
205	16049A015-35	L MINCOM	LENS-INDICATOR LIGHT,*RECORD*	83-3550-1436	1.0
206	16049A015-36	L MINCOM	LENS-INDICATOR LIGHT,*PLAY*	83-3550-1437	1.0
207	DK-153	GASKET MFG	STRIP-GASKET MATL,3/8 X 1/32	83-1190-0073	1.0
208		MIL STD	SCREW-MACH,OVAL HD,6-32 X 7/8	83-9261-4340	4.0
216	17460S	BELDON	CABLE ASSY-PWR,ELEC, 10 FT LG	83-1570-0303	1.0




Figure 47. Tape Deck Assembly

P A R T S L I S T

PL 23013B990

REV G

TITLE .KIT-COMMON PARTS,TAPE DECK

CATALOG NO. 83-5990-0564

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
217	23007A001	A MINCOM	COVER-HEAD,MODEL 23	83-3310-0832	1.0
218	23013A015	D MINCOM	COVER-CAPSTAN,RH,DECORATIVE	83-3310-0834	1.0
219	23013A032	E MINCOM	COVER-CAPSTAN,LH,DECORATIVE	83-3310-0835	1.0
220	23013A007	B MINCOM	BRACKET-MTG,TAPE DECK	83-3320-1114	2.0
221	MS24693-S272	MIL STD	SCREW-MACH,FH,10-32 X 1/2	83-9260-6294	8.0
222	MS35190-240	MIL STD	SCREW-MACH,FH,6-32 X 3/4	83-9260-6522	2.0
231			NUT-HEX,SM PATT,8-32 X .313 WD	83-9260-2203	AR
232	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	AR
233	MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	AR
234	MS35207-261	MIL STD	SCREW-MACH,PAN HD,10-32 X 3/8	83-9260-4570	AR
235			WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	AR
236			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	AR
237			WASHER-FLAT,SM PATT,#6	83-9261-4013	AR
238			WASHER-FLAT,SM PATT,#8	83-9261-4035	AR
239			WASHER-FLAT,SM PATT,#10	83-9261-4046	AR
240	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	AR
241	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	AR
242			WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4306	AR
243	MS35338-43	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#10	83-9261-4307	AR
244	MS35190-223	MIL STD	SCREW-MACH,FH,4-40 X 3/8	83-9260-6504	AR
245	00000A741-3	E MINCOM	LABEL-IDENT,PATENT, MOD 23	83-3550-1500	1.0
246	00000A769	C MINCOM	LABEL-IDENTIFICATION,MODULE	83-3550-1621	1.0

TITLE CONTROL ASSY-REMOTE,OPTIONAL

CATALOG NO. 83-5920-0823

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
DS1,DS2,DS3,DS4,DS5 DS6	327 380672-4	GENERAL ELEC AMP INC	LAMP-INCANDESCENT, .04 AMP LIGHT ASSY-PILOT,AMBER,24VOLTS	83-1550-2506 83-1550-2590	5.0 1.0
P1	201359-3	AMP INC	SHELL-COMM,RECT,26 POSITIONS	83-1610-0674	1.0
S1,S2,S3,S4,S5 S6,S7	1018P 513-0101-604	PENDAR DIALCO	SWITCH-PUSHBUTTON,SPDT,MOMENTY SWITCH-MOMENTARY,PAKE	83-1550-5177 83-1550-5233	5.0 2.0
1	23017A001	MINCOM	PANEL-SWITCH, MODE CONTROL	83-3360-0975	1.0
2	23017A002	MINCOM	HOUSING-MODE CONTROL	83-3310-1039	1.0
3	23017A003	C MINCOM	CHASSIS-SWITCH, MODE CONTROL	83-3310-1040	1.0
4	42980-1-LP	4 AMP INC	PIN-CONTACT,CONN,20-24 GA WIRE	83-1610-0638	15.0
5	42452-1	AMP INC	CONT-ELECT, SOCKET CLIP, .220 WD	83-1610-0847	2.0
6	201923-1	AMP INC	CLIP-SPRING TENSION, MALE	83-1620-0126	1.0
7	201229-1	AMP INC	CLAMP-ELEC, STRAIN REL, .779 MCE	83-1650-0244	1.0
8	00000A769	C MINCOM	LABEL-IDENTIFICATION,MODULE	83-3550-1621	1.0
9	200389-4	AMP INC	PIN-GUIDE,CENTER,AMP SERIES M	83-7260-0196	1.0
10	TY15	THOMS & BETS	CLAMP-LOOP,NYLON TYRAP,7.81 LG	83-7650-0056	1.0
11	8748	BELDEN	WIRE-TYPE 8748, 22 GA,18CONDUCT	83-7910-0534	AP
12	200390-4	AMP INC	RECP-GUIDE PIN,CENTER,SERIES M	83-7270-0302	1.0
13	#7	RUBBERCRAFT	GROMMET-RUBBER,.375ID X.687 OD	83-9630-0097	1.0
14	MS35206-229	MIL STD	SCREW-MACH,PAN HD,6-32 X 7/16	83-9260-4532	5.0
15	MS24693-S25	MIL STD	SCREW-MACH,FH,6-32 X 5/16	83-9260-6555	2.0
16	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	5.0
17			WASHER-FLAT,SM PATT,#6	83-9261-4013	5.0
18	16049A015-3	L MINCOM	LENS-INDICATOR LIGHT,*REVIEW*	83-3550-1207	1.0
19	16049A015-4	L MINCOM	LENS-INDICATOR LIGHT,*FORWARD*	83-3550-1208	1.0
20	16049A015-35	L MINCOM	LENS-INDICATOR LIGHT,*RECORD*	83-3550-1436	1.0
21	16049A015-36	L MINCOM	LENS-INDICATOR LIGHT,*PLAY*	83-3550-1437	1.0
22	23013A038-1	E MINCOM	LENS-IND LT,ENGRAVED STOP	83-3550-1417	1.0
23	185-1873	DIALCO	LENS-CAP ASSY,1/2 IN SQ,AMBER	83-1550-5243	1.0
24	185-1872	DIALCO	LENS-CAP ASSY,1/2 IN SQ,GREEN	83-1550-5244	1.0




Figure 48. Remote Control Assembly

P A R T S L I S T

PL 23017A010

REV A

TITLE CABLE ASSY-EXT,REMOTE CONTROL

CATALOG NO. 83-4570-0428

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
J1	200512-3	AMP INC	SHELL-CONN,RECT,26 POSITIONS	83-1610-0663	1.0
P1	201359-3	AMP INC	SHELL-CONN,RECT,26 POSITIONS	83-1610-0674	1.0
3	42980-1-LP	4 AMP INC	PIN-CONTACT,CONN,20-24 GA WIRE	83-1610-0688	18.0
4	42981-1-LP	4 AMP INC	SOCKET-CONTACT,CONN, SIZE 16	83-1610-0689	18.0
5	201923-1	AMP INC	CLIP-SPRING TENSION, MALE	83-1620-0126	1.0
6	201924-1	AMP INC	CLIP-SPG TENS,POSITION LOCKING	83-1620-0127	1.0
7	201229-1	AMP INC	CLAMP-ELEC,STRAIN REL,.779 MCE	83-1650-0244	2.0
8	200390-4	AMP INC	RECP-GUIDE PIN,CENTER,SERIES M	83-7270-0302	2.0
9	200389-4	AMP INC	PIN-GUIDE,CENTER,AMP SERIES M	83-7280-0196	2.0
10	8748	BFLDEN	WIRE-TYPE 8748, 22 GA,18CUNDUC	83-7910-0534	25.0

TITLE CONTROL ASSY-REMOTE, SYNC

CATALOG NO. 83-5920-1493

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	1.0
CR1, CR2	1N4002	MOTOROLA	RECT-SI, SEMICOND, 100PIV, 1 A	83-1530-0122	2.0
DS1, DS2, DS3, DS4, DS5	327	GENERAL ELEC	LAMP-INCANDESCENT, .04 AMP	83-1550-2506	5.0
DS6	380672-4	AMP INC	LIGHT ASSY-PILOT, AMBER, 24VOLTS	83-1550-2590	1.0
DS7, DS8, DS9, DS10, DS11, DS12, DS13, DS14, DS15, DS16, DS17, DS18, DS19, DS20, DS21, DS22	L-28/40	MURA	LAMP-PANEL ASSY, 28 V 40 MA	83-1550-2603	16.0
P1	201359-3	AMP INC	SHELL-CONN, RECT, 26 POSITIONS	83-1610-0674	1.0
P2	200512-3	AMP INC	SHELL-CONN, RECT, 26 POSITIONS	83-1610-0663	1.0
R1	0A781-7220	MINCOM SPEC	RES-FXD, FILM, 220 OHM, 1/2W, 2% S	83-1520-7220	1.0
S1, S2, S3, S4, S5	1018P	PENDAR	SWITCH-PUSHBUTTON, SPDT, MOMENTY	83-1550-5177	5.0
S6, S7	513-0101-604	DIALCO	SWITCH-MOMENTARY, MAKE	83-1550-5233	2.0
S8, S9, S10, S11, S12, S13, S14, S15	1454	CENTRALAB	SWITCH-LEVER, WAFER TYPE, 2P3POS	83-1550-0031	8.0
S16	DP7	TORSION BAL	SWITCH-TOGGLE, DPDT, 5 AMP	83-1550-5061	1.0
1	23017A101	B MINCOM	PANEL-FRONT, CONT, REMOTE SYNC	83-3360-1206	1.0
2	23017A102	A MINCOM	HOUSING-CONT, REMOTE SYNC	83-3310-1248	1.0
3	23017A003	C MINCOM	CHASSIS-SWITCH, MODE CONTROL	83-3310-1040	1.0
4	00000A773-1	A MINCOM	KNOB-SWITCH LEVER, STAMPED #1	83-3270-0664	1.0
5	00000A773-2	A MINCOM	KNOB-SWITCH LEVER, STAMPED #2	83-3270-0665	1.0
6	00000A773-3	A MINCOM	KNOB-SWITCH LEVER, STAMPED #3	83-3270-0666	1.0
7	00000A773-4	A MINCOM	KNOB-SWITCH LEVER, STAMPED #4	83-3270-0667	1.0
8	00000A773-5	A MINCOM	KNOB-SWITCH LEVER, STAMPED #5	83-3270-0668	1.0
9	00000A773-6	A MINCOM	KNOB-SWITCH LEVER, STAMPED #6	83-3270-0669	1.0
10	00000A773-7	A MINCOM	KNOB-SWITCH LEVER, STAMPED #7	83-3270-0670	1.0
11	00000A773-8	A MINCOM	KNOB-SWITCH LEVER, STAMPED #8	83-3270-0671	1.0
12	16049A015-3	L MINCOM	LENS-INDICATOR LIGHT, *REWIND*	83-3550-1207	1.0
13	16049A015-4	L MINCOM	LENS-INDICATOR LIGHT, *FORWARD*	83-3550-1208	1.0
14	16049A015-35	L MINCOM	LENS-INDICATOR LIGHT, *RECORD*	83-3550-1436	1.0
15	16049A015-36	L MINCOM	LENS-INDICATOR LIGHT, *PLAY*	83-3550-1437	1.0
16	23013A038-1	E MINCOM	LENS-IND LT, ENGRAVED STOP	83-3550-1417	1.0
17	185-1873	DIALCO	LENS-CAP ASSY, 1/2 IN SQ, AMBER	83-1550-5243	1.0
18	185-1872	DIALCO	LENS-CAP ASSY, 1/2 IN SQ, GREEN	83-1550-5244	1.0
19			WASHER-FLAT, SM PATT, #6	83-9261-4013	4.0
20	42980-1-LP	4 AMP INC	PIN-CONTACT, CONN, 20-24 GA WIRE	83-1610-0688	18.0
21	42452-1	AMP INC	CONT-ELECT, SOCKET CLIP, .220 WD	83-1610-0847	2.0
22	201923-1	AMP INC	CLIP-SPRING TENSION, MALE	83-1620-0126	1.0

P A R T S L I S T

PL 23017A100

REV B

TITLE CONTROL ASSY-REMOTE,SYNC

CATALOG NO. 83-5920-1493

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
23	201229-1	AMP INC	CLAMP-ELEC, STRAIN REL, .779 MCE	83-1650-0244	2.0
24	00000A662-1	C MINCOM	LABEL-IDENT, ASSY	83-3550-1276	1.0
25	200389-4	AMP INC	PIN-GUIDE, CENTER, AMP SERIES M	83-7280-0196	2.0
26	MS35206-227	MIL STD	SCREW-MACH, PAN HD, 6-32 X 5/16	83-9260-4530	4.0
27	8748	BELDEN	WIRE-TYPE 8748, 22 GA, 18 CONDUCT	83-7910-0534	AR
28	200390-4	AMP INC	RECP-GUIDE PIN, CENTER, SERIES M	83-7270-0302	1.0
29	SR-9P-1	HEYMAN	BUSHING-STRAIN RELIEF, CABLE	83-1690-0337	1.0
30	8070-E	LERCO	SPACER-SLV, HEX, TAP, .500 LG	83-9350-0063	2.0
31	3935-10	CAMBION	SPACER-THD 6-32 .250 HEX 7/8 L	83-9350-0580	2.0
32	C12008-020	TINNERMAN	NUT-SHEET SPRING,	83-9260-0115	16.0
33		MURA	LENS-CAP, INDICATOR, GREEN	83-1550-1618	8.0
34		MURA	LENS-INDICATOR LIGHT, CAP, RED	83-1550-1616	8.0
35	MS24693-S24	MIL STD	SCREW-MACH, FH, 6-32 X .250 100	83-9260-6571	20.0
36	MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	4.0
37		3M	BUMPER-RUB, ADHESIVE MTG, .50 SQ	83-1230-0449	4.0
38	42981-1-LP	4 AMP INC	SOCKET-CONTACT, CONN, SIZE 16	83-1610-0689	18.0
39	201924-1	AMP INC	CLIP-SPG TENS, POSITION LOCKING	83-1620-0127	1.0

TITLE CONSOLE ASSY-CAR, BASIC

CATALOG NO. 83-4310-0998

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1			ALLMETAL	PIN-DOWEL .250 X 1.250	83-1280-0225	2.0
2		23028A010	A MINCOM	HINGE-PIVOT, CABINET, CONSOLE	83-3270-0560	2.0
3		23028A035-1	D MINCOM	CABINET-ENCLOS, CONSOLE, WAL VEN	83-3310-0840	1.0
4		23028A002	A MINCOM	BRKT-MTG, CABINET	83-3320-1415	2.0
5		23028A043	MINCOM	BRKT-SUP, CABINET	83-3320-1420	1.0
6		23028A001	A MINCOM	TRIM-BAR, CABINET	83-3330-0314	1.0
7		00000A759	MINCOM	PLATE NAME UNIVERSAL	83-3330-0336	1.0
8		23028A005	C MINCOM	SUPPORT-TRANSPORT, CABINET	83-3340-0500	1.0
9		23028A044	A MINCOM	SPACER-PLATE, TRANSPORT SUP	83-3350-0474	2.0
10		23028A015-1	B MINCOM	PANEL-FILLER, CABINET	83-3360-0932	1.0
11		00000A627-10	S MINCOM	LABEL-I.D., M-23, PROFESSION REC	83-3550-1482	1.0
12		MS35649-42	MIL STD	NUT-HEX, PLAIN, 4-40 X .250 WD	83-9260-2003	3.0
14		MS35649-82	MIL STD	NUT-HEX, PLAIN, 8-32 X .344 WD	83-9260-2006	4.0
15		MS24693-S51	MIL STD	SCREW-MACH, FH, 8-32 X .625	83-9260-6563	4.0
16		MS24693-S6	MIL STD	SCREW-MACH, FH, 4-40 X 1/2	83-9260-6572	3.0
17		MS35338-42	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #8	83-9261-4020	4.0
18		AN960-4L	A&N STD	WASHER-FLAT, LIGHT SERIES, #4	83-9261-4024	3.0
20		AN960-8L	A&N STD	WASHER-FLAT, LIGHT SERIES, #8	83-9261-4042	14.0
22		MS35338-40	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #4	83-9261-4303	3.0
24				SCREW-WOOD, RND HD #8 X 7/8	83-9262-0556	4.0
25				SCREW-WOOD, RND HD #8 X 1.00	83-9262-0557	6.0
26				SCREW-WOOD, RND HD #10 X 7/8	83-9262-0558	3.0
27		23000A901	D MINCOM	KIT-INSTALLATION MTG TRANSPORT	83-5990-0415	1.0
28		23028A116	A MINCOM	SHAFT-SPRING, COUNTER BALANCE	83-3280-0614	1.0
29		23028A114	C MINCOM	WASHER-SPRING, COUNTER BALANCE	83-3261-4350	2.0
30		23028A115	A MINCOM	SPACER-SPRING, COUNTER BALANCE	83-3350-0541	12.0
32		#9	DUCOMMUN	PLATE-MOUNTING, FLANG, 3/4 THD	83-1320-1705	1.0
33		MS24665-2/6		PIN-COTTER, .078 DIA X 1 1/2 LG	83-7280-0617	2.0
34		MS35494-629		SCREW-WOOD, FLAT HD, 16-9, 1 1/4	83-9260-0056	4.0
36		MS35207-263	MIL STD	SCREW-MACH, PAN HD, 10-32 X 1/2	83-9260-4572	2.0
37				WASHER-FLAT, GENERAL PURPSE, #10	83-9261-4006	2.0
39		H31U58	HUNTER SPR	SPRING-EXTENSION, .031 THKX 2WD	83-1280-0616	1.0
40		23028A112	MINCOM	ARM-SUPPORT, COUNTER BALANCE	83-3210-0287	1.0
41		MS35338-43	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #10	83-9261-4307	2.0
42		AN960-516L	AN STD	WASHER-FLAT, LIGHT SERIES, #5/16	83-9261-4014	1.0
43		MS35650-102	MIL STD	NUT-HEX, PLAIN, 10-32 X .375 WD	83-9260-2107	2.0
44		MS24665-208	MIL STD	PIN-COTTER, .078 DIA X .500 LG	83-7280-0322	1.0

P A R T S L I S T

PL 23028A050

REV B

TITLE CABLE ASSY-PWR,4TRK,36 IN

CATALOG NO. 83-4570-0346

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	51.0
2	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
3	1-480324-0	AMP INC	SHELL-CONN,RECT, 15POSITION	83-1610-0933	4.0
4		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
5		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
6		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
7		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
8		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
9		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
10		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
11		NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
12	3025-070-5/16ID 3M		TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
13	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
14	G5B134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	8.0
15	G5C194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	8.0
16		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR

TITLE CABLE ASSY-PWR,4 TRK,66 IN

CATALOG NO. 83-4570-0380

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	51.0
2	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
3	1-480324-0	AMP INC	SHELL-CONN,RECT, 15POSITION	83-1610-0933	4.0
4		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
5		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
6		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
7		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
8		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
9		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
10		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
11		NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
12	3025-070-5/16ID 3M		TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
13	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
14	GSC134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	8.0
15	GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	8.0
16		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR

P A R T S L I S T

PL 23028A060

REV C

TITLE CABLE ASSY-PWR,8 TRK,36 IN

CATALOG NO. 83-4570-0347

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	91.0
2	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
3	1-480324-0	AMP INC	SHELL-CONN,RECT, 15POSITION	83-1610-0933	8.0
4		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
5		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
6		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
7		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
8		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
9		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
10		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
11		NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
12	3025-070-5/16ID 3M		TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
13	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
14	GSR134C	THOM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	16.0
15	GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	16.0
16		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR
17	TYPE YQE-91	BURNDY	SPLICE-ELECTRICAL CONDUCTOR	83-9630-0470	1.0

P A R T S L I S T

PL 23028A065

REV B

TITLE CABLE ASSY-PWR,8 TRK,66

CATALOG NO. 83-4570-0381

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	91.0
2	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
3	1-480324-0	AMP INC	SHELL-CONN,RECT, 15POSITION	83-1610-0933	8.0
4		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
5		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
6		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
7		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
8		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
9		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
10		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
11		NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
12	3025-070-5/16ID 3M		TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
13	NB1934N2SJ	NATL WIRE	WIRE-TYPE B,22GA RED/BLU 2 CON	83-7910-0362	AR
14	GSB134C	THUM & BETTS	FERRULE-RF CABLE GND .134ID	83-9690-0020	16.0
15	GSC194C	THOMAS&BETTS	FERRULE-RF CABLE GROUNDING	83-9690-0118	16.0
16		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR

P A R T S L I S T

PL 23028A070

REV D

TITLE DISPLAY ASSY-METER, 4 BAY

CATALOG NO. 83-5920-1126

M A T E R I A L R E Q U I R E M E N T S

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1		23028A039	MINCOM	HOUSING DISPLAY,METER,MOD 23	83-3310-0993	1.0
2		23028A085	A MINCOM	COVER ASSY-DISPLAY PANEL	83-3310-1157	4.0
3		23028A021-3	MINCOM	SUPPORT-ANGULAR, CABINET	83-3340-0522	1.0
4		23028A021-4	MINCOM	SUPPORT-ANGULAR, CABINET	83-3340-0523	1.0
5		23028A038	A MINCOM	PANEL-FILLER, SUPPORT,HOUSING	83-3360-0933	1.0
6		23028A040	MINCOM	PANEL-HSG,DISPLAY, METER	83-3360-0934	1.0
7		MS35649-62	MIL STD	NUT-HEX,PLAIN,6-32 X .313 WD	83-9260-2005	20.0
8		MS35649-82	MIL STD	NUT-HEX,PLAIN,8-32 X .344 WD	83-9260-2006	8.0
9		MS35206-229	MIL STD	SCREW-MACH,PAN HD,6-32 X 7/16	83-9260-4532	2.0
10				SCR-MACH,F HD,8-32 X 1/2	83-9260-6532	4.0
11		MS24693-S28	MIL STD	SCREW-MACH,FH,6-32 X .500	83-9260-6579	2.0
12		MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	8.0
13		AN960-6L	A & N STD	WASHER-FLAT,LIGHT SERIES,#6	83-9261-4041	23.0
14		AN960-8L	A&N STD	WASHER-FLAT,LIGHT SERIES,#8	83-9261-4042	8.0
15		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	4.0
16		23028A075	C MINCOM	HARNESS ASSY-METER, REMOTE	83-4570-0387	1.0
17				SCREW-WOOD, RD HD,#6 X 7/8	83-9262-0555	3.0
18				SCREW-WOOD, RD HD,#10 X 1.00LG	83-9262-0559	10.0
19				WASHER-FLAT,GENERAL PURPSE,#10	83-9261-4006	10.0
20		AN505-8R9	A & N STD	SCREW-MACH,FH,8-32 X 9/16	83-9260-6533	4.0

TITLE HARNESS ASSY-METER, REMOTE

CATALOG NO. 83-4570-0387

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
P1,P2,P3,P4	1-480276-0	AMP INC	SHELL-CONN,RECT, .665 WD X.850	83-1610-0929	4.0
1	60511-4-LP RA863	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	16.0
2		THOM & BETTS	LUG-TERMINAL SOLDERLS,RING,#8	83-9630-0204	8.0
3		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
4		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
5		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
6		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
7			WIRE-TYPE B,22 GA,VIOLET-WHITE	83-7910-0068	AR
8		AUTOLITE	WIRE-TYPE B,22GA GR/WT NYL JKT	83-7910-0170	AR
10		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
11		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
12		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR
13		NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
14			WIRE-TYPE B,22 GA YELLOW NYLN	83-7910-0259	AR
15			WIRE TYPE B,22 GA GRAY NYLN	83-7910-0261	AR
16			WIRE-TYPE B,22 GA RED NYLN JKT	83-7910-0264	AR
17			WIRE-TYPE B,22 GA BLU NYLN JKT	83-7910-0288	AR
18			WIRE-TYPE B,22GA BRN NYLN JKT	83-7910-0301	AR
19			WIRE-TYPE B,22 GA ORN NYLN JKT	83-7910-0303	AR

P A R T S L I S T

PL 23028A080

REV C

TITLE HOUSING ASSY-SIGNAL ELEC 4TRK

CATALOG NO. 83-4310-1000

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23028A036-1	A MINCOM	FILLER-ANGULAR, REAR, LH, CAB	83-3290-0160	1.0
2	23028A036-2	A MINCOM	FILLER-ANGULAR, REAR, RH, CAB	83-3290-0161	1.0
3	23028A025-1	A MINCOM	HOUSING-UPPER, ELEC 4-BAY	83-3310-0991	1.0
4	23028A041	B MINCOM	HOUSING-LOWER, ELECTRONICS	83-3310-0994	1.0
5	23028A024-1	B MINCOM	BRKT-MTG, HOUSING, LH, ELEC	83-3320-1416	1.0
6	23028A024-2	B MINCOM	BRKT-MTG, HOUSING, RH, ELEC	83-3320-1417	1.0
7	23028A021-1	A MINCOM	SUPPORT-ANGULAR,CAB,CONSOLE LH	83-3340-0504	1.0
8	23028A021-2	A MINCOM	SUPPORT-ANGULAR,CAB,CONSOLE,RH	83-3340-0505	1.0
9	23028A038	A MINCOM	PANEL-FILLER, SUPPORT,HOUSING	83-3360-0933	1.0
10	MS35649-62	MIL STD	NUT-HEX,PLAIN,6-32 X .313 WD	83-9260-2005	14.0
11	MS35649-82	MIL STD	NUT-HEX,PLAIN,8-32 X .344 WD	83-9260-2006	8.0
12	MS35206-229	MIL STD	SCREW-MACH,PAN HD,6-32 X 7/16	83-9260-4532	2.0
13			SCR-MACH,F HD,8-32 X 1/2	83-9260-6532	4.0
14	MS24693-S28	MIL STD	SCREW-MACH,FH,6-32 X .500	83-9260-6579	12.0
15	MS35338-42	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#8	83-9261-4020	8.0
16	AN960-6L	A & N STD	WASHER-FLAT,LIGHT SERIES,#6	83-9261-4041	14.0
17	AN960-8L	A&N STD	WASHER-FLAT,LIGHT SERIES,#8	83-9261-4042	8.0
18	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	14.0
19	A6732-5-02	ESNA	NUT-NON LKG,PL,10-32	83-9260-0059	16.0
20			SCREW-WOOD, RD HD,#10 X 1.00LG	83-9262-0559	10.0
21			SCREW-WOOD, RD HD,#6 X 7/8	83-9262-0555	3.0
22	AN505-8R9	A & N STD	SCREW-MACH,FH,8-32 X 9/16	83-9260-6533	4.0

P A R T S L I S T

PL 23028A085

REV A

TITLE COVER ASSY-DISPLAY PANEL

CATALOG NO. 83-3310-1157

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23028A045	MINCOM	PLATE-COVER,DISPLAY PANEL	83-3320-1444	1.0
2	04032.002-1	E MINCOM	HANDLE-PULL,1.517 LONG	83-3270-0144	1.0
3	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
4			WASHER-FLAT,GENFRAL PURPOSE #4	83-9261-4002	2.0
5	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0

P A R T S L I S T

PL 23028A090

REV C

TITLE HOUSING ASSY-SIGNAL ELEC, 2TRK

CATALOG NO. 83-4310-0999

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23028A036-3	A MINCOM	FILLER-ANGULAR, REAR, LH CAB	83-3290-0162	1.0
2	23028A036-4	A MINCOM	FILLER-ANGULAR, REAR, RH, CAB	83-3290-0163	1.0
3	23028A025-2	A MINCOM	HOUSING-UPPER, ELECTRONICS	83-3310-0992	1.0
4	23028A041	B MINCOM	HOUSING-LOWER, ELECTRONICS	83-3310-0994	1.0
5	23028A024-3	B MINCOM	BRKT-MTG, HOUSING, LH ELEC	83-3320-1418	1.0
6	23028A024-4	B MINCOM	BRKT-MTG, HOUSING, RH ELEC	83-3320-1419	1.0
7	23028A021-1	A MINCOM	SUPPORT-ANGULAR, CAB, CONSOLE LH	83-3340-0504	1.0
8	23028A021-2	A MINCOM	SUPPORT-ANGULAR, CAB, CONSOLE, RH	83-3340-0505	1.0
9	23028A038	A MINCOM	PANEL-FILLER, SUPPORT, HOUSING	83-3360-0933	1.0
10	MS35649-62	MIL STD	NUT-HEX, PLAIN, 6-32 X .313 WD	83-9260-2005	14.0
11	MS35649-82	MIL STD	NUT-HEX, PLAIN, 8-32 X .344 WD	83-9260-2006	8.0
12	MS35206-229	MIL STD	SCREW-MACH, PAN HD, 6-32 X 7/16	83-9260-4532	2.0
13			SCR-MACH, F HD, 8-32 X 1/2	83-9260-6532	4.0
14	MS24693-S28	MIL STD	SCREW-MACH, FH, 6-32 X .500	83-9260-6579	12.0
15	MS35338-42	MIL STD	WASHER-LOCK, SPLIT, HELICAL, #8	83-9261-4020	8.0
16	AN960-6L	A & N STD	WASHER-FLAT, LIGHT SERIES, #6	83-9261-4041	14.0
17	AN960-8L	A & N STD	WASHER-FLAT, LIGHT SERIES, #8	83-9261-4042	8.0
18	MS35338-41	MIL STD	WASHER-LOCK, SPLIT, #6	83-9261-4305	14.0
19	A6732-5-02	ESNA	NUT-NON LKG, PL, 10-32	83-9260-0059	8.0
20			SCREW-WOOD, RD HD, #10 X 1.00LG	83-9262-0559	10.0
21			SCREW-WOOD, RD HD, #6 X 7/8	83-9262-0555	3.0
22	AN505-8R9	A & N STD	SCREW-MACH, FH, 8-32 X 9/16	83-9260-6533	4.0

TITLE CABLE ASSY-POWER,REPRODUCER

CATALOG NO. 83-4570-0420

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
J10	1-480273-0	AMP INC	SHELL-CONN,RECT,.565 WDX.65	83-1610-0923	1.0
P1	78S8	AMPHENDL	SOCKET-TUBE, 8 CONTACT	83-1620-0188	1.0
P4	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
1	60510-4	AMP INC	CONTACT-ELEC,SOC,18-22GA SIZE	83-1610-0927	4.0
2	60511-4-LP	AMP INC	CONTACT-ELEC,PIN, .084 DIA	83-1610-0925	5.0
3	3-24	AMPHENDL	CLAMP-CABLE,SOCKET MTG,.375MCE	83-1650-0483	1.0
4	3025-070-5/16ID	3M	TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
5			WIRE-TYPE B 16GA RED NYLON JAC	83-7910-0050	AR
6		NATL WIRE CO	WIRE-PVC,TYPE B,16 GA,GRAY/BLK	83-7910-0047	AR
7	NATL WIRE&CABLE		WIRE-PVC TYPE B NYLON 20GA BRN	83-7910-0037	AR
8		SURPRENANT	WIRE-TYPE B,20 GA RED-WHITE	83-7910-0053	AR
9		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
10		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR

P A R T S L I S T

PL 23028A350

REV A

TITLE CABLE ASSY-PWR, FILM SYNC

CATALOG NO. 83-4570-0466

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MEGR PART NO.	MEGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
P4	1-480278-0	AMP INC	SHELL-CONN,RECT,12 POSITIONS	83-1610-0931	1.0
P110	1-480324-0	AMP INC	SHELL-CONN,RECT, 15POSITION	83-1610-0933	1.0
1	60511-4-LP	AMP INC	CONTACT-FLEC,PIN, .084 DIA	83-1610-0925	20.0
2	GSR134C	THOM & BETTS	FERRULE-RE CABLE GND .134ID	83-9690-0020	2.0
3	GSC194C	THOMAS&BETTS	FERRULE-RE CABLE GROUNDING	83-9690-0118	2.0
4		NATL WIRE	WIRE-PVC,TYPE R, 22GA YELLOW	83-7910-0040	AR
5		NATL WIRE	WIRE-TYPE R,22GA VID NYLON JKT	83-7910-0041	AR
6		NATL WIRE	WIRE-PVC, TYPE R, 22GA GRAY	83-7910-0042	AR
7		NATL WIRE	WIRE-TYPE R,22GA BLU NYLON JKT	83-7910-0044	AR
8		NATL WIRE	WIRE-TYPE R,22GA BLK NYLON JKT	83-7910-0045	AR
9		NATL WIRE	WIRE-TYPE R,22GA,GRN NYLON JKT	83-7910-0248	AR
10		NATL WIRE	WIRE-TYPE R,22GA RED NYLON JKT	83-7910-0249	AR
11		NATL WIRE	WIRE-TYPE R,22GA,BRN NYLON JKT	83-7910-0251	AR
12	3025-070-5/16ID 3M		TUBING-SCOTCHTITE,CLEAR VINYL	83-7910-0279	AR
13	NH1934N2SJ	NATL WIRE	WIRE-TYPE R,22GA RED/BLU 2 CON	83-7910-0362	AR

P A R T S L I S T

PL 23059A010

REV H

TITLE HOUSING ASSY-AUDIO,SIG ELECT

CATALOG NO. 83-5920-0842

M A T E R I A L R E Q U I R E M E N T S					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C101 CR101,CR102,CR104	MIL CS13AC221 1N4002	MIL STD MOTOROLA	CAP-FXD,TA, 47UF 35V 20% RECT-SI,SEMICON,100PIV, 1 A	83-1510-6085 83-1530-0122	1.0 3.0
DS103	RDL-A1F1-0000	TSTR ELECT	LIGHT-INDICATOR,P2STC,RED	83-1550-2582	1.0
J101	D3F	SWITCHCRAFT	CONN-RECP,ELFC,PML MTG, 3 SOC	83-1610-1105	1.0
J102	D3M	SWITCHCRAFT	CONN-RECP,ELEC,PML MTG, 3 PIN	83-1610-1106	1.0
J103	N-111	SWITCHCRAFT	JACK-TEL,2 CONDUCTOR,INSULATED	83-1610-0885	1.0
J104,J105,J106,J107,J108	MS3102E10SL-3P	MIL STD	CONN-RECP,BOX MTG,3 PIN CONT	83-1610-1510	5.0
J109,J111	1-480273-0	AMP INC	SHELL-COON,RECT,.565 WDX.65	83-1610-0923	2.0
J110	1-480323-0	AMP INC	SHELL-COON,RECT,.650WDX1.280	83-1610-0934	1.0
K101,K102	KHP17D11	POTTR & BRUM	RELAY-4PDT,650 OHM 24VDC 3 AMP	83-1550-3550	2.0
Q101	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	1.0
R100	302163	CTS OF BERNE	RES-VAR, WW, 2K OHM 5W 5%	83-1520-1299	1.0
R101	0A781-7356	MINCOM SPEC	RES-FXD,FILM,620 OHM,1/2W,2% S	83-1520-7356	1.0
R102,R118	0A781-7202	MINCOM SPEC	RES-FXD,FILM,150 OHM,1/2W,2% S	83-1520-7202	2.0
R104,R105	0A781-7365	MINCOM SPEC	RES-FXD,FILM,5.6K OHM,1/2W,2% S	83-1520-7365	2.0
R106	301073	CTS OF BERNE	RES-VAR, WW, 10K OHM 5W 5%	83-1520-1336	1.0
R108	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R110	LITTLE DEVIL	OHMITE	RES-FXD,COMP,33 OHM,1 W, 5%	83-9520-4120	1.0
R114	LITTLE DEVIL	OHMITE	RES-FXD,COMP,270 OHM 1W 5%	83-9520-4091	1.0
R115,R117	LITTLE DEVIL	OHMITE	RES-FXD,COMP,390 OHM 1W 5%	83-9520-4142	2.0
R116	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
R119	0A781-7359	MINCOM SPEC	RES-FXD,FILM,1.2K OHM,1/2W,2% S	83-1520-7359	1.0
R120	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
S101	SEE DESC	DIALCO	SWITCH-PB, 922-1141-1572-523	83-1550-5227	1.0
S102	SEE DESC	DIALCO	SWITCH-PB, 922-1141-1573-523	83-1550-5226	1.0
S103,S104	PA-022-1449	CENTRALAB	SWITCH-ROT,PHEN,115VAC 230 MA	83-1550-5225	2.0
S105	SS43	STACKPOLE	SWITCH-SLIDE,SP 3 POSITION	83-1550-5228	1.0
S106	SS50	STACKPOLE	SWITCH-SLIDE,DPDT	83-1550-5229	1.0
T101	23059A025	B MINCOM	XMFR-AUDIO INPUT,SIGNAL ELECT	83-3540-1122	1.0
T102	23059A029	A MINCOM	XMFR-AUDIO OUTPUT,SIGNAL ELECT	83-3540-1109	1.0
TB1,TB2	4-01769	ALCON	TERM BD-5 POS,.325 WD X1.312LG	83-1640-0625	2.0
1	23059A001-1	B MINCOM	PLATE-HSG MTG,RH,SIG ELECT	83-3320-1128	1.0
2	23059A001-2	B MINCOM	PLATE-MTG,HSNG,RH,SIGNAL ELECT	83-3320-1129	1.0
3	23059A006-1	D MINCOM	PLATE-PANEL MTG,LH,SIG ELECT	83-3320-1130	2.0

P A R T S L I S T

PL 23059A010

REV H

TITLE HOUSING ASSY-AUDIO,SIG ELECT

CATALOG NO. 83-5920-0842

----- M A T E R I A L R E Q U I R E M E N T S -----

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
5		23059A004	B MINCOM	SUPPORT-ROD,GUIDE,P.C. BOARD	83-3340-0389	4.0
6		23059A024	E MINCOM	BRACKET-XMFR MTG,SIGNAL ELECT	83-3320-1133	2.0
7		23059A026	B MINCOM	BRACKET-SLOTTED,DOOR STOP	83-3320-1127	1.0
8		23059A003	D MINCOM	PANEL-FRONT,SIGNAL ELECTRONICS	83-3360-0731	1.0
9		23059A014-3	B MINCOM	HINGE-BUTT,CHASSIS HALF	83-3270-0479	1.0
10		23059A027	B MINCOM	ROD-DOOR STOP,SIGNAL ELECT	83-3280-0418	1.0
11		23059A013-1	B MINCOM	HINGE-BUTT,DOOR LEAF,LH	83-3270-0475	1.0
12		23059A013-2	B MINCOM	HINGE-BUTT,DOOR LEAF,RH	83-3270-0476	1.0
13		R102-125	SCANBE	SPACER-GUIDE,P.C. BD,.125 THK	83-1350-0385	8.0
14		00000A614-7	G MINCOM	SPACER-P.C. RD,CHAN,.500 LG	83-3350-0236	16.0
15		00000A614-9	G MINCOM	SPACER-P.C. RD,CHAN,.625 LG	83-3350-0238	16.0
16		00000A614-21	G MINCOM	SPACER-P.C. RD,CHAN,2.941 LG	83-3350-0386	4.0
17		00000A614-22	G MINCOM	SPACER-P.C. RD,CHAN,3.190 LG	83-3350-0387	8.0
18		23059A002	D MINCOM	PANEL-CONNECTOR MTG,SIG ELECT	83-3360-0730	1.0
19		23059A007	B MINCOM	PANEL-FRONT,COMPONENT MTG	83-3360-0729	1.0
20		091-0024-000	VIKING	INSERT-POLARIZING,CONN,.300 LG	83-1610-0760	8.0
23		23059A028	B MINCOM	SPRING-DOOR CATCH,SIG ELECT	83-3280-0447	1.0
31		KL701	RAYTHEON	LOCK-DIAL,KNOB,RD,1.00 DIA	83-1270-0388	2.0
32		DS70-1-2	RAYTHEON	KNOB-CONTROL,RD,UNSKIRTED	83-1270-0486	2.0
33		DS70-3-2	RAYTHEON	KNOB-CONTROL,RD,SKIRTED	83-1270-0487	2.0
34		327	GENERAL ELEC	LAMP-INCANDESCENT,.04 AMP	83-1550-2506	3.0
35		R-301-51A	SCANBE	GUIDE-P.C. BD,5.287 LG	83-1340-0393	20.0
37		9KH1	POT.BRUM	SOCKET-RELAY,14CONT	83-1620-0108	2.0
38		2VK22S/1-2	VIKING	CONN-P.C.,ELEC,PIERCD, 22 CON	83-1610-0845	8.0
44		60510-4	AMP INC	CONTACT-ELEC,SOC,18-22GA SIZE	83-1610-0927	27.0
48		MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	38.0
49		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	2.0
50		MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	14.0
51		MS35190-223	MIL STD	SCREW-MACH,FH,4-40 X 3/8	83-9260-6504	4.0
52				SCR-MACH,F HD,8-32 X .500 LG	83-9260-6610	8.0
53				NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	24.0
54				NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	20.0
55				WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	42.0
56				WASHER-FLAT,SM PATT,#6	83-9261-4013	30.0
57		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	42.0
58		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	30.0
59		SE-45 BRASS	UNITED SHOE	EYELET-MET,.121 OD X.169LG	83-7290-0097	4.0
60		23059A051	B MINCOM	LENS-MOLDED,PWR SUP,WITH METER	83-3550-1419	1.0
62		23059A012-1	B MINCOM	LABEL-I.D,NAB & DYNATRACK, LH	83-3550-1573	1.0
63		23059A012-2	B MINCOM	LABEL-I.D,NAB & DYNATRACK, RH	83-3550-1574	1.0
64		00000A769	C MINCOM	LABEL-IDENTIFICATION,MODULE	83-3550-1621	1.0
65		YEC 120	BURNDY	FERRULE-RF CABLE GND,.300 OD	83-9690-0240	18.0




Figure 49. Audio Signal Electronics Housing Assembly

P A R T S L I S T

PL 23059A010

REV H

TITLE HOUSING ASSY-AUDIO,SIG ELECT

CATALOG NO. 83-5920-0842

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
66	YEC-100	BRUNDY	FERRULE-RF CABLE YEL,.270 OD	83-9690-0212	32.0
67		NATIONAL	WIRE,PVC,SHIELDED 24GA 2COND	83-7910-0511	AR
68		NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0052	AR
69	1561-2		WIRE-TYPE MW,22GA BLK NYLN JKT	83-7910-0460	AR
70	1561-3		WIRE-TYPE MW,22GA RED NYLN JKT	83-7910-0461	AR
71	1561-8	ALPHA WIRE	WIRE-TYPE MW,22GA ORNG NYL JKT	83-7910-0462	AR
72	1561-5		WIRE-TYPE MW,22GA YEL NYLN JKT	83-7910-0463	AR
73	1561-6	ALPHA WIRE	WIRE-TYPE MW,22GA BLU NYLN JKT	83-7910-0464	AR
74	1561-1	ALPHA WIRE	WIRE-TYPE MW,22GA WHT NYLN JKT	83-7910-0467	AR
75		NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
76		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
77		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
78		NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0043	AR
79		NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR
80		NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
81		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
82		NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
83		NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR
84		SURPRENANT	WIRE-PVC TYPE B, 22 GA,RED-BLK	83-7910-0066	AR
85		SURPRENANT	WIRE-PVC,B NYLON,22GA,YEL-BLK	83-7910-0067	AR
86		SURPRENANT	WIRE-PVC,B NYLON,22GA,GRN-BLK	83-7910-0069	AR
87		SURPRENANT	WIRE-PVC,B NYLON,22GA,BLU-BLK	83-7910-0070	AR
88		NATL WIRE	WIRE-TYPE B,22GA WHT/BLK NYLN	83-7910-0262	AR
89		NATL WIRE	WIRE-TYPE B,22GA ORN/BLK NYLN	83-7910-0297	AR
90		NATL WIRE	WIRE-TYPE B,22GA GRY/BLK NYLN	83-7910-0298	AR
91		NATL WIRE	WIRE-TYPE B,22GA PR/BLK NYLN	83-7910-0299	AR
92		NATL WIRE	WIRE-PVC,B NYLON,22GA,BRN-BLK	83-7910-0300	AR
93			WIRE-TYPE B,22 GA,VIOLET-WHITE	83-7910-0068	AR
94		SURPRENANT	WIRE-PVC,B NYLON,22GA,BLK-WHT	83-7910-0071	AR
95			WIRE-TYPE B,22 GA YELLOW NYLN	83-7910-0259	AR
96		NATL WIRE	WIRE-PVC TYPE B, 22 GA,GRN-WHT	83-7910-0260	AR
97			WIRE TYPE B,22 GA GRAY NYLN	83-7910-0261	AR
98			WIRE-TYPE B,22 GA RED NYLN JKT	83-7910-0264	AR
99			WIRE-TYPE B,22 GA BLU NYLN JKT	83-7910-0288	AR
100			WIRE-TYPE B,22GA BRN NYLN JKT	83-7910-0301	AR
101			WIRE-TYPE B,22 GA ORN NYLN JKT	83-7910-0303	AR
102	MS35206-205	MIL STD	SCREW-MACH, PAN HD,2-56 X 3/8	83-9260-4504	2.0
103			WASHER-FLAT,SM PATT,#2	83-9261-4011	2.0
104	MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	2.0
105			NUT-HEX,SM PATT,2-56 X .156 WD	83-9260-2206	2.0
106	RA853	THUMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	2.0
107	MS35333-42	MIL STD	WASHER-LOCK,FLAT,INT T,#3/8	83-9261-4211	2.0

P A R T S L I S T

PL 23059A010

REV H

TITLE HOUSING ASSY-AUDIO,SIG ELECT

CATALOG NO. 83-5920-0842

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
108	M-2786	ALLEN BRADLY	NUT-HEX,PLAIN,3/8-32 X .500 OD	83-9260-2112	4.0

P A R T S L I S T

PL 23059A020

REV F

TITLE P.C. BD ASSY-BIAS,ERASE

CATALOG NO. 83-4930-1121

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	D1P5D	HOPKINS	CAP-FXD,PAPER, .10UF, 50V,20%	83-1510-4185	1.0
C2	107X002	SPRAGUE	CAP-FXD,TA, 100 UF, 25V, 20%	83-1510-6222	1.0
C3,C20	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
C4,C5	210B1B103J	ELECTRO CUBE	CAP-FXD,PLSTC, .01UF,100V, 5%	83-1510-4192	2.0
C6,C7,C8,C9	TSD-1-20-225	COMP INC	CAP-FXD,TA, 2.2UF 20V 20%	83-1510-6240	4.0
C10,C13,C16	192P10392	SPRAGUE	CAP-FXD,PAPER, .01 UF,200V,10%	83-1510-4414	3.0
C12,C15	TSD3-15-226	COMP INC	CAP-FXD,TA, 22UF 15V 20%	83-1510-6257	2.0
C14,C17	192P33292	SPRAGUE	CAP-FXD,PAPER,.0033UF,200V,10%	83-1510-4405	2.0
C18	WMF1S47	CORNEL-DUBLR	CAP-FXD,PLSTC,.047UF 100V 10%	83-1510-4481	1.0
C19	831-X3R-271K	ERIE	CAP-FXD,CER, 270PF1000V 10%	83-1510-1103	1.0
C21	4610	ARCO	CAP-VAR,MICA,190-900 PF	83-1510-6252	1.0
CR1,CR2,CR3	1N270	HUGHES	DIODE-GE,GEN PUR,100PIV, 60 MA	83-1530-0263	3.0
L1	4631	J.W. MILLER	INDUCTOR-FXD,82UH,250MA	83-1540-0409	1.0
L2	70F333AI	J.W. MILLER	CHOKE-RF,3.3 MH 5 %	83-1540-0410	1.0
Q1,Q2,Q5,Q6	2N3053	R.C.A.	TSTR-SI,NPN, PWR, 60 VCB	83-1530-2180	4.0
Q3,Q4	2N3054	R.C.A.	TSTR-SI,NPN, H PWR, 100 HFE	83-1530-2227	2.0
R1,R14,R17	0A781-7221	MINCOM SPEC	RES-FXD,FILM,100 OHM,1/2W,2% S	83-1520-7221	3.0
R2	0A781-7358	MINCOM SPEC	RES-FXD,FILM,820 OHM,1/2W,2% S	83-1520-7358	1.0
R3,R4	0A781-7175	MINCOM SPEC	RES-FXD,FILM,1K OHM,1/2W,2% S	83-1520-7175	2.0
R5,R27	0A781-7144	MINCOM SPEC	RES-FXD,FILM,15K OHM,1/2W,2% S	83-1520-7144	2.0
R6,R8	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	2.0
R7,R28	0A781-7145	MINCOM SPEC	RES-FXD,FILM,12K OHM,1/2W,2% S	83-1520-7145	2.0
R9,R10	0A781-7355	MINCOM SPEC	RES-FXD,FILM,560 OHM,1/2W,2% S	83-1520-7355	2.0
R11,R12	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	2.0
R13	0A781-7363	MINCOM SPEC	RES-FXD,FILM,3.9K OHM,1/2W,2% S	83-1520-7363	1.0
R15,R18	0A781-7329	MINCOM SPEC	RES-FXD,FILM,22 OHM,1/2W,2% S	83-1520-7329	2.0
R16	0A781-7146	MINCOM SPEC	RES-FXD,FILM,18K OHM,1/2W,2% S	83-1520-7146	1.0
R19,R22	0A781-7331	MINCOM SPEC	RES-FXD,FILM,27 OHM,1/2W,2% S	83-1520-7331	2.0
R20,R21	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	2.0

M23 RRM 2-69

281

P A R T S L I S T

PL 23059A020

REV F

TITLE P.C. BD ASSY-BIAS,ERASE

CATALOG NO. 83-4930-1121

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R23,R24	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	2.0
R25	77PR1K	BECKMAN	RES-VAR,COMP,1K OHM,3/4 W, 10%	83-1520-1211	1.0
R26	0A781-7379	MINCOM SPEC	RES-FXD,FILM,47K OHM,1/2W,2% S	83-1520-7379	1.0
R29	0A781-7325	MINCOM SPEC	RES-FXD,FILM,10 OHM,1/2W,2% S	83-1520-7325	1.0
T1	00000A718	A MINCOM	XMFR-TORROIDAL,ARNOLD CORE	83-3540-1150	1.0
T2,T4,T5	00000A719	A MINCOM	XMFR-TORROIDAL,ARNOLD CORE	83-3540-1151	3.0
T3	00000A720	A MINCOM	XMFR-TORR/IDAL,ARNOLD CORE	83-3540-1152	1.0
TP1	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	1.0
1	23059A021	E MINCOM	P.C. BD-BIAS,ERASE	83-3640-0666	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	00000A734-1	B MINCOM	LABEL-IDENT,P.C. BD,MARKED *1*	83-3550-1446	1.0
5	23059A016	A MINCOM	BRACKET-COMPONENT MTG,SIG ELEC	83-3320-1132	1.0
7	TXBF-032-025B	IERC	HEAT SINK-ELEC COMP,TO-5 CASE	83-9690-0108	2.0
8	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	4.0
9			NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	4.0
10			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	4.0
11	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	4.0
12	#EXE-22-122	THERMAX	WIRE-TYPE C,22GA WHT TEFLN JKT	83-7910-0476	AR
13			WASHER-FLAT,SM PATT,#10	83-9261-4046	1.0

P A R T S L I S T

PL 23059A030

REV D

TITLE P.C.BD ASSY-NAB ERASE COUPLER

CATALOG NO. 83-4930-1117

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	TYPE 311	ARCO	CAP-VAR,MICA,780-2110PF 250V	83-1510-6274	1.0
R3	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	1.0
TP1	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	1.0
1	23059A031	E MINCOM	P.C.BD-NAB ERASE COUPLER	83-3640-0665	1.0
2	30113A018-2	A MINCOM	SHIELD-CIRCUIT BD	83-3650-0387	1.0
3	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
4	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
5	1434	BIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR
6	MS35206-202	MIL STD	SCREW-MACH,PAN HD,2-56 X 3/16	83-9260-4501	4.0
7			WASHER-FLAT,GENERAL PURPOSE,#2	83-9261-4040	4.0
8	MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	4.0
9	00000A734-2	B MINCOM	LABEL-IDENT,P.C. BD,*3N*	83-3550-1447	1.0
10	NAS620-416	NAS STD	WASHER-FLAT,SM PATT,#1/4	83-9261-4043	2.0

TITLE P.C. BD ASSY-RECORD,NAB

CATALOG NO. 83-4930-1214

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R13	0A781-7383	MINCOM SPEC	RES-FXD,FILM,68K OHM,1/2W,2% S	83-1520-7383	1.0
R15	0A781-7201	MINCOM SPEC	RES-FXD,FILM,1.8K OHM,1/2W,2% S	83-1520-7201	1.0
R16,R29	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	2.0
R17	0A781-7359	MINCOM SPEC	RES-FXD,FILM,1.2K OHM,1/2W,2% S	83-1520-7359	1.0
R18	0A781-7342	MINCOM SPEC	RES-FXD,FILM,82 OHM,1/2W,2% S	83-1520-7342	1.0
R19	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	1.0
R20	77PR100	BECKMAN	RES-VAR,COMP,100 OHM,3/4 W,10%	83-1520-1153	1.0
R21	0A781-7333	MINCOM SPEC	RES-FXD,FILM,33 OHM,1/2W,2% S	83-1520-7333	1.0
R22	0A781-7345	MINCOM SPEC	RES-FXD,FILM,180 OHM,1/2W,2% S	83-1520-7345	1.0
R23	0A781-7379	MINCOM SPEC	RES-FXD,FILM,47K OHM,1/2W,2% S	83-1520-7379	1.0
R26	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R27	0A781-7220	MINCOM SPEC	RES-FXD,FILM,220 OHM,1/2W,2% S	83-1520-7220	1.0
R28	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R30	77PR10K	BECKMAN	RES-VAR,COMP,10K OHM,3/4 W,10%	83-1520-1213	1.0
S1	TYPE G350-PC	CONTL WIRT	SWITCH-SLIDE, DPDT,125V 3AMP	83-1550-5212	1.0
TP1	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	1.0
TP2	3-582118-0	AMP INC	JACK-TEST,.156WD X .230 HT,BLK	83-1610-0765	1.0
1	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
2	23059A016	A MINCOM	BRACKET-COMPONENT MTG,SIG ELEC	83-3320-1132	2.0
3	00000A734-3	B MINCOM	LABEL-IDENT,P.C.BD, *4*	83-3550-1448	1.0
4	23059B041	F MINCOM	P.C. BD-RECORD,NAB	83-3640-0729	1.0
5	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
6	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	3.0
7	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	1.0
8	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
9			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0
10	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
12	1434	BIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR

P A R T S L I S T

PL 230598040

REV F

TITLE P.C. BD ASSY-RECORD,NAB

CATALOG NO. 83-4930-1214



- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1,C10,C14	TSD3-15-226	COMP INC	CAP-FXD,TA, 22UF 15V 20%	83-1510-6257	3.0
C2	112A18334J	ELECTRO CUBE	CAP-FXD,PAPER, .33UF 100V 5%	83-1510-4301	1.0
C3	112A18683K	ELECTRO CUBE	CAP-FXD,PAPER,.068 UF,100V,10%	83-1510-4332	1.0
C4	112A1A104J	ELECTRO-CUBE	CAP-FXD,PAPER, .10UF 50V 5%	83-1510-4310	1.0
C5	17W1-203J	JEDCO	CAP-FXD,PLSTC, .02UF,100V, 5%	83-1510-4191	1.0
C7	TSD-1-20-225	COMP INC	CAP-FXD,TA, 2.2UF 20V 20%	83-1510-6240	1.0
C8	TYPE E3FR	MIDWEC	CAP-FXD,PLSTC,.0033UF 100V 5%	83-1510-4445	1.0
C9	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C11	TSD5-20-476	COMP INC	CAP-FXD,TA, 47UF 20V 20%	83-1510-6199	1.0
C12	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C13	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	1.0
C15	TSD1-20-475	COMP INC	CAP-FXD,TA, 4.7UF 20V 20%	83-1510-6196	1.0
C17	210B1C102K	ELECTRO CUBE	CAP-FXD,PLSTC,.001 UF,200V,10%	83-1510-4296	1.0
C18,C19	464	ARCO	CAP-VAR,MICA,25 MMF-280 MMF	83-1510-6277	2.0
K1	701-3	ELEC-TROL	RELAY-SPDT, 2K OHM 24VDC	83-1550-3620	1.0
Q1,Q3,Q7	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR; 25 VCB	83-1530-2230	3.0
Q2	2N3684		TSTR-SI,N-CHAN,FLD EFFECT 50MA	83-1530-2244	1.0
Q4	2N3405	G.E.	TSTR-SI,NPN,GEN PUR,50VCE	83-1530-2232	1.0
Q5,Q6	2N2614		TSTR-GE,PNP, SIGNAL, 40VCB	83-1530-2233	2.0
R1	0A781-7397	MINCOM SPEC	RES-FXD,FILM,390K OHM,1/2W,2% S	83-1520-7397	1.0
R2,R25	0A781-7372	MINCOM SPEC	RES-FXD,FILM,22K OHM,1/2W,2% S	83-1520-7372	2.0
R3	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	1.0
R4	0A781-7175	MINCOM SPEC	RES-FXD,FILM,1K OHM,1/2W,2% S	83-1520-7175	1.0
R5	0A781-7174	MINCOM SPEC	RES-FXD,FILM,390 OHM,1/2W,2% S	83-1520-7174	1.0
R6,R24	0A781-7393	MINCOM	RES-FXD,FILM,270K OHM,1/2W,2% S	83-1520-7393	2.0
R7	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	1.0
R8	0A781-7387	MINCOM SPEC	RES-FXD,FILM,100K OHM,1/2W,2% S	83-1520-7387	1.0
R9,R14	0A781-7369	MINCOM SPEC	RES-FXD,FILM,8.2K OHM,1/2W,2% S	83-1520-7369	2.0
R10	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
R12	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	1.0

TITLE PWR SUP ASSY-SIG ELECT,W/METER

CATALOG NO. 83-5920-0822

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	HC5020A	MALLORY	CAP-FXD,ELECT,2000 UF,50 LVDC	83-1510-2075	1.0
M1	23059A052	C MINCON	METER-MICROVOLT,ILLUM DIAL	83-3550-3405	1.0
Q1	2N3055	R.C.A.	TSTR-SI,MPN, PUR, 100 VCB	83-1530-2157	1.0
T1	23009A004	A MINCON	XFER-PWR,48-62 CPS.115V 100	83-3540-1141	1.0
1	CMC-28A	SPRAGUE	RETAINER-CAP MTC,RING TYPE	83-1650-0140	1.0
2	BBT0-3-62	BRUSH-BERYLM	PAD-TSTR,1.05 MD X 1.563 LG	83-1690-0187	1.0
3	23059A017	MINCON	CHAS-COMP MTC,SIG ELECTRONICS	83-3310-0052	1.0
4	23059A011	D MINCON	PLATE-MTC,METER MODULE	83-3320-1126	1.0
5	23059A008	MINCON	BRKT-METER MTC,SIG ELECTRONICS	83-3320-1121	1.0
6	23059A009	MINCON	SPACER-METER PANEL,SIG ELEC	83-3350-0344	1.0
7	23059A055	F MINCON	P.C. BD ASSY-PWR SUP,SIG ELEC	83-4930-1014	1.0
8			NUT-HEX,SI PATT,6-32 X .250 MD	83-9200-2202	7.0
9	MS35206-227	MIL STD	SCREW-WACH,PAN HD,6-32 X 5/16	83-9200-4530	25.0
10			SCREW-WACH,PAN HD,6-32 X 9/16	83-9200-4534	2.0
11			WASHER-FLAT,SI PATT,#6	83-9261-4012	25.0
12	MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	25.0
13	7856	WALSCO	INSULATOR-WASHER,.140 ID	83-9630-0038	2.0
14	1414-6	HP SMITH	TERM STRIP-GRDING,#6 SCREW MTC	83-9630-0066	1.0



DRAWING NO. 23059A050

REV B

Figure 50. Signal Electronics Power Supply Assembly with Meter

P A R T S L I S T

PL 23059A055

REV F

TITLE P.C. RD ASSY-PWR SUP,SIG FLEEC

CATALOG NO. 83-4930-1014

----- P A T E R N I A L R E F O R I P P E F E M T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - DESGR PART NO.	AFGR MADE	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C2,C4	MIL CS13AC221	MIL STD	CAP-EXD,TA, 470F 35V 20V	83-1510-6085	2.0
C3	TYPE RPD	AEROMOX	CAP-EXD,CER, 1000PF 1000V GVM	83-1510-1024	1.0
CR1,CR2,CR3,CR4,CR5	1M4002	ROTOROLA	RECT-SI,SEMI COND,100PIV, 1 A	83-1530-0122	5.0
CR6	1M754A	TEXAS INST	DIODE-SI, ZENER, 6.8V 400 MW	83-1530-0097	1.0
F1	31201.5	LITTLEFUSE	FUSE-3AG-1.5 AMP.	83-7550-8009	1.0
Q2,Q3,Q4	2N3417	G.E.	TSTR-SILICON,NPN,SMALL SIGNAL	83-1530-2236	3.0
P1	BWH	INTIMATEL RES	RESISTOR-1/4 1 OHM, 1W, 10%	83-1520-8261	1.0
P2	4334	OHMITE	RES-EXD,M/W,1.5 OHM 3 W 5 %	83-1520-7771	1.0
P3	0A781-7148	MINGCON SPEC	RES-EXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	1.0
P4,P6	0A781-7147	MINGCON SPEC	RES-EXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	2.0
P5	0A781-7350	MINGCON SPEC	RES-EXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
P7	0A781-7372	MINGCON SPEC	RES-EXD,FILM,22K OHM,1/2W,2% S	83-1520-7372	1.0
P8	0A781-7368	MINGCON SPEC	RES-EXD,FILM,7.5K OHM,1/2W,2% S	83-1520-7368	1.0
P11	LITTLE DEVIL	OHMITE	RES-EXD,COMP,270 OHM 1W 5%	83-9520-4091	1.0
P12	RC32GE2315	MIL-R-110/6	RESISTOR-CARBON, 330 OHM 1W-5%	83-9520-4140	1.0
P13	LITTLE DEVIL	OHMITE	RESISTOR-CAR, 220 OHM-1W-5%	83-9520-4137	1.0
1	101003	LITTLEFUSE	CLIP-FUSE,LUG,PHOSPHOR BRONZE	83-1620-0190	2.0
2	23059A056	MINGCON	P.C.RD-POWER SUPPLY	83-3640-0597	1.0
3	SE-44 BRASS	UNITED SHOE	FYFLET-BRASS,FLANGED,.112X.121	83-7290-0091	2.0
4	7717-2	THERMALLOY	PAD-TSTR, IMLINE, 3 LEADS	83-9690-0191	3.0
5	1434	RIERBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR

P A R T S L I S T

PL 23059A060

REV G

TITLE P.C. BD ASSY-LNE AMP,SIG ELECT

CATALOG NO. 83-4930-1091

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	1.0
C2,C6	TSD4-20-226	COMP INC	CAP-FXD,TA, 22UF 20V 20%	83-1510-6203	2.0
C3	610B1B103J	ELECTRO CUBE	CAP-FXD,POLYCARBON,.01UF,100V	83-1510-4227	1.0
C4,C5	BR150-50	CORNELL DUBL	CAP-FXD,ELECT, 150UF 50V	83-1510-2212	2.0
C7	TSD5-20-476	COMP INC	CAP-FXD,TA, 47UF 20V 20%	83-1510-6199	1.0
C8	DM15F500J	ARCO	CAP-FXD,MICA, 50PF 500V 5%	83-1510-5148	1.0
C9	TSD1-35-105	COMP INC	CAP-FXD,TA, 1UF 35V 20%	83-1510-6208	1.0
C10	TSD5-10-157	COMP INC	CAP-FXD,TA, 150UF 10V 20%	83-1510-6245	1.0
C11,C12	TYPE BPD	AEROVOX	CAP-FXD,CER, 1000PF 1000V GMV	83-1510-1024	2.0
C13	DM15F201J	ARCO	CAP-FXD,MICA, 200PF 500V 5%	83-1510-5214	1.0
C14	BR500-25	CORNELL DUBL	CAP-FXD,ELECT, 500UF 25V	83-1510-2044	1.0
C15	P222MC	HOPKINS	CAP-FXD,PLSTC, .22UF 200V 5%	83-1510-4167	1.0
CR1,CR2,CR3,CR4,CR5,CR6,	1N4002	MOTOROLA	RECT-SI,SEMICON,100PIV, 1 A	83-1530-0122	7.0
CR7					
Q1,Q2,Q3	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	3.0
Q4	2N3638	FAIRCHILD	TSTR-SI,PNP, SW, 25 VCB	83-1530-2155	1.0
Q5,Q6	2N3054	R.C.A.	TSTR-SI,NPN, H PWR, 100 HFE	83-1530-2227	2.0
R1	0A781-7362	MINCOM SPEC	RES-FXD,FILM,3.6K OHM,1/2W,2% S	83-1520-7362	1.0
R2,R17,R21	0A781-7175	MINCOM SPEC	RES-FXD,FILM,1K OHM,1/2W,2% S	83-1520-7175	3.0
R3	0A781-7368	MINCOM SPEC	RES-FXD,FILM,7.5K OHM,1/2W,2% S	83-1520-7368	1.0
R4	77PR1K	BECKMAN	RES-VAR,COMP,1K OHM,3/4 W, 10%	83-1520-1211	1.0
R5,R8,R15,R22	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	4.0
R6	,LITTLE DEVIL	OHMITE	RES-FXD, COMP, 820KOHM 1/2W 5	83-9520-3218	1.0
R7	0A781-7398	MINCOM SPEC	RES-FXD,FILM,430K OHM,1/2W,2% S	83-1520-7398	1.0
R9	0A781-7359	MINCOM SPEC	RES-FXD,FILM,1.2K OHM,1/2W,2% S	83-1520-7359	1.0
R10,R12	0A781-7221	MINCOM SPEC	RES-FXD,FILM,100 OHM,1/2W,2% S	83-1520-7221	2.0
R11	0A781-7346	MINCOM SPEC	RES-FXD,FILM,200 OHM,1/2W,2% S	83-1520-7346	1.0
R13	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	1.0

P A R T S L I S T

PL 23059A060

REV G

TITLE P.C. BD ASSY-LNE AMP,SIG ELECT

CATALOG NO. 83-4930-1091

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R14	0A781-7263	MINCOM SPEC	RES-FXD,FILM,2K OHM,1/2W,2% S	83-1520-7263	1.0
R16	0A781-7219	MINCOM SPEC	RES-FXD,FILM,3K OHM,1/2W,2% S	83-1520-7219	1.0
R18	0A781-7344	MINCOM SPEC	RES-FXD,FILM,120 OHM,1/2W,2% S	83-1520-7344	1.0
R19,R20	0A781-7357	MINCOM SPEC	RES-FXD,FILM,750 OHM,1/2W,2% S	83-1520-7357	2.0
R23	0A781-7329	MINCOM SPEC	RES-FXD,FILM,22 OHM,1/2W,2% S	83-1520-7329	1.0
R24	LITTLE DEVIL	OHMITE	RES-FXD,COMP,2.7 OHM 1/2W 5%	83-9520-3258	1.0
R25	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
S1,S2	TYPE G350-PC	CONTL WIRT	SWITCH-SLIDE, DPDT,125V 3AMP	83-1550-5212	2.0
TP1	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	1.0
1	23059A061	F MINCOM	P.C. BD-LINE AMP,SIGNAL ELECT	83-3640-0668	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	00000A734-4	B MINCOM	LABEL-IDENT,P.C. BD,*6*	83-3550-1449	1.0
6	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	4.0
7			NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	4.0
8			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	4.0
9	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	4.0
10	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	3.0

P A R T S L I S T

PL 23059B090-1

REV A

TITLE P.C.BD ASSY-PREAMP, OVERDUB 7.5/15

CATALOG NO. 83-4930-2180

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFR PART NO.	MFR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1,C6	TSD4-20-226	COMP INC	CAP-FXD,TA, 22UF 20V 20%	83-1510-6203	2.0
C2	DM15F271J	ARCO	CAP-FXD,MICA, 270PF 500V 5%	83-1510-5096	1.0
C3	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C4	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C5	E3XFR	MIDWEC	CAP-FXD,PLSTC, .010UF 100V 5%	83-1510-4449	1.0
C7,C8	TYPE E3FR	MIDWEC	CAP-FXD, PLS .0068UF 100V 5%	83-1510-4447	2.0
C9,C10	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
C11	DM15F501J	ARCO	CAP-FXD,MICA, 500PF 500V 5%	83-1510-5120	1.0
K1	701-3	ELEC-TROL	RELAY-SPDT, 2K OHM 24VDC	83-1550-3620	1.0
K2	201-3	ELECTROL	RELAY-SPST, 2K OHM 24 V DC	83-1550-3621	1.0
L1	70F333AI	J.W. MILLER	CHOKERF,3.3 MH 5 %	83-1540-0410	1.0
Q1,Q2,Q3,Q4,Q5	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	5.0
R1,R5	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 1M OHM 1/2W 5%	83-9520-3220	2.0
R2	0A781-7344	MINCOM SPEC	RES-FXD,FILM,120 OHM,1/2W,2% S	83-1520-7344	1.0
R3	0A781-7393	MINCOM	RES-FXD,FILM,270K OHM,1/2W,2% S	83-1520-7393	1.0
R4	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R6,R25	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	2.0
R7,R18,R21	0A781-7389	MINCOM SPEC	RES-FXD,FILM,180K OHM,1/2W,2% S	83-1520-7389	3.0
R8	0A781-7174	MINCOM SPEC	RES-FXD,FILM,390 OHM,1/2W,2% S	83-1520-7174	1.0
R9	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R10	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	1.0
R11,R12,R13,R14,R15	0A781-7201	MINCOM SPEC	RES-FXD,FILM,1.8K OHM,1/2W,2% S	83-1520-7201	5.0
R16	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	1.0
R17	79P R5K	BECKMAN	RES-VAR,CER, 5 K OHM,3/4W,10%	83-1520-1420	1.0
R19,R22	79P R1MEG	BECKMAN	RES-VAR, FILM, 1 MEG OHM	83-1520-1421	2.0
R20,R23	79P R20K	BECKMAN	RES-VAR,FILM, 20 K OHM	83-1520-1422	2.0
R24	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
R26	0A781-7217	MINCOM SPEC	RES-FXD,FILM,680 OHM,1/2W,2% S	83-1520-7218	1.0
T1	TR-145 RV-35845	REYER XMFR	XMFR-AF,2.0 OHM PRIM-95 OHM	83-1540-1284	1.0
1	23059B091	D MINCOM	PC BD-PREAMP, OVERDUB	83-3640-1507	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	5.0
5	00000A734-7	B MINCOM	LABEL-IDENT,P.C. BD,*7 9*	83-3550-1452	1.0
6	23059A092	MINCOM	BRKT-COMP,P.C.BD,PREAMP	83-3320-1974	1.0

P A R T S L I S T

PL 23059B090-2

REV A

TITLE PC BD ASSY-PREAMP,OVERDUB15/30

CATALOG NO. 83-4930-2511

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1,C6	TSD4-20-226	COMP INC	CAP-FXD,TA, 22UF 20V 20%	83-1510-6203	2.0
C2	DM15F271J	ARCO	CAP-FXD,MICA, 270PF 500V 5%	83-1510-5096	1.0
C3	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C4	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C5	E3XFR	MIDWEC	CAP-FXD,PLSTC, .010UF 100V 5%	83-1510-4449	1.0
C7,C8	TYPE E3FR	MIDWEC	CAP-FXD, PLS .0068UF 100V 5%	83-1510-4447	2.0
C9,C10	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
C11	DM15F501J	ARCO	CAP-FXD,MICA, 500PF 500V 5%	83-1510-5120	1.0
K1	701-3	ELEC-TROL	RELAY-SPDT, 2K OHM 24VDC	83-1550-3620	1.0
K2	201-3	ELECTROL	RELAY-SPST, 2K OHM 24 V DC	83-1550-3621	1.0
L1	70F333AI	J.W. MILLER	CHOKERF,3.3 MH 5 %	83-1540-0410	1.0
Q1,Q2,Q3,Q4,Q5	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	5.0
R1,R5	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 1M OHM 1/2W 5%	83-9520-3220	2.0
R2	0A781-7344	MINCOM SPEC	RES-FXD,FILM,120 OHM,1/2W,2% S	83-1520-7344	1.0
R3	0A781-7393	MINCOM	RES-FXD,FILM,270K OHM,1/2W,2% S	83-1520-7393	1.0
R4	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R6,R25	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	2.0
R7,R18,R21	0A781-7389	MINCOM SPEC	RES-FXD,FILM,180K OHM,1/2W,2% S	83-1520-7389	3.0
R8	0A781-7174	MINCOM SPEC	RES-FXD,FILM,390 OHM,1/2W,2% S	83-1520-7174	1.0
R9	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R10	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	1.0
R11,R12,R15	0A781-7201	MINCOM SPEC	RES-FXD,FILM,1.8K OHM,1/2W,2% S	83-1520-7201	3.0
R13,R14	0A781-7264	MINCOM SPEC	RES-FXD,FILM,910 OHM,1/2W,2% S	83-1520-7264	2.0
R16	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	1.0
R17	79P R5K	BECKMAN	RES-VAR,CER, 5 K OHM,3/4W,10%	83-1520-1420	1.0
R19,R22	79P R1MEG	BECKMAN	RES-VAR, FILM, 1 MEG OHM	83-1520-1421	2.0
R20,R23	79P R20K	BECKMAN	RES-VAR,FILM, 20 K OHM	83-1520-1422	2.0
R24	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0

P A R T S L I S T

PL 23059B090-2

REV A

TITLE PC BD ASSY-PREAMP,OVERDUB15/30

CATALOG NO. 83-4930-2511

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R26	0A781-7217	MINCOM SPEC	RES-FXD,FILM,680 OHM,1/2W,2% S	83-1520-7218	1.0
T1	TR-145 BV-35845	BEYER XMFR	XMFR-AF,2.0 OHM PRIM-95 OHM	83-1540-1284	1.0
1	23059B091	D MINCOM	PC BD-PREAMP, OVERDUB	83-3640-1507	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	5.0
6	23059A092	MINCOM	BRKT-COMP,P.C.BD,PREAMP	83-3320-1974	1.0

P A R T S L I S T

PL 23059A110

REV A

TITLE P.C. BD ASSY-EXTENDER

CATALOG NO. 83-4930-1746

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23059A111	B MINCOM	P.C. BD-EXTENDER	83-3640-1139	1.0
2	2VK22S/1-2	VIKING	CUMM-P.C.,ELEC,PIERCE, 22 GR	83-1610-0845	1.0
3	MS35206-217	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/2	83-9260-4517	2.0
4			WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	2.0
5	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,64	83-9261-4303	2.0
6	1434	PIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR
7	TFT-200/22	ALPHA WIRE	TUBING-TEFLON, 22,.027 ID,PAT	83-7910-0388	AR

TITLE P.C. BD ASSY-DYNATRACK,RECORD

CATALOG NO. 83-4930-1006

M A T E R I A L R E Q U I R E M E N T S					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	3.0
C1	TSD-1-20-225	COMP INC	CAP-FXD,TA, 2.2UF 20V 20%	83-1510-6240	1.0
C2,C4,C7,C9	TSD3-15-226	COMP INC	CAP-FXD,TA, 22UF 15V 20%	83-1510-6257	4.0
C3	TSD5-10-157	COMP INC	CAP-FXD,TA, 150UF 10V 20%	83-1510-6245	1.0
C5,C11	112A1C223J	ELECTRO CUBE	CAP-FXD,PAPER, .022UF 200V 5%	83-1510-4475	2.0
C6,C10	112A1A104J	ELECTRO-CUBE	CAP-FXD,PAPER, .10UF 50V 5%	83-1510-4310	2.0
C8	DM15F501J	ARCO	CAP-FXD,MICA, 500PF 500V 5%	83-1510-5120	1.0
C12,C13	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
C14	TSD5-20-476	COMP INC	CAP-FXD,TA, 47UF 20V 20%	83-1510-6199	1.0
C15	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C16	192P15392	SPRAGUE	CAP-FXD,PAPER, .015UF,200V,10%	83-1510-4416	1.0
C18	WMF1S47	CORN-L-DUBLR	CAP-FXD,PLSTC,.047UF 100V 10%	83-1510-4481	1.0
C19	4610	ARCO	CAP-VAR,MICA,190-900 PF	83-1510-6252	1.0
CR1,CR2	1N270	HUGHES	DIODE-GE,GEN PUR,100PIV, 60 MA	83-1530-0263	2.0
L1,L2	70F333AI	J.W. MILLER	CHOKE-RF,3.3 MH 5 %	83-1540-0410	2.0
Q1	2N3684		TSTR-SI,N-CHAN,FLD EFFECT 50MA	83-1530-2244	1.0
Q2,Q3,Q4	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	3.0
Q5	2N3405	G.E.	TSTR-SI,NPN,GEN PUR,50VCE	83-1530-2232	1.0
Q6,Q7	2N2614		TSTR-GE,PNP, SIGNAL, 40VCB	83-1530-2233	2.0
R1,R25	0A781-7379	MINCOM SPEC	RES-FXD,FILM,47K OHM,1/2W,2% S	83-1520-7379	2.0
R2	0A781-7369	MINCOM SPEC	RES-FXD,FILM,8.2K OHM,1/2W,2% S	83-1520-7369	1.0
R3	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
R4,R28,R32	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	3.0
R5	0A781-7387	MINCOM SPEC	RES-FXD,FILM,100K OHM,1/2W,2% S	83-1520-7387	1.0
R6	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R7	0A781-7349	MINCOM SPEC	RES-FXD,FILM,300 OHM,1/2W,2% S	83-1520-7349	1.0
R8,R29,R30	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2% S	83-1520-7147	3.0
R9,R13	0A781-7354	MINCOM SPEC	RES-FXD,FILM,510 OHM,1/2W,2% S	83-1520-7354	2.0
R10	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	1.0
R11	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	1.0

P A R T S L I S T

PL 23059A130

REV D

TITLE P.C. BD ASSY-DYNATRACK,RECORD

CATALOG NO. 83-4930-1006

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R12,R19	0A781-7359	MINCOM SPEC	RES-FXD,FILM,1.2K OHM,1/2W,2%S	83-1520-7359	2.0
R14	0A781-7349	MINCOM SPEC	RES-FXD,FILM,300 OHM,1/2W,2% S	83-1520-7349	1.0
R15	0A781-7361	MINCOM SPEC	RES-FXD,FILM,2.7K OHM,1/2W,2%S	83-1520-7361	1.0
R16	0A781-7370	MINCOM SPEC	RES-FXD,FILM,9.1K OHM,1/2W,2%S	83-1520-7370	1.0
R17	0A781-7264	MINCOM SPEC	RES-FXD,FILM,910 OHM,1/2W,2% S	83-1520-7264	1.0
R18	0A781-7175	MINCOM SPEC	RES-FXD,FILM,1K OHM,1/2W,2% S	83-1520-7175	1.0
R20	0A781-7342	MINCOM SPEC	RES-FXD,FILM,82 OHM,1/2W,2% S	83-1520-7342	1.0
R21	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	1.0
R22	77PR100	BECKMAN	RES-VAR,COMP,100 OHM,3/4 W,10%	83-1520-1153	1.0
R23	0A781-7333	MINCOM SPEC	RES-FXD,FILM,33 OHM,1/2W,2% S	83-1520-7333	1.0
R24	0A781-7345	MINCOM SPEC	RES-FXD,FILM,180 OHM,1/2W,2% S	83-1520-7345	1.0
R26	77PR1K	BECKMAN	RES-VAR,COMP,1K OHM,3/4 W, 10%	83-1520-1211	1.0
R31	0A781-7372	MINCOM SPEC	RES-FXD,FILM,22K OHM,1/2W,2% S	83-1520-7372	1.0
S1	TYPE G350-PC	CONTL WIRT	SWITCH-SLIDE, DPDT,125V 3AMP	83-1550-5212	1.0
TP1,TP2	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	2.0
1	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	3.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	23059A016	A MINCOM	BRACKET-COMPONENT MTG,SIG ELEC	83-3320-1132	1.0
4	00000A734-8	B MINCOM	LABEL-IDENT,P.C. BD,*3D*	83-3550-1453	1.0
5	23059A131	MINCOM	P.C. BD-DYNATRACK,RECORD	83-3640-0672	1.0
6	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
7	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	1.0
8	MS35649-42	MIL STD	NUT-HEX,PLAIN,4-40 X .250 WD	83-9260-2003	1.0
9			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	1.0
10	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	1.0
11	1434	BIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR

TITLE P.C.BD ASSY-DYNATRACK,REPRO

CATALOG NO. 83-4930-1964

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	DESCRIPTION	PH CATALOG NO.	QTY.
C1,C6,C10	TSD4-20-226	COMP INC	CAP-FXD,TA, 22UF 20V 20%	83-1510-6203	3.0
C2	DM15F271J	ARCO	CAP-FXD,MICA, 270PF 500V 5%	83-1510-5096	1.0
C3	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C4	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C5,C9	E3XFR	MIDWEC	CAP-FXD,PLSTC, .010UF 100V 5%	83-1510-4449	2.0
C7	TYPE E3FR	MIDWEC	CAP-FXD,PLSTC,.0047UF 100V 5%	83-1510-4446	1.0
C8	DM15F621J	ARCO	CAP-FXD,MICA, 620PF 300V 5%	83-1510-5123	1.0
C11	TYPE E3FR	MIDWEC	CAP-FXD, PLS .0068UF 100V 5%	83-1510-4447	1.0
C12	E3XFR	MIDWEC	CAP-FXD,PLSTC,.033UF 100V 5%	83-1510-4452	1.0
C13	E3XFR	MIDWEC	CAP-FXD, PLSTC .047UF 100V 5%	83-1510-4453	1.0
C14	TSD2-35-225	COMP INC	CAP-FXD,TA, 2.2UF 35V 20%	83-1510-6207	1.0
C15	E3XFR	MIDWEC	CAP-FXD,PLSTC, .10UF,100V, 5%	83-1510-4456	1.0
C16	112A1C824	ELECTRO CUBE	CAP-FXD PAPER .82UF 200V 20%	83-1510-4309	1.0
C17,C18	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
DS1	NE-2	CHICAGO MIN	LAMP-GLOW, NEON	83-1550-2596	1.0
Q1,Q2,Q3,Q4,Q5,Q6,Q7,Q8,Q9, Q10	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	10.0
Q11	2N3638	FAIRCHILD	TSTR-SI,PNP, SW, 25 VCB	83-1530-2155	1.0
Q12	2N4056	GE	TSTR-2N4056, SI, HIGH VOLTAGE	83-1530-2332	1.0
R1,R5	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 1M OHM 1/2W 5%	83-9520-3220	2.0
R2,R31	0A781-7344	MINCOM SPEC	RES-FXD,FILM,120 OHM,1/2W,2% S	83-1520-7344	2.0
R3	0A781-7393	MINCOM	RES-FXD,FILM,270K OHM,1/2W,2% S	83-1520-7393	1.0
R4	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R6,R26	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	2.0
R7,R47	0A781-7389	MINCOM SPEC	RES-FXD,FILM,180K OHM,1/2W,2% S	83-1520-7389	2.0
R8	0A781-7174	MINCOM SPEC	RES-FXD,FILM,390 OHM,1/2W,2% S	83-1520-7174	1.0
R9,R17,R37	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	3.0
R10	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	1.0
R11,R12,R13,R14,R36,R39	0A781-7201	MINCOM SPEC	RES-FXD,FILM,1.8K OHM,1/2W,2% S	83-1520-7201	6.0
R15,R27	79P R5K	BECKMAN	RES-VAR,CER, 5 K OHM,3/4W,10%	83-1520-1420	2.0
R16,R29,R32,R41	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	4.0

P A R T S L I S T

PL 23059A140

REV C

TITLE P.C.BD ASSY-DYNATRACK,REPRO

CATALOG NO. 83-4930-1964

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
R18,R33	0A781-7387	MINCOM SPEC	RES-FXD,FILM,100K OHM,1/2W,2%S	83-1520-7387	2.0
R19	0A781-7383	MINCOM SPEC	RES-FXD,FILM,68K OHM,1/2W,2% S	83-1520-7383	1.0
R20	LITTLE DEVIL	OHMITE	RESISTOR-CAR, 1.5M 1/2W 5%	83-9520-3224	1.0
R21	LITTLE DEVIL	OHMITE	RES-FXD,COMP,10M OHM 1/2 W 5%	83-9520-3250	1.0
R22	0A781-7399	MINCOM SPEC	RES-FXD,FILM,470K OHM,1/2W,2%S	83-1520-7399	1.0
R23	0A781-7363	MINCOM SPEC	RES-FXD,FILM,3.9K OHM,1/2W,2%S	83-1520-7363	1.0
R24	0A781-7372	MINCOM SPEC	RES-FXD,FILM,22K OHM,1/2W,2% S	83-1520-7372	1.0
R25,R38	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2%S	83-1520-7360	2.0
R28	0A781-7391	MINCOM SPEC	RES-FXD,FILM,220K OHM,1/2W,2%S	83-1520-7391	1.0
R30	0A781-7361	MINCOM SPEC	RES-FXD,FILM,2.7K OHM,1/2W,2%S	83-1520-7361	1.0
R34	0A781-7149	MINCOM SPEC	RES-FXD,FILM,3.3K OHM,1/2W,2%S	83-1520-7149	1.0
R35	0A781-7365	MINCOM SPEC	RES-FXD,FILM,5.6K OHM,1/2W,2%S	83-1520-7365	1.0
R40	0A781-7337	MINCOM SPEC	RES-FXD,FILM,47 OHM,1/2W,2% S	83-1520-7337	1.0
R42,R43	0A781-7379	MINCOM SPEC	RES-FXD,FILM,47K OHM,1/2W,2% S	83-1520-7379	2.0
R44	0A781-7381	MINCOM SPEC	RES-FXD,FILM,56K OHM,1/2W,2% S	83-1520-7381	1.0
R45,R51	0A781-7145	MINCOM SPEC	RES-FXD,FILM,12K OHM,1/2W,2% S	83-1520-7145	2.0
R46	0A781-7353	MINCOM SPEC	RES-FXD,FILM,470 OHM,1/2W,2% S	83-1520-7353	1.0
R48	79P R1MEG	BECKMAN	RES-VAR, FILM, 1 MEG OHM	83-1520-1421	1.0
R49	79P R20K	BECKMAN	RES-VAR,FILM, 20 K OHM	83-1520-1422	1.0
R50	CK1101	RAYTHEON	RES-VAR,LIGHT ACTIVATED	83-1520-1433	1.0
R52	0A781-7142	MINCOM SPEC	RES-FXD,FILM,5.1K OHM,1/2W,2%S	83-1520-7142	1.0
S1	G128	CONT WIRT	SWITCH-SLIDE, DP3T,125 V .5AMP	83-1550-5430	1.0
S2	7101RPC	C & K COMP	SWITCH-TOGGLE, SPDT,28VDC	83-1550-5429	1.0
1	23059A141	E MINCOM	P.C.BD-DYNATRACK,REPRODUCE	83-3640-1274	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	10.0
5	100-300-4-3	ATLEE CORP	CLIP-SPG TENS,.093 MTG HOLE	83-1620-0091	1.0

P A R T S L I S T

PL 23059A140

REV C

TITLE P.C.BD ASSY-DYNATRACK,REPRO

CATALOG NO. 83-4930-1964

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO. DRAWING NUMBER MFGR NAME D E S C R I P T I O N PH CATALOG NO. QTY.

- MFGR PART NO.

6	MS35338-39	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#2	83-9261-4301	4.0
7			WASHER-FLAT,SM PATT,#2	83-9261-4011	5.0
8			NUT-HEX,SM PATT,2-56 X .156 WD	83-9260-2206	6.0
9	MS35206-202	MIL STD	SCREW-MACH,PAN HD,2-56 X 3/16	83-9260-4501	4.0
10	00000A734-9	MINCOM	LABEL-IDENT,P.C. BD *8D*	83-3550-1454	1.0

P A R T S L I S T

PL 23059A170

REV B

TITLE P.C.BD ASSY-PREAMP,NAB,REPRO

CATALOG NO. 83-4930-1940


----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1,C6	TSD4-20-226	COMP INC	CAP-FXD,TA, 22UF 20V 20%	83-1510-6203	2.0
C2	DM15F271J	ARCO	CAP-FXD,MICA, 270PF 500V 5%	83-1510-5096	1.0
C3	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C4	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C5	E3XFR	MIDWEC	CAP-FXD,PLSTC, .010UF 100V 5%	83-1510-4449	1.0
C7,C8	TYPE E3FR	MIDWEC	CAP-FXD, PLS .0068UF 100V 5%	83-1510-4447	2.0
C9,C15	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	2.0
K1	701-3	ELEC-TROL	RELAY-SPDT, 2K OHM 24VDC	83-1550-3620	1.0
K2	201-3	ELECTROL	RELAY-SPST, 2K OHM 24 V DC	83-1550-3621	1.0
Q1,Q2,Q3,Q4,Q5	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	5.0
R1,R5	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 1M OHM 1/2W 5%	83-9520-3220	2.0
R2	0A781-7344	MINCOM SPEC	RES-FXD,FILM,120 OHM,1/2W,2% S	83-1520-7344	1.0
R3	0A781-7393	MINCOM	RES-FXD,FILM,270K OHM,1/2W,2% S	83-1520-7393	1.0
R4	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R6,R25	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	2.0
R7,R18,R21	0A781-7389	MINCOM SPEC	RES-FXD,FILM,180K OHM,1/2W,2% S	83-1520-7389	3.0
R8	0A781-7174	MINCOM SPEC	RES-FXD,FILM,390 OHM,1/2W,2% S	83-1520-7174	1.0
R9	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R10	0A781-7375	MINCOM SPEC	RES-FXD,FILM,33K OHM,1/2W,2% S	83-1520-7375	1.0
R11,R12,R13,R14,R15	0A781-7201	MINCOM SPEC	RES-FXD,FILM,1.8K OHM,1/2W,2% S	83-1520-7201	5.0
R16	0A781-7147	MINCOM SPEC	RES-FXD,FILM,4.7K OHM,1/2W,2%	83-1520-7147	1.0
R17	79P R5K	BECKMAN	RES-VAR,CER, 5 K OHM,3/4W,10%	83-1520-1420	1.0
R19,R22	79P R1MEG	BECKMAN	RES-VAR, FILM, 1 MEG OHM	83-1520-1421	2.0
R20,R23	79P R20K	BECKMAN	RES-VAR,FILM, 20 K OHM	83-1520-1422	2.0
R24	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
1	23059A191	C MINCOM	P.C.BD-PREAMP, NAB, OVERDUR	83-3640-1265	1.0
2	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
3	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
4	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	5.0
5	00000A734-5	B MINCOM	LABEL-IDENT,P.C. BD,*7*	83-3550-1450	1.0

TITLE HSG-SIG ELECT,REPRO ONLY,8 TRK

CATALOG NO. 83-5920-1261

----- M A T E R I A L R E Q U I R E M E N T S -----					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
DS1	327	GENERAL ELEC	LAMP-INCANDESCENT, .04 AMP	83-1550-2506	1.0
J1	N-111	SWITCHCRAFT	JACK-TEL, 2 CONDUCTOR, INSULATED	83-1610-0885	1.0
J11, J12, J21, J22, J31, J32, J41, J42, J51, J52, J61, J62, J71, J72, J81, J82	2VK22S/1-2	VIKING	CONN-P.C., ELEC, PIERCD, 22 CON	83-1610-0845	16.0
J101, J201, J301, J401, J501, J601, J701, J801	D3M	SWITCHCRAFT	CONN-RECP, ELEC, PNL MTG, 3 PIN	83-1610-1106	8.0
J102, J202, J302, J402, J502, J602, J702, J802	MS3102E10SL-3P	MIL STD	CONN-RECPT, BOX MTG, 3 PIN CONT	83-1610-1510	8.0
M1	4140018-10	SIMPSON	METER ASSY-VU, -20 TO PLUS 3	83-1550-3094	1.0
P10	1-480276-0	AMP INC	SHELL-CONN, RECT, .665 WD X.850	83-1610-0929	1.0
R1, R2, R3, R4, R5, R6, R7, R8 R9	0A781-7350 0A781-7362	MINCOM SPEC MINCOM SPEC	RES-FXD, FILM, 330 OHM, 1/2W, 2% S RES-FXD, FILM, 3.6K OHM, 1/2W, 2% S	83-1520-7350 83-1520-7362	8.0 1.0
S1	PA-1005	CENTRALAB	SW-ROTARY, 2 SECTIONS, 2-111 POS	83-1550-5279	1.0
T1, T2, T3, T4, T5, T6, T7, T8	23059A029	A MINCOM	XMFR-AUDIO OUTPUT, SIGNAL ELECT	83-3540-1109	8.0
1	23059A211	MINCOM	PANEL-FRONT	83-3360-1053	1.0
2	23059A013-1	B MINCOM	HINGE-BUTT, DOOR LEAF, LH	83-3270-0475	1.0
3	23059A013-2	B MINCOM	HINGE-BUTT, DOOR LEAF, RH	83-3270-0476	1.0
4	23059A004	B MINCOM	SUPPORT-ROD, GUIDE, P.C. BOARD	83-3340-0389	4.0
5	23059A001-1	B MINCOM	PLATE-HSG MTG, RH, SIG ELECT	83-3320-1128	1.0
6	23059A001-2	B MINCOM	PLATE-MTG, HSG, RH, SIGNAL ELECT	83-3320-1129	1.0
7	23059A212	C MINCOM	PANEL-REAR	83-3360-1054	1.0
8	23059A006-1	D MINCOM	PLATE-PANEL MTG, LH, SIG ELECT	83-3320-1130	2.0
9	23059A014-3	B MINCOM	HINGE-BUTT, CHASSIS HALF	83-3270-0479	1.0
10	23059A027	B MINCOM	ROD-DOOR STOP, SIGNAL ELECT	83-3280-0418	1.0
11	23059A026	B MINCOM	BRACKET-SLOTTED, DOOR STOP	83-3320-1127	1.0
12	23059A028	B MINCOM	SPRING-DOOR CATCH, SIG ELECT	83-3280-0447	1.0
13	R102-125	SCANBE	SPACER-GUIDE, P.C. BD, .125 THK	83-1350-0385	8.0
14	00000A614-7	G MINCOM	SPACER-P.C. BD, CHAN, .500 LG	83-3350-0236	16.0
15	00000A614-8	G MINCOM	SPACER-P.C. BD, CHAN, .562 LG	83-3350-0237	32.0
16	00000A614-9	G MINCOM	SPACER-P.C. BD, CHAN, .625 LG	83-3350-0238	16.0
17	00000A754-1	MINCOM	SPACER-CARD GUIDE, 2.937 LG	83-3350-0529	4.0
18	23059A213	D MINCOM	PANEL-FRONT, COMPONENT MTG	83-3360-1055	1.0
19	7036	WALSCO	GROMMET-PLST, .375 ID X .625 OD	83-9630-0007	1.0
20	60511-4-LP	AMP INC	CONTACT-ELEC, PIN, .084 DIA	83-1610-0925	4.0



TOLERANCES		BLOCK
PART NO.	CATALOG NO.	QUANTITY
23059A210-1	83-5920-1289	4 TRACKS
23059A210-2	83-5920-1281	8 TRACKS AS SHOWN

DRAWING NO. 23059A210

Figure 51. Reproduce Signal Electronics Housing

P A R T S L I S T

PL 23059A210-2

REV D

TITLE HSG-SIG ELECT,REPRO ONLY,8 TRK

CATALOG NO. 83-5920-1261

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF.	DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
21		DS70-3-2	RAYTHEON	KNOB-CONTROL,RD,SKIRTED	83-1270-0487	1.0
22		R-301-51A	SCANBE	GUIDE-P.C. BD,5.287 LG	83-1340-0393	32.0
23		23059A214	MINCOM	LABEL-I.D,DYNATRACK & NAB	83-3550-1582	2.0
24		MS35190-222	MIL STD	SCREW-MACH,FH,4-40 X 5/16	83-9260-6503	16.0
25				SCR-MACH,F HD,8-32 X .500 LG	83-9260-6610	8.0
26		MS35206-214	MIL STD	SCREW-MACH,PAN HD,4-40 X 5/16	83-9260-4514	32.0
27		MS35206-228	MIL STD	SCREW-MACH,PAN HD,6-32 X 3/8	83-9260-4531	4.0
28				WASHER-FLAT,.219 OD X .125 ID	83-9261-4012	80.0
29				WASHER-FLAT,SM PATT,#6	83-9261-4013	48.0
30		MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	80.0
31		MS35338-41	MIL STD	WASHER-LOCK,SPLIT, #6	83-9261-4305	38.0
32				NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	48.0
33				NUT-HEX,SM PATT,6-32 X .250 WD	83-9260-2202	40.0
34		RDL-A1F1-0000	TSTR ELECT	LIGHT-INDICATOR,P2STC,RED	83-1550-2582	1.0
35		00000A769	C MINCOM	LABEL-IDENTIFICATION,MODULE	83-3550-1621	1.0
36		6050-AC	G.C. ELECT	NUT-HEX,PLAIN,3/8-32 X .563 WD	83-9262-0073	1.0
37		RA853	THOMS & BETS	TERM-LUG, INSUL,R TG,.26WD	83-9630-0203	1.0
38		091-0024-000	VIKING	INSERT-POLARIZING,CONN,.300 LG	83-1610-0760	12.0
39		MS35206-216	MIL STD	SCREW-MACH,PAN HD,4-40 X 7/16	83-9260-4516	32.0
40		MS35206-227	MIL STD	SCREW-MACH,PAN HD,6-32 X 5/16	83-9260-4530	8.0
41		YEC 120	BURNDY	FERRULE-RF CABLE GND,.300 OD	83-9690-0240	16.0
42			NATIONAL	WIRE,PVC,SHIELDED 24GA 2COND	83-7910-0511	AR
43			NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
44		TFT-200/22	ALPHA WIRE	TUBING-TEFLON,#22,.027 ID,NAT	83-7910-0388	AR
45		1434	BIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR
46		1418	BIRNBACH	WIRE-BUS BAR, 18 GA, .040 OD	83-7910-0560	AR
47			NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0052	AR
48			NATL WIRE	WIRE-TYPE B,22GA WHT NYLON JKT	83-7910-0043	AR
49			NATL WIRE	WIRE-TYPE B,22GA BLK NYLON JKT	83-7910-0045	AR
50			NATL WIRE	WIRE-TYPE B,22 GA ORNG NYL JKT	83-7910-0250	AR
51				WIRE-TYPE B,22 GA ORN NYLN JKT	83-7910-0303	AR
52			NATL WIRE	WIRE-TYPE B,22GA ORN/BLK NYLN	83-7910-0297	AR
53			NATL WIRE	WIRE-TYPE B,22GA RED NYLON JKT	83-7910-0249	AR
54				WIRE-TYPE B,22 GA RED NYLN JKT	83-7910-0264	AR
55			SURPRENANT	WIRE-PVC TYPE B, 22 GA,RED-BLK	83-7910-0066	AR
56			NATL WIRE	WIRE-PVC,TYPE B, 22GA YELLOW	83-7910-0040	AR
57				WIRE-TYPE B,22 GA YELLOW NYLN	83-7910-0259	AR
58			SURPRENANT	WIRE-PVC,B NYLON,22GA,YEL-BLK	83-7910-0067	AR
59			NATL WIRE	WIRE-TYPE B,22GA,BRN NYLN JKT	83-7910-0251	AR
60				WIRE-TYPE B,22GA BRN NYLN JKT	83-7910-0301	AR
61			NATL WIRE	WIRE-PVC,B NYLON,22GA,BRN-BLK	83-7910-0300	AR
62			NATL WIRE	WIRE-TYPE B,22GA BLU NYLON JKT	83-7910-0044	AR

P A R T S L I S T

PL 23059A210-2

REV D

TITLE HSG-SIG ELECT,REPRO ONLY,8 TRK

CATALOG NO. 83-5920-1261

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
63			WIRE-TYPE B,22 GA BLU NYLN JKT	83-7910-0288	AR
64		SURPRENANT	WIRE-PVC,B NYLON,22GA,BLU-BLK	83-7910-0070	AR
65		NATL WIRE	WIRE-PVC, TYPE B, 22GA GRAY	83-7910-0042	AR
66			WIRE TYPE B,22 GA GRAY NYLN	83-7910-0261	AR
67		NATL WIRE	WIRE-TYPE B,22GA GRY/BLK NYLN	83-7910-0298	AR
68		NATL WIRE	WIRE-TYPE B,22GA,GRN NYLN JKT	83-7910-0248	AR
69		NATL WIRE	WIRE-PVC TYPE B, 22 GA,GRN-WHT	83-7910-0260	AR
70		SURPRENANT	WIRE-PVC,B NYLON,22GA,GRN-BLK	83-7910-0069	AR
71		NATL WIRE	WIRE-TYPE B,22GA VIO NYLON JKT	83-7910-0041	AR
72			WIRE-TYPE B,22 GA,VIOLET-WHITE	83-7910-0068	AR
73		NATL WIRE	WIRE-TYPE B,22GA PR/BLK NYLN	83-7910-0299	AR

P A R T S L I S T

PL 23059A330

REV B

TITLE P.C. BD ASSY-FILM SYNC,RECORD

CATALOG NO. 83-4930-1711

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFGR PART NO.	MFGR NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C9	TSD3-15-226	COMP INC	CAP-FXD,TA, 22UF 15V 20%	83-1510-6257	1.0
C13	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	1.0
C14	TSD5-20-476	COMP INC	CAP-FXD,TA, 47UF 20V 20%	83-1510-6199	1.0
C18	WMF1S47	CORNL-DUBLR	CAP-FXD,PLSTC,.047UF 100V 10%	83-1510-4481	1.0
C19	4610	ARCO	CAP-VAR,MICA,190-900 PF	83-1510-6252	1.0
L2	70F333AI	J.W. MILLER	CHOKERF,3.3 MH 5 %	83-1540-0410	1.0
Q4	2N3391A	GENERAL ELEC	TSTR-SI,NPN, PWR, 25 VCB	83-1530-2230	1.0
Q5	2N3405	G.E.	TSTR-SI,NPN,GEN PUR,50VCE	83-1530-2232	1.0
R4,R32	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	2.0
R16	0A781-7369	MINCOM SPEC	RES-FXD,FILM,8.2K OHM,1/2W,2% S	83-1520-7369	1.0
R17	0A781-7264	MINCOM SPEC	RES-FXD,FILM,910 OHM,1/2W,2% S	83-1520-7264	1.0
R19	0A781-7359	MINCOM SPEC	RES-FXD,FILM,1.2K OHM,1/2W,2% S	83-1520-7359	1.0
R20	0A781-7342	MINCOM SPEC	RES-FXD,FILM,82 OHM,1/2W,2% S	83-1520-7342	1.0
R23	0A781-7333	MINCOM SPEC	RES-FXD,FILM,33 OHM,1/2W,2% S	83-1520-7333	1.0
R24	0A781-7345	MINCOM SPEC	RES-FXD,FILM,180 OHM,1/2W,2% S	83-1520-7345	1.0
R25	0A781-7379	MINCOM SPEC	RES-FXD,FILM,47K OHM,1/2W,2% S	83-1520-7379	1.0
R26	77PR1K	BECKMAN	RES-VAR,COMP,1K OHM,3/4 W, 10%	83-1520-1211	1.0
R27	0A781-7331	MINCOM SPEC	RES-FXD,FILM,27 OHM,1/2W,2% S	83-1520-7331	1.0
T1	SS0-7	U.T.C.	XMFR-TSTR SPLY,INPUT,20K OHM	83-1540-1199	1.0
TP1,TP2	3-582118-9	AMP INC	JACK-TIP,.156 WD X .460 DP	83-1610-0752	2.0
1	SS0-CH	U.T.C.	BRACKET-XMFR MTG, U TYPE	83-1320-1663	1.0
2	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	1.0
3	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. BD,1.50 LG	83-3270-0371	1.0
4	23059A016	A MINCOM	BRACKET-COMPONENT MTG,SIG FLEC	83-3320-1132	1.0
5	00000A734-20	MINCOM	LABEL-IDENT, P.C. BD, *3S*	83-3550-1591	1.0
6	23059A331	B MINCOM	P.C.BD-FILM, SYNC, RECORD	83-3640-1220	1.0
7	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
8	1434	BIRNBACH	WIRE-BUS,22GA ROUND	83-7910-0105	AR
9	MS35206-215	MIL STD	SCREW-MACH,PAN HD,4-40 X 3/8	83-9260-4515	1.0
10	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
11			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	3.0
12	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	3.0
13			NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	3.0

TITLE P.C. BD ASSY-FILM SYNC,REPRO

CATALOG NO. 83-4930-1712

M A T E R I A L R E Q U I R E M E N T S

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
C1,C10,C12	TSD5-35-156	COMP INC	CAP-FXD, TA, 15UF 35V 20%	83-1510-6209	3.0
C2,C9	TSD5-20-476	COMP INC	CAP-FXD,TA, 47UF 20V 20%	83-1510-6199	2.0
C3	TYPE E3FR	MIDWEC	CAP-FXD, PLS .0068UF 100V 5%	83-1510-4447	1.0
C4	DM15F271J	ARCO	CAP-FXD,MICA, 270PF 500V 5%	83-1510-5096	1.0
C5	TSD5-6-227	COMP INC	CAP-FXD,TA, 220UF 6V 20%	83-1510-6259	1.0
C6	TSD-1-20-225	COMP INC	CAP-FXD,TA, 2.2UF 20V 20%	83-1510-6240	1.0
C7	DM15F501J	ARCO	CAP-FXD,MICA, 500PF 500V 5%	83-1510-5120	1.0
C8	112A1B334J	ELECTRO CURE	CAP-FXD,PAPER, .33UF 100V 5%	83-1510-4301	1.0
C11	TSD5-20-686	COMP INC	CAP-FXD,TA, 68UF 20V 20%	83-1510-6211	1.0
C13	DM19F102J	ARCO	CAP-FXD,MICA, 1000PF 500V 5%	83-1510-5041	1.0
C14	E3XFR	MIDWEC	CAP-FXD,PLSTC, .068UF 100 V 5%	83-1510-4454	1.0
C15	E3XF	MIDWEC	CAP-FXD,PLSTC, .22 UF 100V 5%	83-1510-4436	1.0
CR1,CR2	1N270	HUGHES	DIODE-GE,GEN PUR,100PIV, 60 MA	83-1530-0263	2.0
K1	201-3	ELECTROL	RELAY-SPST, 2K OHM 24 V DC	83-1550-3621	1.0
L1	70F333AI	J.W. MILLER	CHUKE-RF,3.3 MH 5 %	83-1540-0410	1.0
Q1,Q2,Q3,Q4,Q5,Q6	2N3391A	GENERAL ELEC	TSTR-SI,MPN, PWR, 25 VCB	83-1530-2230	6.0
R1	LITTLE DEVIL	OHMITE	RES-FXD,COMP, 1W OHM 1/2W 5%	83-9520-3220	1.0
R2	0A781-7399	MINCOM SPEC	RES-FXD,FILM,470K OHM,1/2W,2% S	83-1520-7399	1.0
R3,R7	0A781-7148	MINCOM SPEC	RES-FXD,FILM,10K OHM,1/2W,2% S	83-1520-7148	2.0
R4	0A781-7350	MINCOM SPEC	RES-FXD,FILM,330 OHM,1/2W,2% S	83-1520-7350	1.0
R5,R10,R23	0A781-7388	MINCOM SPEC	RES-FXD,FILM,120K OHM,1/2W,2% S	83-1520-7388	3.0
R6,R12,R17	0A781-7175	MINCOM SPEC	RES-FXD,FILM,1K OHM,1/2W,2% S	83-1520-7175	3.0
R8	3068P-1-203	BOURNS	RES-VAR,COMP, 20K OHM .2W 20%	83-1520-1166	1.0
R9	0A781-7217	MINCOM SPEC	RES-FXD,FILM,680 OHM,1/2W,2% S	83-1520-7218	1.0
R11	0A781-7383	MINCOM SPEC	RES-FXD,FILM,68K OHM,1/2W,2% S	83-1520-7383	1.0
R13	0A781-7348	MINCOM SPEC	RES-FXD,FILM,270 OHM,1/2W,2% S	83-1520-7348	1.0
R14	0A781-7357	MINCOM SPEC	RES-FXD,FILM,750 OHM,1/2W,2% S	83-1520-7357	1.0
R15,R21	0A781-7373	MINCOM SPEC	RES-FXD,FILM,27K OHM,1/2W,2% S	83-1520-7373	2.0
R16	0A781-7221	MINCOM SPEC	RES-FXD,FILM,100 OHM,1/2W,2% S	83-1520-7221	1.0
R18	0A781-7358	MINCOM SPEC	RES-FXD,FILM,820 OHM,1/2W,2% S	83-1520-7358	1.0
R19	0A781-7367	MINCOM SPEC	RES-FXD,FILM,6.8K OHM,1/2W,2% S	83-1520-7367	1.0
R20	3067P-1-502	BOURNS	RES-VAR, WW, 5K OHM 1/2W 10%	83-1520-1319	1.0
R22	0A781-7360	MINCOM SPEC	RES-FXD,FILM,2.2K OHM,1/2W,2% S	83-1520-7360	1.0
T1	SS0-11	U.T.C.	XFR-TSTR SPLY,OUTPUT,500 OHM	83-1540-1200	1.0
1	23059A391	B MINCOM	P.C.BD-FILM SYNC, REPRODUCE	83-3640-1174	1.0
2	SS0-CH	U.T.C.	BRACKET-XFR MTC, U TYPE	83-1320-1663	1.0

P A R T S L I S T

PL 23059A390

REV B

TITLE P.C. RD ASSY-FILM SYNC,REPRO

CATALOG NO. 83-4930-1712

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
3	MS35206-213	MIL STD	SCREW-MACH,PAN HD,4-40 X 1/4	83-9260-4513	2.0
4			WASHER-FLAT,GENERAL PURPOSE #4	83-9261-4002	2.0
5	MS35338-40	MIL STD	WASHER-LOCK,SPLIT,HELICAL,#4	83-9261-4303	2.0
6			NUT-HEX,SM PATT,4-40 X .188 WD	83-9260-2201	2.0
7	00000A667	B MINCOM	HANDLE-EJECTOR,P.C. RD,1.50 LG	83-3270-0371	1.0
8	79-022-094-0250	ESNA	PIN-SPRING, .094 DIA X .250 LG	83-7280-0270	1.0
9	00000A734-21	MINCOM	LABEL-IDENT, P.C. RD, *9S*	83-3550-1592	1.0
10	7717-2	THERMALLOY	PAD-TSTR, INLINE, 3 LEADS	83-9690-0191	6.0

TITLE KIT-P.C.BD,NAB TO DYNATRACK

CATALOG NO. 83-5990-0425

- - - - - M A T E R I A L R E Q U I R E M E N T S - - - - -					
REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23059A080	MINCOM	P.C. BD ASSY-CONVERSN,NAB REP	83-4930-1122	1.0
2	23059A130	E MINCOM	P.C. BD ASSY-DYNATRACK,RECORD	83-4930-1006	1.0
3	23059A140	C MINCOM	P.C.BD ASSY-DYNATRACK,REPRO	83-4930-1964	1.0

P A R T S L I S T

PL 23059A950

REV P

TITLE KIT-FILM SYNC, SIG ELEC

CATALOG NO. 83-5990-0541

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23059A310	D MINCOM	HOUSING ASSY-AUDIO & FILM SYNC	83-5920-1320	1.0
2	23000A310	A MINCOM	CABLE ASSY-HEAD, FILM SYNC	83-4570-0465	1.0
3	23028A350	A MINCOM	CABLE ASSY-PWR, FILM SYNC	83-4570-0466	1.0
4	23059A020	F MINCOM	P.C. BD ASSY-BIAS, ERASE	83-4930-1121	1.0
5	23059A030	D MINCOM	P.C. BD ASSY-NAB ERASE COUPLER	83-4930-1117	1.0
6	23059A330	B MINCOM	P.C. BD ASSY-FILM SYNC, RECORD	83-4930-1711	1.0
7	23059B040	F MINCOM	P.C. BD ASSY-RECORD, NAB	83-4930-1214	1.0
8	23059A050	B MINCOM	PWR SUP ASSY-SIG ELECT, W/METER	83-5920-0822	1.0
9	23059A060	G MINCOM	P.C. BD ASSY-LME AMP, SIG ELECT	83-4930-1091	1.0
10	23059A170	B MINCOM	P.C. BD ASSY-PREAMP, NAB, REPRO	83-4930-1940	1.0
11	23059A390	B MINCOM	P.C. BD ASSY-FILM SYNC, REPRO	83-4930-1712	1.0
12	1-480276-0	AMP INC	SHELL-CONN, RECT, .665 WD X.850	83-1610-0929	1.0
13	60511-4-LP	AMP INC	CONTACT-ELEC, PIN, .084 DIA	83-1610-0925	9.0
14	1-480304-0	AMP INC	SHELL-CONN, RECT, 3 POSITION	83-1610-1137	1.0
15	60510-4	AMP INC	CONTACT-ELEC, SOC, 18-22GA SIZE	83-1610-0927	3.0
16	201359-3	AMP INC	SHELL-CONN, RECT, 26 POSITIONS	83-1610-0674	1.0
17	42980-1-LP	4 AMP INC	PIN-CONTACT, COMM, 20-24 GA WIRE	83-1610-0688	15.0
18	201923-1	AMP INC	CLIP-SPRING TENSION, MALE	83-1620-0126	1.0
19	201229-1	AMP INC	CLAMP-ELEC, STRAIN REL, .779 MCE	83-1650-0244	1.0
20	200390-4	AMP INC	RECP-GUIDE PIN, CENTER, SERIES M	83-7270-0302	1.0
21	200389-4	AMP INC	PIN-GUIDE, CENTER, AMP SERIES M	83-7280-0196	1.0
22	1-480305-0	AMP INC	SHELL-CONN, RECT, 3 POS	83-1610-1142	1.0

P A R T S L I S T

PL 23059A960-2


REV R

TITLE KIT-NAB REPRO,SIG ELEC, 8 TRK

CATALOG NO. 83-5990-0567

----- M A T E R I A L R E Q U I R E M E N T S -----

REF. DES. OR FIND NO.	DRAWING NUMBER - MFG PART NO.	MFG NAME	D E S C R I P T I O N	PH CATALOG NO.	QTY.
1	23059A210-2	D MINCOM	HSG-SIG ELECT,REPRO ONLY,8 TRK	83-5920-1261	1.0
2	23059A060	G MINCOM	P.C. BD ASSY-LNE AMP,SIG ELECT	83-4930-1091	8.0
3	23059A170	B MINCOM	P.C.BD ASSY-PREAMP,NAB,REPRO	83-4930-1940	8.0
4	BX28N2.5-2	ACDC ELECTS	POWER SUPPLY-28VOLTS 2.5 AMPS	83-1930-1672	1.0
5	23000A030-2	MINCOM	CABLE ASSY-HD,REPRODUCE,8 TRK	83-4570-0390	1.0
6	23028A250	A MINCOM	CABLE ASSY-POWER,REPRODUCER	83-4570-0420	1.0



"...three generations ahead of its time"

3M BRAND PROFESSIONAL TAPE RECORDER

The 3M Brand Professional Tape Recorder you now own is the finest quality recording instrument available. It has been engineered to the world's most exacting standards for performance and reliability.

Your 3M Brand Professional Tape Recorder was tested at our factory, by electronic measuring equip-

ment, prior to shipment. It met or surpassed every current specification. Therefore, it should operate with maximum performance and without trouble. If difficulties are encountered, however, the following warranty will be of value to you.

WARRANTY

The 3M Company warrants to the original purchaser that the 3M Professional Tape Recorder, or its "Dynatrack", or its electronic NAB system, or its "Isoloop" tape transport, or its magnetic heads* (if any of these components are purchased separately) is/are free of defects of material and/or workman-

ship for a period of one year from date of delivery to the original purchaser.

3M Company agrees to either replace or repair defective parts subject to the following provisions:

*This warranty shall not constitute any guarantee as to the duration of the life expectancy of magnetic heads, since that is affected by many variables depending upon use, speed, tape, and other factors.

CONDITIONS OF PARTS WARRANTY

The obligation of 3M under this warranty is limited to remedying any such defect by repairing or replacing defective parts. For the first ninety (90) days after delivery to the original purchaser, defects in materials and workmanship covered by this warranty will be remedied at no cost for labor or material to the

original purchaser. During the balance of the first year after delivery to the original purchaser, repairs or replacement of defective parts will be made at no charge for material, but a reasonable charge for labor will be made to the original purchaser.

CONDITIONS OF WARRANTY

- A. The attached warranty registration card must be completed and mailed to 3M at the address printed thereon, within ten (10) days from date of delivery of the equipment to original purchaser.
- B. All defects must be reported within the warranty period to 3M, who will make warranty repairs found to be required either at the place of business of the purchaser or at the 3M factory to which any defective equipment shall be returned, transportation prepaid by the purchaser. Equipment shall not be returned to 3M without 3M's prior instructions to do so.
- C. Purchaser shall not have used, or allowed to have been used in the equipment, any parts (except accessory items such as transistors, magnetic heads, tape, etc.) not supplied by 3M Company, nor shall this warranty cover damages to the 3M equipment, resulting from the incorporation of

other than original systems compatible components or accessories.

- D. The equipment must not have been altered or modified without the express approval of 3M; nor subjected to misuse, negligence or accident. Serial numbers must not have been altered, defaced or removed.

This warranty is made in lieu of all other warranties, expressed or implied, and 3M's only obligation shall be to repair or replace defective parts as provided in the warranty. 3M shall not otherwise be liable for any injury, loss or damage, direct or consequential, arising out of the use or the inability to use the equipment. Before using, purchaser shall determine the suitability of the equipment for his intended use and assumes all risks and liability whatsoever in connection therewith. The foregoing may not be changed except by an agreement signed by an officer of seller.

Mincom Division **3M**
COMPANY
3M CENTER • ST. PAUL, MINNESOTA 55101

3M BRAND PROFESSIONAL TAPE RECORDER WARRANTY REGISTRATION

Model

Serial Number

Date

I hereby submit for validation this Warranty Registration Certificate for the 3M Brand Professional Tape Recorder identified above. I understand that the One Year Warranty accompanying this Certificate constitutes the sole warranty on this product, and that it is subject to the terms enumerated on said warranty, which I have read and agree to.

Which categories below best describe your recording application(s)?


- | | | |
|--|---|--|
| <input type="checkbox"/> Broadcast | <input type="checkbox"/> Recording Studio | <input type="checkbox"/> Medical |
| <input type="checkbox"/> Film Producer | <input type="checkbox"/> Government | <input type="checkbox"/> Industrial |
| <input type="checkbox"/> Duplicator | <input type="checkbox"/> Education | <input type="checkbox"/> Instrumentation |
| <input type="checkbox"/> Other: _____ | | |

Name

CITY

STATE

ZIP



3M COMPANY

Mincom Division

300 S. Lewis Road

Camarillo, California 93010

ATTN: MINCOM WARRANTY VALIDATION

This 3M M23 manual
was
"scanned by the klettster"
as a GIFT*

to those who have these machines
and want to keep them operational

The 3M M23 was the first 3M iso-loop
tape recorder for professional use

3M M23 machines were around 45 years
old at the time this scan was made

enjoy this...
keep the reels turning

*if some opportunist charges you money for this pdf he's making money from no investment other than his time, trolling around on the interweb finding this and other docs, downloading and flipping multiple copies for cash - like a money machine... whereas the klettster has several hours and \$36 in costs (for scanning the larger pages) invested in to this... and is asking nothing... other than that you use and enjoy... maybe I am the idiot and the trolling pdf reseller is the genius...

I'll leave that for others to debate.